


HISTORY


PHOTOGRAPHY




3 1761 03563 1118

THE HISTORY OF PHOTOGRAPHY







PERKEN, SON & RAYMENT,

Manufacturing Opticians,

99, HATTON GARDEN, LONDON, E.C.

"OPTIMUS" PHOTOGRAPHIC LENSES.



Euryscopes, F/6.
Rapid Rectilinear, F/8. Quick-acting Portrait, F/4.
Portable Symmetrical, F/16. Rapid Landscape, F/11.

Euryscope Extra large Diameter (Double).—The aperture is F/6. The Lenses are of special optical glass, constructed with the nicest precision of curvatures, so maintaining good marginal definition, coupled with the most extreme rapidity.

To cover—5×4	7×5	9×7	10×8
68/-	94/6	126/-	220/-

Rapid Rectilinear (Double).—Second only to the above for Rapidity, therefore well suited for instantaneous effects, out-door groups and views, as well as interiors. Copying and enlarging are also within the capabilities of the Lens; in fact, its work may be styled "UNIVERSAL."


To cover 5/4	6/5	7/5	8/5	9/7	10/8	12/10	15/12	18/16
33/-	45/-	49/6	64/-	82/6	127/6	142/6	180/-	225/-

Portable Symmetrical (Double). with revolving diaphragms.—Specially adapted for Architecture: being of short focus and wide angular aperture, can be used to advantage when very close to the subject. It is also useful for landscapes as well as copying. The smaller sizes give



beautiful Lantern Slides, the definition being exceptionally crisp.

To cover—5/4	7/5	9/7	10/8	12/10	15/12	18/16	plates.
39/-	52/6	82/6	127/6	142/6	180/-	225/-	



Portrait Lens.—Specially constructed as quick-acting for short exposure in portraiture. They are second to none, the definition being maintained by their perfect optical qualities.

Diam.	2 in.	2½ in.	3½ in.
Price.	90/-	120/-	180/-
	1 B.	2 B.	3 B.

Larger sizes to order.

Portrait Lenses of good Quality.

To cover—	1/4	1/2	1/1	10/8	12/10	plates.
	27/9	60/-	135/-	270/-	375/-	

Larger sizes to order.

"We now turn to the 'OPTIMUS RAPID EURYSCOPE,' with its full aperture of 1½ in. (its equivalent focus being 11 in.) it defines with EXTREME BRILLIANCY, and when used with a stop it easily covers a 10×8 plate to the corners, which is larger than that engraved on the mount as its possibility. Working as it does with such a LARGE APERTURE (F/6 approx.) it serves as a portrait and group Lens, as well as a landscape and copying objective. There is no doubt of its proving a most USEFUL LENS."
—J. TRAILL TAYLOR, *British Journal of Photography*, August 12th, 1887.

"We are pleased to say the 'OPTIMUS' LENS submitted to us by Perken, Son and Rayment is really an EXCELLENT INSTRUMENT, giving FLATNESS OF FIELD, and GOOD MARGINAL DEFINITION. We have placed the instrument among those set aside for use."—*Photographic News*, May 27th, 1887.

"PORTRAIT LENS. — The 'OPTIMUS' LENSES are MODERATE in PRICE, and yield most EXCELLENT results."—*Amateur Photographer*, December 8rd, 1886.

THE TRADE AND SHIPPERS ONLY SUPPLIED. DISCOUNT LIST ON APPLICATION.



PERCY LUND AND CO.

Beg to offer the services of their extensive establishment to Photographic Material Manufacturers and Dealers requiring any kind of letterpress printing. They are specially prepared to undertake

Scientific and Technical Work,

and will spare no trouble to give every satisfaction. For bookwork, publications, catalogues, price lists, and high-class circulars their price and style is unequalled. They can point with pleasure to catalogues produced by them for many leading firms in the British Isles and abroad. Their work has also been most favourably reviewed by the Press.

QUOTATIONS GIVEN.

THE COUNTRY PRESS, BRADFORD.

A HISTORY
OF
PHOTOGRAPHY.

PERCY LUND AND CO.,
THE COUNTRY PRESS,
BRADFORD.

PERCY LUND & CO.

MANUFACTURERS OF ALL KINDS OF
Photographic Materials
and Apparatus,
WHOLESALE & RETAIL.

COMPLETE CATALOGUE Post-free 6d.

The Amateur's First Handbook of Photography.

A Complete Guide and Instructor in | *FOURTH EDITION.*
 the Art of Modern Photography. | *ONE SHILLING.*


"A lucid and practical little treatise."—*Manchester News.*

"The directions are full and complete."—*English Mechanic.*

This excellent little manual should be in the hands of all who are taking up Photography. It has been most favourably reviewed by the Press—and many private persons write praising it.

Photographic Labels.

A book containing over 100 printed gumméd labels for all photographic chemicals and requisites. For the articles that are in most common use, four or five labels are provided, while for the others one or two suffice. A number of blank labels are added, as well as a page of small perforated squares for numbering negatives. Price 6d.



Negative Bags.

For the systematic storing of Negatives. A really cheap line. Used in the leading studios of Great Britain and Colonies.

	s.	d.
Quarter plate	3	8 per 1000
Half plate	4	8 "
Whole plate	6	8 "
10 by 8	8	8 "
12 " 10	12	8 "
15 " 12	14	8 "

The Premier Waxed Vignettters.

Print almost as quickly as the bare negative, and have a softening effect on the retouching. Produce the same softness and delicacy of effect in the strongest summer sunshine or in the shade of a winter's day. They are durable, and if damaged by creases or thumb-nail marks can be restored by simply warming, without re-waxing. Assorted shapes and sizes, for portrait and landscape.

	s.	d.		s.	d.		s.	d.
Carte-de-Visite ..	0	8	1/1	1	0	12 by 10 ..	2	0
Cabinet	0	6	10 by 8	1	6	15 " 12 ..	4	0

These goods can be obtained from any dealer in photographic materials or direct from

PERCY LUND & CO.,
ST. JOHN'S ST., BRADFORD.

PERCY LUND & CO.

The "Professional" Registered Single and Double Printing Cloud Negatives.

WAXED PAPER OR GLASS.

This series of negatives is really a new departure in the printing of clouds.

We claim that this is the only perfect series ever produced, and believe that this claim will be admitted by everyone who uses the "PROFESSIONAL" Clouds.

The special and distinguishing feature of the "PROFESSIONAL" Negatives is that with them the landscape and clouds can be printed at the same time, excepting in cases where the sky of the landscape is very dense. If the sky is too dense to print through, double printing may be resorted to; and the "PROFESSIONAL" clouds are more suitable for this purpose than any series hitherto offered.

There is an immense variety of studies, all taken from nature, so that it is almost impossible to imagine a Building, Landscape, or Sea-view for which we have not some suitable cloud. The "PROFESSIONAL" clouds are equally adapted for Silver, Carbon, Platinotype, Bromide, or any other process.

The waxed series is treated with a real wax, which is perfectly dry in working, and cannot grease the print. The wax will never go spotty; and if it should be creased or rubbed by careless usage, the negative can be perfectly restored by warming and hanging up to dry, *without* re-waxing.

Each side of the negative can be printed from, so that one study does the work of two.

PRICES.

	s. d.		s. d.		s. d.		s. d.		
Waxed Paper	0 8	Size $\frac{1}{2}$ plate.	Glass	1 0	Waxed Paper	3 0	Size 12 by 10	Glass	5 0
"	1 0	" $\frac{3}{4}$ "	"	2 0	"	4 0	" 15 " 12		
"	1 6	" $1\frac{1}{2}$ "	"	3 0	"	8 0	" 21 " 17		
"	2 0	" 10 by 8	"	4 0					

"Snowdrift" Opals.

The "Snowdrift" Opals print out by contact, and are toned and fixed exactly as ordinary albumenized paper. The exquisite beauty of the resulting prints, and the great variety of warm tone obtainable, have already caused the "Snowdrifts" to be great favourites with the professional photographers. The "Snowdrift" Opals are *not* made from the same formula as any other opal at present in the market, and we believe that they are fully equal, if not superior, to all others.

These plates will keep safely for three months, and in a favourable storing place for much longer. Even when they have taken a decided yellow stain from careless exposure, they will generally clear in the toning.

On finely ground pot opal.

	3 in box.	6 in box.	12 in box.
	s. d.	£ s. d.	£ s. d.
$4\frac{1}{2}$ by $3\frac{1}{2}$...	0 3 0	0 5 0	
$6\frac{1}{2}$ " $4\frac{1}{2}$..	0 5 0	0 9 0	
$8\frac{1}{2}$ " $6\frac{1}{2}$..	0 8 3	0 15 9	
12 " $7\frac{1}{2}$..	8 0	0 14 9	1 8 3
12 " 10 ..	8 9	0 15 9	1 9 3
15 " 12 ..	12 9	1 4 0	2 4 9

On best egg-shell flashed opal.

	3 in box.	6 in box.	12 in box.
	s. d.	£ s. d.	£ s. d.
$4\frac{1}{2}$ by $3\frac{1}{2}$..	0 3 9	0 6 6	
$6\frac{1}{2}$ " $4\frac{1}{2}$..	0 7 6	0 13 3	
$8\frac{1}{2}$ " $6\frac{1}{2}$..	0 11 0	1 0 0	
12 " $7\frac{1}{2}$..	11 0	0 19 9	1 16 6
12 " 10 ..	12 3	1 3 6	2 0 6
15 " 12 ..	18 3	1 13 6	3 0 9

Extra charge for bevelled edges;— $4\frac{1}{2}$ by $3\frac{1}{2}$, 1/6; $6\frac{1}{2}$ by $4\frac{1}{2}$, 3/-; $8\frac{1}{2}$ by $6\frac{1}{2}$, 4/- per doz.

Mr. F. J. Gregory, *The Gables Studio, Reigate*, writes:—"I think these opals are the best I have seen of the kind, and beat Bromide all hollow."

Messrs. J. D. Cowell & Co., *Common Garden Street, Lancaster*, write:—"We are delighted with the Snowdrift Opals you sent us."

These goods can be obtained from any dealer in photographic materials or direct from

PERCY LUND & CO.,
ST. JOHN'S ST., BRADFORD.



JOSEPH NICÉPHORE NIEPCE.

1765—1833.


From a Photograph of the Statue at Chalons.

A
HISTORY
OF
PHOTOGRAPHY

WRITTEN AS
A PRACTICAL GUIDE AND AN INTRODUCTION
TO ITS LATEST DEVELOPMENTS.

BY
W. JEROME HARRISON, F.G.S.

WITH
AN APPENDIX BY DR. MADDOX ON THE DISCOVERY OF
THE GELATINO-BROMIDE PROCESS



. 90071
13/8/08.

BRADFORD:
PERCY LUND & CO., THE COUNTRY PRESS.

LONDON:
TRUBNER & CO., LUDGATE HILL.

1888.

TR

15

H37

TRY

Professional Cloth Backgrounds.
Professional Cloud Negatives.
Professional Mountant.
Professional Negative Bags.
Professional Print Knives.
Professional Waxed Vignettters.
Snowdrift Chloride Opals.

OF ALL DEALERS AND CHEMISTS.

Wholesale from

PERCY LUND & CO., BRADFORD.

PROCESS ENGRAVING.

MEISENBACH.

THE **Meisenbach Improved Process of Engraving** Blocks from Photographs, Paintings, &c., is now adopted by all the leading Art Publications and Illustrated Papers of the day.

SPECIMENS POST-FREE.


MEISENBACH COMPANY, Ltd.,
WEST NORWOOD, LONDON.

PERKEN, SON & RAYMENT,

Manufacturing Opticians,

99, HATTON GARDEN, LONDON, E.C.

RAYMENT'S CAMERA (EXTRA LONG FOCUS).



"I should strongly recommend RAYMENT'S Camera. It is LIGHT, COMPACT very RIGID, and extends to about double the usual focus."—*Amateur Photographer*, August 5th, 1887.

"The 'RAYMENT' Camera, in particular, claims attention, both for its BEAUTY of WORKMANSHIP and for the EASE and READINESS with which it can be put into action."—*The Camera*, Dec. 1st, 1886.


It can be set up almost instantaneously, has no loose parts, and includes all motions, and has reversing back arranged so that oblong dark slides give either horizontal or vertical pictures without unscrewing the Camera from the tripod

Price of Camera, including 3 Double Dark Slides :

$4\frac{1}{4} \times 8\frac{1}{4}$	$5 \times 4\frac{1}{2}$	$6\frac{1}{2} \times 4\frac{3}{4}$	$8\frac{1}{2} \times 6\frac{1}{2}$	10×8	12×10	15×12
120/-	126/-	145/-	168/-	212/-	258/-	314/-

"OPTIMUS" CAMERA.

(EXTRA LONG FOCUS)



This advantage is obtained without sacrifice of either Portability or Rigidity. The folding bottom board has an innertelescopic frame which racks out, so giving the great length of focal adjustment. It is fitted with double swing back, horizontal and vertical fronts. The larger sizes are efficient for Studio as well as Field purposes.

Price of Camera, including 3 Double Dark Slides :


$4\frac{1}{4} \times 8\frac{1}{4}$	5×4	$6\frac{1}{2} \times 4\frac{3}{4}$	$8\frac{1}{2} \times 6\frac{1}{2}$	10×8	12×10	15×12
112/6	118/6	131/-	161/-	207/6	255/6	301/6

Extra for Camera, made square, with Reversing Frame :

17/-	18/-	20/-	25/-	27/-	29/-	31/-
------	------	------	------	------	------	------

"OPTIMUS" UNIVERSAL CAMERA.

Specially arranged for Studio use.



"Invited to say if, in our estimation, the Studio Cameras of Perken, Son, and Rayment could be improved in any way whatever, for the purpose for which they are intended, we must answer, No!"—*British Journal of Photography*, November 25th, 1887.

This Camera is perfectly rigid, has double length of Bellows to suit small studios where large pictures are required, is fitted with Mechanical Adjustment to Focus, and is in all respects a perfect Instrument.

Camera, with Repeating Frame, Masks, and one Single Dark Slide ;

$8\frac{1}{2} \times 8\frac{1}{2}$	10×10	12×12	15×15
185/-	225/-	268/-	325/-

Rack to Swing Adjustments :

Extra, 12/-	14/-	16/-	16/-	16/-
-------------	------	------	------	------

EXTRA DOUBLE DARK SLIDES for any of our Cameras :

	$4\frac{1}{4} \times 8\frac{1}{4}$	5×4	$6\frac{1}{2} \times 4\frac{3}{4}$	$8\frac{1}{2} \times 6\frac{1}{2}$	10×8	12×10	15×12
Solid, no hinges.. .. each	7/8	8/8	10/9				
" with hinged shutters ..	10/3	10/9	11/9				
Hinged opening & hinged shutter	14/-	14/6	15/-	21/6	25/	31/6	47/8

THE TRADE AND SHIPPERS ONLY SUPPLIED. DISCOUNT LIST ON APPLICATION

PREFACE.

PHOTOGRAPHY has advanced with such rapid strides—its votaries have been “making history” so quickly—that a complete history of photography has become needful. I only claim for my little book that it is “complete” in the sense that it gives a consecutive account of the principal processes which have been employed in photography during the brief half century of its practical existence.

The materials for this history I was able to gather while compiling the *Bibliography of Photography*, which has appeared during the last two years in the columns of the *Photographic News*, in England, and in *Anthony's Photographic Bulletin*, in America. My lists include books by 170 different authors; and I have done my best to give in the present volume some *resumé* of their work. The history of photography from 1854 to 1888 is practically contained in the pages of the two old-established periodicals—*The British Journal of Photography*, and the *Photographic News*; but *Notes and Queries*, the *Athenæum*, and the *Art Journal* are useful in filling up the gap between 1854 and 1839—the year in which Talbot and Daguerre first published their discoveries.

For several of the illustrations of the “fathers of photography” I am indebted to my kind friend Professor E. Stebbing, of Paris; and to M. Nadar, also of that city, whose contributions to both the science and the art of photography are so well known.

I am also indebted to the Committee of the Camera Club for the loan of a fine portrait of the late W. B. Woodbury; and to Messrs. W. W. Winter (Derby), J. Thomson (London), Vandyke (Liverpool), and J. Stuart (Glasgow), for other portraits.

Of the twelve illustrations, eight have been reproduced by

Messrs. Waterlow & Sons ; two by Bemrose & Co. ; one by the Meisenbach Co. ; and one by Shields. All are, of course, executed by photo-mechanical processes.

Further, I have to thank many veterans of photography for the information they have been kind enough to give me. We have still among us—and long may they live—men who have worked every process from the daguerreotype onwards, and who can remember the time when it was necessary to sit in full sunshine for half-an-hour to secure a portrait ! Even with their assistance, however, I can scarcely hope to have avoided all errors in the mass of dates and names which I have had to give. I can only say that I shall be truly grateful for corrections and additions. Lastly, I wish to tender my thanks to the Librarians of the British Museum and of the Birmingham Public Library for their courtesy and patience.

W. J. H.

PERCY LUND & CO.,

Bradford.

PUBLISHERS AND AGENTS FOR ALL
PHOTOGRAPHIC PUBLICATIONS.

Wilson's Quarter Century in Photography.

528 pages, 386 illustrations. Price 17/-, post-free 17/6. Second edition, supply just to hand. The experience of experts with camera and chemicals. "The most complete handbook of photography ever issued in the English language."—*Photographic News*.

Photographic Printing Methods.

By the REV. W. H. BURBANK. 200 pages; cloth, 4/6; post-free 4/10½. A complete text book, embracing all methods of printing, with a chapter on the theory of light.

Photo-Engraving and Photo-Lithography.

By W. T. WILKINSON. Second edition, revised and enlarged, post-free 3/6.

The American Annual of Photography for 1888.

With numerous illustrations. 90 original contributions. "A standard book of reference, good for all times." Post-free 2/10½.

Photographic Mosaics for 1888.

The popular American Year-book. 144 pages, with a 4-page frontispiece. Post-free 2/3.

John Burnet's Art Essays.

Price 17/-, post-free 17/6. *This work should be in the hands of every one who would understand the principles of art.* It teaches every one, from the rudiments to the highest forms of composition. Photographer and Painter alike will find it invaluable. Over one hundred fine illustrations and etchings (some of them full-page) are given from the most exemplary works of Cuyp; Potter; Ostade; Burnet; Claude; Rubens; De Laer; Terburg; Metzu; Rembrandt; Corregio; Raphael; Guido; West; Domenichino; Wilkie; and others. Handsomely bound. As a help to photographers in making positions it cannot be over estimated. It teaches the practical elements of art entire, and supplies the best examples for study. Owing to the fact that Mr. Burnet's works have been long out of print, few are privileged to enjoy its advantages. Mr. E. L. Wilson has reprinted and republished the original works by means of a photo-lithographic process, thus securing all the charms of the original drawings.

The Ferrotyper's Guide.

A complete manual of instruction in the art of Ferrotyping. Eighth edition. 9d. post-free.

The Modern Practice of Retouching.

By M. PIQUEPE. Third edition. Post-free 1/2.

W. WATSON & SONS

MANUFACTURERS OF HIGHEST-CLASS

Photographic Instruments

Watson's Premier Tourists' Cameras

have patented stops and springs to shutters of dark slides, and the dark slides, fronts, and screws are fitted to standard gauges, so as to be interchangeable in any of the various sizes.

Watson's Detective Camera.

Thoroughly efficient—unobtrusive—a most perfect Instantaneous Apparatus.

Watson's Cyclists' Tripod.

Folds to 16 inches. Perfectly rigid when set up. Price £1 1 0; or with sliding adjustable legs, £1 5 0.

AN ILLUSTRATED DESCRIPTIVE CATALOGUE of everything required in Photography sent post-free to any address on application.

The following awards have been made to W. Watson and Sons.

The Only Medal and First Award for Photographic Cameras, and the Only Medal and First Award for Studio and Tripod Stands; at the GREAT PHOTOGRAPHIC EXHIBITION, held at the Crystal Palace, 1888.

The Only First Award for Photographic Apparatus, Adelaide, 1887.

The Only Gold Medal and First Award for Photographic Apparatus, Liverp'l, 1886. And 10 other Medals and Awards at various International Exhibitions.

W. WATSON & SONS,

Contractors by Appointment to H. M. Government,

313, HIGH HOLBORN, LONDON.

CONTENTS.

	PAGE
INTRODUCTION - - - - -	5
CHAPTER I.	
THE ORIGIN OF PHOTOGRAPHY - - - - -	7
CHAPTER II.	
SOME PIONEERS OF PHOTOGRAPHY—WEDGWOOD AND NIEPCE - -	13
CHAPTER III.	
THE DAGUERREOTYPE PROCESS - - - - -	21
CHAPTER IV.	
FOX-TALBOT AND THE CALOTYPE PROCESS - - - - -	28
CHAPTER V.	
SCOTT-ARCHER AND THE COLLODION PROCESS - - - - -	38
CHAPTER VI.	
COLLODION DRY-PLATES, WITH THE BATH - - - - -	45
CHAPTER VII.	
COLLODION EMULSION - - - - -	53
CHAPTER VIII.	
GELATINE EMULSION WITH BROMIDE OF SILVER - - - - -	57
CHAPTER IX.	
INTRODUCTION OF GELATINO-BROMIDE EMULSION AS AN ARTICLE OF COMMERCE BY BURGESS AND BY KENNETT - - - - -	63
CHAPTER X.	
GELATINE DISPLACES COLLODION - - - - -	70
CHAPTER XI.	
HISTORY OF PHOTOGRAPHIC PRINTING PROCESSES - - - - -	77
CHAPTER XII.	
HISTORY OF PHOTOGRAPHIC PRINTING PROCESSES. Continued - -	95
CHAPTER XIII.	
HISTORY OF ROLLER-SLIDES; AND OF NEGATIVE-MAKING ON PAPER AND ON FILMS - - - - -	106

CHAPTER XIV.

HISTORY OF PHOTOGRAPHY IN COLOURS	-	-	-	-	-	116
-----------------------------------	---	---	---	---	---	-----

CHAPTER XV.

HISTORY OF THE INTRODUCTION OF DEVELOPERS—SUMMING UP	-	125
--	---	-----

APPENDIX.

DR. MADDOX ON THE DISCOVERY OF THE GELATINO-BROMIDE PROCESS	-	129
---	---	-----

BIOGRAPHIES.

NIEPCE DE ST. VICTOR; SAYCE; ABNEY; WOODBURY; ROBINSON; POITEVIN; TRAILL TAYLOR; RUSSELL	-	-	-	-	133
---	---	---	---	---	-----

LIST OF ILLUSTRATIONS.

STATUE OF NICEPHORE NIEPCE	-	-	-	-	-	Frontispiece
DAGUERRE, L. J. M.	-	-	-	-	-	to face page 21
FOX-TALBOT	-	-	-	-	-	" " 28
NIEPCE DE ST. VICTOR	-	-	-	-	-	" " 36
MAJOR C. RUSSELL	-	-	-	-	-	" " 51
B. J. SAYCE	-	-	-	-	-	" " 54
DR. R. L. MADDOX	-	-	-	-	-	" " 61
ROBINSON, H. P.	-	-	-	-	-	" " 85
POITEVIN, A. L.	-	-	-	-	-	" " 100
WOODBURY, W. B.	-	-	-	-	-	" " 112
ABNEY, CAPT. W. DE W.	-	-	-	-	-	" " 122
TAYLOR, J. TRAILL	-	-	-	-	-	" " 131

INTRODUCTION.



WHEN a kind and experienced friend first pressed me to write upon photography, he recommended "practical" subjects. And in this History of Photography I believe I have chosen something directly useful and practical; though, perhaps, a few will be at first disposed to question the utility of such a record of the past. "Don't tell us these old tales!" some budding camera knight of full twenty-four hours' standing will exclaim, "our processes are perfect, and we care for nothing else!"

But photography is an evolutionary science. The key to the proper comprehension of the present lies in the past; and no man can afford to neglect the rich mine of experience which is furnished by the work of his predecessors. Perhaps in no other art have so many things been discovered and re-discovered, and patented twenty times over, as in photography. Even to-day it only requires a diligent study of the photographic literature of the past to bring to light many germs which, with our more advanced knowledge, can be perfected and turned to sources of pleasure and of profit.

Then photography ought to be learned—and taught—historically. Let no man call himself a "photographer" on the strength of having fired off a few gelatine dry plates. To obtain a complete knowledge of the science, you must work your way experimentally along the historical path. Repeat the experiments of Niepce and Daguerre, of Fox-Talbot and Scott-Archer, and you will learn to appreciate the labours of these "fathers of photography;" will sympathise with their difficulties, and glory in their ultimate success.

Not only will you produce a collection of most interesting specimens, but you will accumulate a store of solid knowledge, and will return to your gelatine dry plates a master instead of an apprentice.

To the many whose avocations and want of time forbid so complete a course, we still say, "Study the past!" Buy the old books as well as the new ones; they will all teach you something. So far from photography having attained perfection, we believe it to be but as a little child. Great are our hopes and wondrous our visions of its future; but every advance must be made step by step, and to successfully climb the pyramid of knowledge—which, unlike other pyramids, is daily increasing in altitude—*we must start from the base!*

Then, have not the "men of might" who laid the foundations of our science, a claim that we should make ourselves acquainted with their lives and their work? What soldier is there that does not love to read of Wellington and Bonaparte, of Grant and Lee? With equal interest ought the "children of the sun" to follow the painful path of Niepce, and stand by the death-bed of Scott-Archer—the photographer who gave his precious discovery freely for the use of all, and who died poor and before his time, because he had overstrained his powers in the cause of our science.

Let us hope that the great increase in the number of photographic societies which has marked the last few years, will lead to the establishment of libraries in connection with them, and the formation of modest museums in which interesting relics, illustrating old processes, may be preserved, so that greater facilities may be afforded for the study of the history of photography. As an introduction to that history this humble book has been written by

W. JEROME HARRISON.

Science Laboratory, Icknield Street, Birmingham.

A HISTORY OF PHOTOGRAPHY.

CHAPTER I.

THE ORIGIN OF PHOTOGRAPHY.

PHOTOGRAPHY is the child of optics and chemistry. As neither of these sciences attained anything like a full development until the present century, it is not surprising that the art of taking photographs was unknown to our ancestors. And yet there are many facts that must have been known, even to the ancients, whose meaning, if rightly appreciated, would have led to the early discovery of the art of photography. For example, lenses are all but absolutely necessary to the taking of photographs, and a lens has been found among the ruins of Nineveh, a city which was destroyed more than a thousand years before the birth of Christ. This lens is now in the British Museum. During the Middle Ages the manufacture and properties of simple lenses were well understood in Europe.

The changes produced by the action of light upon matter are so common as to be matters of every-day observation. At a very early stage of civilization the tanning or bronzing of the human skin by the solar rays must have been noticed, even if the black skin of the negro was not assigned to its true cause—a constant residence beneath the intense rays of a tropical sun. During the first century of the Christian era, the Roman philosopher, Pliny, noticed and recorded the fact that yellow wax is bleached by exposure to sunlight. The Greeks knew well that certain gems—the opal and the amethyst more especially—lost their lustre

from the same cause; while the great Roman architect and painter, Vitruvius, was so conscious of the decolourizing effect of sunlight that he invariably placed his paintings in rooms facing the north.

During the Middle Ages almost the only inquirers into the secrets of nature were the alchemists, who vainly sought the philosopher's stone which should transmute the baser metals into gold. But though their search was vain, yet, as so often happens, these experimenters—Roger Bacon, Albert Magnus, Paracelsus, and a host of smaller lights—although they did not find what they were looking for, yet they made many discoveries of great value. The storehouse of nature is so rich that even the blind seeker is rewarded. And so these old alchemists became acquainted with some of the most powerful agents of modern chemistry—the acids, for example—and, as the centuries rolled by, their discoveries bore fruit.

Among those alchemists who experimented with the compounds of silver we find the name of Fabricius, who, in 1556, published a book upon metals.

Horn-silver, or *luna cornea* as it was then termed, was the name given to a semi-transparent compound of silver and chlorine which occurred as an ore in the silver mines of Germany, but which Fabricius found could be prepared by adding a solution of common salt to a solution of silver nitrate. Fabricius and his co-workers appear to have been much surprised when they noticed that this silver compound—white when freshly prepared—quickly turned black when exposed to the sunlight; but as the fact appeared to have no relation to the object which engrossed all their thoughts—the search for gold—no attempt was made to inquire into the nature of this surprising change: a change which must also have been noticed by the miners who extracted the ore.

During the seventeenth and eighteenth centuries many instances were recorded of the effect of light in changing the colours of bodies; but, as the result is most rapid and most striking in the case of compounds of silver, it was to these that attention appears to have been chiefly directed.

Schulze's Experiment.

In 1727, J. H. Schulze actually obtained copies of writing by placing the written characters upon a level surface previously prepared with a mixture of chalk and silver-nitrate solution. The rays of sunlight passing through the translucent paper blackened the silver compound beneath, except where it was protected by the ink forming the letters, and thus a white copy upon a black ground was obtained. Although we cannot, on the strength of this single experiment, assign to Schulze the title which Dr. Eder claims for him as the "discoverer of photography," yet it must be admitted that the experiment was a very remarkable one, and it is much to be regretted that it was not successfully and quickly followed up.

Charles William Scheele, of Stralsund (then a Swedish town), was a distinguished investigator, who may be considered as one of the founders of modern chemistry. In 1777, Scheele examines Silver Chloride. he made the first scientific investigation of the behaviour of silver chloride under the influence of light. First he noted the action of differently coloured light, showing that while the silver salt was quickly darkened by violet or blue light, the red and yellow rays had much less effect upon it. His results were confirmed by Senebier in 1782, who wrote that "in fifteen seconds the violet rays blackened silver chloride as much as the red rays did in twenty minutes." But Scheele also discovered the *cause* of the darkening. He exposed chloride of silver to the action of sunlight underneath water, reasoning, doubtless, that the water would arrest and dissolve any substance which might be given off under the action of light. When the white salt of silver had blackened, Scheele poured away the water and added to it a little silver nitrate. Immediately a white substance was formed (owing to the silver nitrate combining with chlorine dissolved in the water), which was silver chloride formed anew. Thus Scheele proved that the effect of white light upon silver chloride is to decompose it, and cause it to give up some or all of its chlorine. As to whether the black residue is metallic silver (which appears black when in a very fine state of subdivision), or is a compound known as silver subchloride (Ag_2Cl), that is a matter upon which chemists even yet are not agreed. Scheele's conclusions were doubted by Count

Rumford, whose paper entitled "An Enquiry Concerning the Chemical Properties that have been attributed to Light," was published in the Philosophical Transactions of the Royal Society for 1798. He considered that the changes observed were due to *heat* rather than to light; but his arguments were successfully controverted by Robert Harrup, who, in the case of the salts of mercury at all events, conclusively proved (*Nicholson's Journal*, 1802), that light alone was the determining agent of the changes observed.

It was not till near the close of the eighteenth century that any one, with the exception, perhaps, of Schulze, seems to have thought of applying the changes of colour produced by the action of light upon silver compounds to any practical purpose. And yet the instrument called the camera obscura had long been known; and those who gazed upon the beautiful pictures produced by its agency must often have longed to find some method by which they might be fixed and retained. Invented by the Italian philosopher, Baptista Porta, about the middle of the sixteenth century, the camera obscura at first consisted simply—as its name implies—of a darkened room to which light was admitted only through a single small hole in the window-shutter. In such a room, when the sun is shining brightly, a faint inverted image of external objects, as the houses, trees, etc., upon which the window looks, is seen upon the white surface of the wall or screen within the room which faces the window. Porta improved this primitive contrivance by placing a double convex glass lens in the aperture of the shutter, outside which a mirror was placed to receive the rays of light and reflect them through the lens. The image upon the screen within was thus made brighter and more distinct, and was moreover shown in a natural or erect position. Crowds flocked to Porta's house in Naples to see these pictures painted by light, glowing with colour, and depicted with marvellous accuracy. Soon further improvements were made, and the camera obscura became a favourite adjunct to the country houses of the wealthy, often taking the form of a small circular building, erected if possible on a hill-top. The lens was then usually placed in the centre of the conical roof, with a slanting mirror arranged so as

to reflect the light from surrounding objects downward through the lens; the picture thus formed was received upon the whitened surface of a table placed within the little building. Such erections are still not uncommon in places of popular out-door resort, and interesting discoveries are not unfrequently made by those who have gained admittance, as to the doings of unsuspecting outsiders, who little think that their proceedings are pictured for the delectation of others.

Now the photographer's camera is a miniature camera obscura, being nothing more than a well-made box having a lens at one end and a ground glass screen at the other. Still, a modern camera made by one of the masters of the art of cabinet-making as applied to photography, and provided with a battery of first-class lenses, is nothing less than a work of art, and is correspondingly expensive.

A Chinese tradition credits the sun with sometimes producing pictures of the neighbouring objects upon the ice-covered surfaces of lakes and rivers. A similar idea must have possessed the mind of Fénélon, when, in 1690, he wrote his fable called "Une Voyage Supposé," descriptive of the imaginary journeys of an imaginary personage, in which the following passage occurs: "There was no painter in that country; but if anybody wished to have the portrait of a friend, of a picture, a beautiful landscape, or of any other object, water was placed in great basins of gold or silver, and the object desired to be painted was placed in front of that water. After a while the water froze and became a glass mirror, on which an ineffaceable image remained."

But it was reserved for another Frenchman, Tiphaigne de la Roche, to make a still nearer guess as to the manner in which "nature-printed" pictures would one day be produced. In 1760 he wrote a book entitled "Giphantie" (an anagram of his own name), containing a series of wild imaginings, one of which must have appeared especially improbable to his contemporaries, although it has since been literally fulfilled. The hero of "Giphantie" is carried by a hurricane to a strange land, where he is shown the method by which the native genii produce pictures. "You know," said the guide, "that rays of light

reflected from different bodies form pictures, paint the image reflected on all polished surfaces, for example, on the retina of the eye, on water, and on glass. The spirits have sought to fix these fleeting images; they have made a subtle matter by means of which a picture is formed in the twinkling of an eye. They coat a piece of canvas with this matter, and place it in front of the object to be taken. The first effect of this cloth is similar to that of a mirror, but by means of its viscous nature the prepared canvas, as is not the case with the mirror, retains a fac-simile of the image. The mirror represents images faithfully, but retains none; our canvas reflects them no less faithfully, but retains them all. This impression of the image is instantaneous. The canvas is then removed and deposited in a dark place. An hour later the impression is dry, and you have a picture the more precious in that no art can imitate its truthfulness."

After reading this very remarkable prophecy, one can hardly help thinking that De la Roche must have conceived the idea after viewing the pictures shown with Porta's "dark chamber," a contrivance which was then, as we know, in vogue.

CHAPTER II.

SOME PIONEERS OF PHOTOGRAPHY—WEDGWOOD AND NIEPCE.

The discovery of photography, altogether or in part, has been claimed for at least two men, who attained distinction in science towards the end of the eighteenth century. It has been stated that Professor Charles, who was well known in Paris as a lecturer on chemistry and physics about the year 1780, not uncommonly (as a lecture experiment) obtained profiles of the heads of his students by placing them so that the required shadow of the features was cast by a strong beam of sunlight upon a sheet of paper coated with chloride of silver. As the light would discolour that portion of the paper upon which it fell, the result was a white outline of the face upon a black background. But this statement is a mere tradition, and the best authorities have considered it "too vague and improbable to be taken into serious account."

Some twenty years back, an attempt was made to prove that Matthew Boulton, the partner of James Watt, was acquainted with a method of producing photographs, at least as early as 1777. But the numerous pictures which about that date were sold by the famous Birmingham firm of Boulton & Watt, were executed by a mechanical process—possibly aquatint—the invention of an ingenious artist, Mr. Eginton, who was then employed at the great Soho factory. These pictures were of large size, as much as five feet by four, and were coloured. In a series of pamphlets published in 1864-5, Boulton's grandson—Mr. M. P. W. Boulton—clearly proved that photography had nothing to do with the production of these pictures. Living in that district of Birmingham where Boulton and Watt did their work, we have carefully studied this question, and can endorse the conclusions arrived at and very ably stated by the younger Boulton. A claim to rank as a discoverer of photography

recently made on behalf of Lord Brougham rests only on his statement that in a paper communicated by him to the Royal Society in 1795, he suggested the use of a plate of ivory rubbed with nitrate of silver, as a surface which might secure, permanently, the pictures of the camera obscura. But as this paragraph did not appear in the published paper (Brougham says it was eliminated by the secretary), we cannot seriously take it into account.

With the dawn of the nineteenth century all things were propitious for the rapid advancement of matters scientific.

Great progress had by this time been made both in chemistry and in optics; while the art of experimenting — the knowledge of how to question nature—had become familiar to many men of talent and education. Thomas Wedgwood, fourth son of the great potter, earnestly studied the action of light upon certain compounds of silver. He was encouraged and assisted by Humphrey Davy, then just rising into fame as a chemist, and after Wedgwood's death Davy wrote an account of their work, which appeared in the *Journal of the Royal Institution*, for 1802. Wedgwood's best results were obtained by coating paper or white leather with a weak solution of silver nitrate. The more or less opaque object which it was desired to copy was then placed on the prepared surface, and the whole exposed to sunlight. In a few minutes, the unprotected portions of the paper were darkened, and when the opaque object was removed, its form remained in white upon a black ground. Paintings on glass could be copied in this way, the light passing through the transparent and semi-transparent portions, and blackening the sensitive paper placed underneath. Wedgwood noticed that "red rays, or the common sunbeams passed through red glass, have very little action upon paper prepared in this manner; yellow and green are more efficacious, but blue and violet light produce the most decided and powerful effects." These facts had been previously published by Scheele and by Senebier, but Wedgwood does not appear to have known of their work. The scantiness of scientific literature at that time, and the difficulty of communication between different countries, were indeed great hindrances to progress. The workers in any one

Copying by Sun-
light — Wedgwood
and Davy.

country were usually ignorant of what had been done elsewhere; so that the same track was pursued again and again, and the same discoveries made several times over. Davy made some important additions to Wedgwood's work. He found that the chloride was much more sensitive to light than the nitrate of silver. Both Wedgwood and Davy attempted to secure the pictures formed within a camera, upon paper coated with these salts of silver, but without success. Davy, however, using the more concentrated light of the solar microscope, readily obtained images of small objects upon paper prepared with silver chloride.

But there was another and more fatal objection to this method of "picturing by light," which not even Davy, with all his chemical knowledge, was able to surmount. When the copies obtained were exposed to daylight, the same agency which had produced the picture proceeded to destroy it. The action of sunlight upon the white or lightly shaded portions constituting the picture speedily blackened the entire surface of the paper or leather, causing the whole to become of one uniform tint in which nothing could be distinguished. To prevent this it was clearly necessary to remove the unacted-on silver salt after the image had been formed; and before the paper was exposed, as a whole, to daylight. Long-continued washing in water was tried, but proved ineffectual; nor was a coating of transparent varnish found of any service. Davy does not seem to have pursued the process with much energy, and the whole thing dropped into obscurity. Still he clearly recognized its capabilities, for he writes: "Nothing but a method of preventing the unshaded parts of the delineations from being coloured by exposure to the day is wanting to render this process as useful as it is elegant." In this copying process, devised by Wedgwood and improved by Davy, we see the germ of the ordinary method by which our negative photographs on glass are made to yield a positive proof or impression upon sensitized paper.

The first man to obtain a permanent photograph was Joseph Nicéphore Niepce, who was born at Chalons-sur-Saone, March 7th, 1765. Well educated, his parents designed him for the Church, but the outbreak of the French Revolution upset all their plans, and in 1794 Niepce fought in

A Patient Photo-
grapher — Joseph
Nicéphore Niepce.

the ranks of the Republican army which invaded Italy. Ill-health soon compelled his retirement from active service, and, marrying, he settled down at Chalons ; his brother Claude, to whom he was devotedly attached, residing with him.

Even during childhood, the fondness of the brothers Niepce for scientific pursuits had been very noticeable, and they now applied themselves to the task of invention, bringing out a machine called the pyrelophore, which propelled vessels by the aid of hot air ; and a velocipede, the ancestor of our modern bicycle. Endeavouring to bring these inventions before the public, Claude went to Paris in 1811, and afterwards crossed over to England, where he settled down at Kew.

It was, apparently, about the year 1813 that Nicéphore Niepce began the experiments which resulted in his discovery of what may be called the bitumen process in photography. From his correspondence with his brother Claude, we learn something of this method ; and when, in 1827, Nicéphore visited his brother at Kew, he brought with him many specimens of his work. These pictures, the first permanent photographs ever produced, Niepce desired to bring before the notice of the Royal Society, but as he declined to publish the process by which they were produced (being desirous to perfect it before making it public), the rules of the society compelled them to refuse Niepce's communication. Having examined several of the specimens presented by this early French experimenter to his English friends, we can testify to the successful manner in which he had succeeded in copying engravings.

Making but a short stay in England, Niepce returned to France, where, in 1829, he entered into a partnership with another investigator, named Daguerre. But Niepce was not destined to complete his work, or even to publish his results ; he died in 1833, at the age of sixty-eight. Although it is impossible to assign the title of "Inventor of Photography" to any one man, yet Niepce has probably the best claim to it. Quite recently a statue of Niepce has been erected at Chalons.

Lithography, invented by a German, Senefelder, in 1798, was successfully practiced in France in 1812. Expert draughtsmen were required to execute the necessary drawings upon the

Lithography and
Photography.

prepared surfaces of the smooth blocks of limestone employed. Now Niepce thought that it might be possible, by the action of light, to cause designs, engravings, etc., to copy themselves upon the lithographic stone. The basis of all his work was the discovery that bitumen, or "Jew's pitch," as it was then commonly called, is rendered insoluble by the action of light. Niepce dissolved bitumen in oil of lavender, and spread a thin layer of it upon the stone. Next he varnished the drawing on paper, of which he desired to secure an impression—the varnish rendering the paper fairly transparent—and laid it upon the bitumenized stone. After exposing the whole to sunlight for an hour or so, the paper was removed and oil of lavender poured upon the bitumen, by which those portions of it that had been protected from light by the opaque lines of the drawing were dissolved away, and the surface of the stone beneath was in those parts exposed. Thus, the outlines of the original subject were reproduced with perfect truth. Lastly, by treating the stone with an acid, the exposed portions could be "bitten" or eroded more deeply, and it was then ready for printing from. Finding much difficulty in securing stone of a sufficiently fine and close grain, Niepce substituted metal, employing plates of polished tin, etc., on which to spread the bitumen. Although the results he obtained were far from perfect, yet they were very promising, and heliography, as Niepce named this method, has since proved very useful.

Having obtained pictures by what we may call contact-printing, Niepce's next endeavour was to apply his process to securing the beautiful views produced by the aid of a camera. For this purpose he tried the chlorides

Niepce Secures
Photographs in the
Camera

of silver and of iron, and gum guaiacum, whose sensibility to light had been investigated by Wollaston, in 1804. Nothing, however, answered so well in his hands as the surface of bitumen or asphalt, with which he had already been successful in heliography. When exposed to the action of the light forming the picture within a camera, the bitumen became insoluble in proportion to the intensity of the light by which the various parts of the image were produced, an effect which we now know to be due to the oxidation, and consequent hardening of this

resinous substance. When the resinized plate was removed from the camera, no picture at all was visible on its surface. But by steeping the exposed plate in a mixture of oil of lavender and petroleum, the still soluble portions of the bitumen were removed. The shadows of the landscape were then represented by bare portions of the metal plate, while the insoluble resin which remained indicated the brightest parts, or "high-lights," of the original. Obviously such a picture would look more natural if the portions of polished metal exposed could be darkened, and for this purpose we know that Niepce employed various chemicals, and among others iodine.

It is unfortunate that Nicéphore Niepce never published a single line descriptive of his methods, so that it is only from his correspondence—and more especially his letters to his brother Claude—that we can glean our information. The difficulties of an experimenter in an obscure French town, seventy years ago, were indeed great. Niepce tells us that his first camera was fashioned out of a cigar box, while his lenses were "the lenses of the solar microscope, which, as you know, belonged to our grandfather, Barrault." In a letter, written to his brother in 1816, Niepce describes how he secured what was probably the first picture ever taken in a camera: "My object glass being broken, and being no longer able to use my camera, I made an artificial eye with Isidore's ring box, a little thing from sixteen to eighteen lines square. . . . I placed this little apparatus in my workroom, facing the open window looking on to the pigeon house. I made the experiment in the way you are acquainted with, and I saw on the white paper the whole of the pigeon house seen from the window. . . . One could distinguish the effects of the solar rays in the picture from the pigeon house up to the window sash. The possibility of painting by this means appears almost clear to me. . . . I do not hide from myself that there are great difficulties, especially as regards fixing the colours, but with work and patience one can accomplish much."

"Work!" and "Patience!"—truly Niepce himself combined these in no common degree. From the reference to white paper used in this early experiment, it would seem probable that silver

chloride was employed. We know that Niepce used the substance, and that he gave it up, because, like Wedgwood and Davy, he was unable to fix or render permanent the pictures secured by its aid.

The agreement made between Niepce and Daguerre bound the two investigators to communicate to each other all the

Niepce's agreement with Daguerre. processes which they had discovered for fixing the camera-image; and it went on to state that

the two inventors were to share equally in any profits that might be obtained. In compliance with this resolution, Niepce drew up the following important statement, which is dated December 5th, 1829: "The discovery which I have made, and to which I give the name of heliography, consists in producing spontaneously, by the action of light, with gradations of tints from black to white, the images received by the camera obscura. Light acts chemically upon bodies. It is absorbed; it combines with them, and communicates to them new properties. Thus it augments the natural consistency of some of these bodies; it solidifies them even; and renders them more or less insoluble, according to the duration or intensity of its action. The substance which has succeeded best with me is asphaltum, dissolved in oil of lavender. A tablet of plated silver is to be highly polished, on which a thin coating of the varnish is to be applied with a light roll of soft skin. The plate, when dry, may be immediately submitted to the action of light in the focus of the camera. But even after having been thus exposed a length of time sufficient for receiving the impressions of external objects, nothing is apparent to show that these impressions exist. The forms of the future picture remain still invisible. The next operation then is to disengage the shrouded imagery, and this is accomplished by a solvent, consisting of one part by volume of essential oil of lavender, and ten of oil of white petroleum. Into this liquid the exposed tablet is plunged, and the operator observing it by reflected light, begins to perceive the images of the objects to which it had been exposed, gradually unfolding their forms. The plate is then lifted out, allowed to drain, and well washed with water." To this Niepce adds: "It were, however, to be desired that, by blackening the metal plate, we could


obtain all the gradations of tone from black to white. The substance which I now employ for this purpose is iodine, which possesses the property of evaporating at the ordinary temperature." We cannot but admire the graphic description of the phenomena of development here given by Niepce, and, without doubt, it formed the foundation of all the discoveries in photography that followed. It will be noticed that Niepce's method of development was a physical one only, for it consisted in simply washing away by a suitable solvent, the unacted-on, and therefore still soluble, parts of the bitumen.

The chief objection to the beautiful and ingenious process discovered by Nicéphore Niepce was the great length of time for which the bitumenized plate needed to be exposed in the camera. For an ordinary landscape an exposure of from six to eight hours was required. During this time the shadows of objects changed from one side to the other, so that the resulting pictures were comparatively flat and spiritless, being devoid of the charming effects resulting from the contrast of light and shade. Another trouble arose from the fact that in the half-tones of the picture the bitumen was only hardened at the surface, the layer beneath remaining soft and soluble. When the developing liquid was applied this lower layer was apt to be dissolved, and in the final washing it sometimes carried away with it the hardened upper portion, so producing bare patches or defects.

Most black varnishes are made from asphalt, and we can easily imitate Niepce's process by coating a glass or metal plate with a thin layer of such varnish and exposing it under a negative to bright sunshine. By subsequent washing with petroleum the picture is readily developed.

Defects of Niepce's
Process.

Experiments in
Heliography.



LOUIS JACQUES MANDÉ DAGUERRE.
1787—1851.

CHAPTER III.

THE DAGUERREOTYPE PROCESS.

Nicéphore Niepce was a man of a quiet and retiring disposition ; a student who was so immersed in his work and so desirous of perfecting it, that he hesitated—while
Life of Daguerre. as yet he felt it to be incomplete—to publish even the smallest details with regard to it.

But the man with whom Niepce entered into partnership—Louis Jacques Mandé Daguerre — was of a very opposite temperament, bold and energetic, desirous of fame and its accompanying rewards, accustomed to success and to the applause of the public.

Daguerre was born at Corneilles, a village near Paris, in 1787. Neglected by his parents, his native talents asserted themselves, and while still young he became known as a scene-painter of great power and originality ; while the mechanical effects which he introduced to add to the realism of his stage-views were the admiration of all Paris.

In 1822, Daguerre opened a diorama in Paris, for which he executed paintings on a colossal scale of such scenery as the “Village of Goldau,” the “Valley of Sarnen,” etc. By painting on both sides of the canvas, and showing the picture first by reflected, and then by transmitted light, very remarkable changes and effects could be produced.

In the sketches from nature which Daguerre made as a preliminary aid to the execution of these immense pictures, he frequently employed the camera obscura ; and it was the remarkable beauty and perfection of the images produced by this instrument that determined the artist to attempt the discovery of some means by which they could be permanently retained.

Without any scientific education or training this task would have seemed to most persons a hopeless one ; but perhaps

Daguerre's very ignorance of the difficulties to be encountered was one cause of his perseverance. The date of his first attempts appears to have been about 1824, and during the next two or three years we hear of his paying frequent visits to the shop of Chevalier, a well-known Parisian optician, of whom Daguerre purchased the camera, lenses, and other articles necessary to his new pursuit.

In 1826, Daguerre was informed—probably by Chevalier—that a gentleman at Chalons had already made considerable progress toward the end which he was himself desiring to attain. Letters addressed to Niepce received, however, but curt responses, and it was not till 1827, when Niepce passed through Paris on his way to England, that he entered into cordial relations with Daguerre. The partnership between these two workers, which was established in 1829, was continued after the death of the elder Niepce; Isidore Niepce taking the place of his father.

Year after year passed away and left our scene-painter still toiling after his ideal—ever endeavouring to fix the fleeting images formed by the lens of his camera. His ordinary work is neglected; but he passes nine-tenths of his time in his laboratory. It was at this period that Madame Daguerre sought advice as to the sanity of her husband, and was not, perhaps, much comforted by the assurance of the men of science whom she consulted that the object of her husband's researches was "not absolutely impossible!" Five years after the death of Niepce, his partner was able to announce that he had overcome all difficulties, and that henceforth nature would depict her own likeness with a pencil of light. In 1838, Daguerre attempted to form a company which should acquire and work the new process; but the Parisian public was utterly incredulous, and the shares were not taken up. In this extremity Daguerre showed his specimens, and, in confidence, explained his method to the eminent French astronomer and physicist, Arago. Arago's admiration and delight with this new and wonderful process by which objects were made to draw their own pictures were unbounded. As a man of science, and of world-wide reputation, his endorsement of the value of Daguerre's discovery at once established its

Publication of the
Daguerreotype Pro-
cess in 1839.

worth, and on his recommendation the French Government awarded to Daguerre a life pension of 6,000 francs, and to Isidore Niepce one of 4,000 francs per annum, on the condition that the invention should be published without patenting it; this money being paid by France for "the glory of endowing the world of science and of art with one of the most surprising discoveries that honour their native land." Notwithstanding this official statement, a patent was taken out by Daguerre in one country—England—in 1839.

Daguerre is said to have placed a written account of his process in the hands of Arago in January, 1839, and at the same time to have publicly exhibited specimens of the results which he had up to that time obtained; but no details were revealed, nor was the paper published until the meeting of the Academy in August of that year. The new process was named *Daguerreotype*, and the excitable inhabitants of the French metropolis went into ecstasies over it. Nevertheless, the daguerreotype process was, at the time of its publication, very imperfect; and it was destined to undergo important modifications and improvements during the next three or four years.

The news of Daguerre's wonderful discovery soon spread to other countries, and the inventor obtained a rich reward by the sale of apparatus, and by the instruction of hundreds who flocked to Paris to learn the details of the new art. A keen observer—Sir John Robinson—wrote as follows, in 1839, to a friend in the United States: "Circumstances led to my being included in a small party of English gentlemen who were lately invited to visit the studio of M. Daguerre to see the results of his discovery. I satisfied myself that the pictures produced by his process have no resemblance of anything, as far as I know, that has yet been produced in this country. Excepting the absence of colour, they are perfect images as seen by reflection from a highly polished surface. The subjects which I saw were views of streets, boulevards and buildings; vacillating objects made indistinct pictures. There can be no doubt that when the daguerreotype process is known to the public it will be immediately applied to numberless useful processes; and even the fine arts will gain, for the eye, accustomed to the accuracy of the Daguerre pictures,

will no longer be satisfied with bad drawing, however splendidly it may be coloured." Every word of this prediction has since been fulfilled.

Daguerre died in 1851, aged sixty-three. In 1883, a bust of this ardent worker was unveiled at Corneilles; funds for its execution having been contributed by photographers of all civilized nations. Viewing his whole career, Daguerre must be considered as a fortunate man. Not only did he reap much honour and material benefit from his discovery, but he lived to see photography rise to an important place amongst the arts and sciences.

The materials employed by Daguerre in his early experiments—between 1824 and 1829—appear to have been the same as those used by Wedgwood and Davy—the chloride and nitrate of silver spread upon paper; and he did not advance upon it, indeed, he equalled, the results obtained by the two English chemists. After entering into partnership with Niepce, and learning the details of his bitumen process, Daguerre followed for a time in the same track; but further study enabled him to work out improvements and modifications which led him ultimately to a greater success. We know that Niepce sometimes used metal plates coated with silver; moreover, he employed iodine to darken these plates after the picture had been developed. Using these two materials—plates of silver and vapour of iodine—Daguerre found that the iodide of silver, formed by exposing silver to the vapour of iodine, was sensitive to light. When such "iodized silver plates" were exposed within the camera, faint images of bright objects were impressed upon them in the course of two or three hours.

At this stage a happy "accident" occurred, which revealed to Daguerre a method by which not only was the time of exposure necessary to secure a good picture greatly reduced, but the distinctness and beauty of the image was much enhanced. It appears that one day Daguerre removed from his camera a plate, which, either from the shortness of the exposure or the dullness of the light, showed no sign of an image. He placed this blank plate in a store cupboard, intending to clean the surface and use it again. But what must have been

How Daguerre
was Led to his Discoveries.

Development by
Mercury Vapour.

our photographer's surprise when, on taking out this plate the next morning, he found upon its surface a distinct and perfect picture! Another prepared plate was quickly exposed for an equally short time within the camera, and again a sojourn of twenty-four hours within the magic cupboard sufficed to bring out a picture. The next step was to ascertain to which of the numerous chemicals kept within the cupboard this marvellous effect was due. By a process of elimination it was at last traced to a dish full of mercury.

Delighted by this fortunate discovery, Daguerre at once proceeded to place his exposed plates over a dish of warm mercury, when the vapour proceeding from the liquid metal was found to settle upon the iodized silver in exact proportion to the intensity of the light by which each part of the plate had been affected. This was, in fact, a process of "development;" an invisible or "latent" image being strengthened and thereby made visible. Some such method of "developing" the originally feeble impressions produced upon sensitive plates by a short exposure to light has been found necessary in every photographic process.

Another advance made by the French artist was the discovery of a fixing agent. This was neither more nor less than a strong solution of common salt, in which the plates were soaked after development; and which dissolved and washed away the iodide of silver that had not been acted on by light. But when, almost immediately after the publication of the daguerreotype process in 1839, Sir John Herschel drew attention to the superior qualities of hyposulphite of soda as a solvent of the silver salt, Daguerre immediately adopted it for clearing and fixing his exposed plates. We may mention that this substance, so valuable to every photographer, was discovered by Chaussier in 1799, and its power of dissolving the haloid salts of silver had been described by Herschel as early as 1819.*

The first daguerreotypes were so delicate that the merest touch of the finger was sufficient to mar their beauty; and, when exposed to the air, they rapidly tarnished and deteriorated.

* See paper on "Hyposulphurous Acid and Its Compounds," *Edinburgh Philosophical Journal*, vol. i, pp. 8, 396.

Improvements in
the Daguerreotype
Process.

This defect was remedied by M. Fizeau, who gilded the image by means of a mixture of chloride of gold and hyposulphite of soda. This solution was poured over the silver plate, which was then heated until the liquid evaporated, leaving a thin coating of gold upon the picture, which was thereby rendered more distinct, as well as more permanent.

Another great improvement was introduced by Mr. Goddard, a London science lecturer, in 1840. He exposed the iodized silver plate to the action of bromine vapour, thereby forming a bromide of silver upon the plate in addition to iodide of silver. In 1841, M. Claudet used chlorine vapour in a like manner. Plates prepared by either of these methods were found to be far more sensitive to light than those which had been simply iodized. In fact, the time required to produce a picture in the camera was thereby reduced to from one to five minutes; or, with a very good light, to less than one minute.

As the three elements referred to above were only discovered, chlorine in 1774, iodine in 1811, and bromine in 1826, we see that photography was hardly possible before the present century.

After the improvements of Goddard and Claudet, which were quickly adopted by Daguerre, the production of portraits by the daguerreotype process became comparatively easy. In the very first attempts at portraiture, which appear to have been made in America by

Introduction of
Portraiture by Pho-
tography.

Draper and Morse, in 1839, the sitter's face was covered with white powder, the eyes were closed, and the exposure, lasting for perhaps half an hour, was made in bright sunshine! To lessen the glare of light, which painfully affected the sitter, Draper caused the sunlight to pass through a large glass tank containing a clear blue liquid—ammonia—sulphate of copper—before falling upon the sitter, thus filtering out most of the heat rays, which could well be spared, as they possess little or no actinic value. In 1840, Beard and Claudet opened photographic studios in London; Davidson followed suit in Edinburgh, and Shaw in Birmingham, and soon daguerreotypy became a trade. For landscapes, etc., the daguerreotype process was, however, but seldom employed, though we read of a fine

instantaneous picture of New York Harbour being secured by its aid.*

The expense of the plates, which were usually of copper plated with silver, was a serious objection to the daguerreotype process. As late as 1854 we find the price of daguerreotypes in England was two and a half guineas each for the quarter-plate size ($4\frac{1}{4} \times 3\frac{1}{4}$) and four guineas each for half-plate size. The cleansing and polishing of the silver surface on which the picture was to be produced, was a most troublesome task, necessitating great care and a vast amount of labour in the production of the "black polish" which was necessary. It must also be remembered that there was practically no power of multiplying a daguerreotype—a fact due to the opacity of the silver plate. It is true that Grove (now Sir W. R. Grove, one of Her Majesty's Justices) devised a method of etching daguerreotypes with acid, so that they could be used in a printing press; but, practically, this method was a failure.

The daguerreotype held sway for about ten years only, from 1839 to 1851. It was more popular in America† than in England; indeed, in the latter country, specimens of the art are now quite rare. With all its faults it was an immense advance on anything previously known, and entitles Daguerre to rank with the leading inventors of the nineteenth century!

* The original is in the possession of Mr. J. Werge, of Berners Street, London, to whom I am indebted for a copy.

† For an admirable description of the faults and merits of a daguerreotype portrait, see Hawthorne's "House of the Seven Gables," chap. vi.

CHAPTER IV.

FOX-TALBOT AND THE CALOTYPE PROCESS.

While Daguerre was pursuing his researches into matters photographic, in France, another worker was advancing toward the same goal in England, though by a different road. Henry Fox-Talbot, born February, 1800, was of high lineage; the Talbots taking rank among the oldest families in England; while his mother—Lady Elizabeth Fox-Strangways—was the eldest daughter of the Earl of Ilchester.

The future discoverer of photography graduated at Cambridge with high honours, in 1821. He sat for two years in Parliament, but politics had no charms for him, and in 1834 he retired from public life to devote himself wholly to scientific research.


Talbot was a very versatile student of nature. His earliest work was mathematical; but between 1826 and 1834 he published five papers upon various phenomena connected with light. Then for many years photography engrossed his thoughts; but in after life he studied and wrote on "Spectrum Analysis," the "Cuneiform Inscriptions of Egypt," etc. Altogether fifty papers from his pen appeared in various scientific periodicals between 1822 and 1872.

Fox-Talbot died at his family seat, Lacock Abbey, in Wiltshire, on the 17th of September, 1877, full of years and honour. As a discoverer of photographic processes, he may fairly claim to be placed on an equality with Niepce and Daguerre.

Talbot tells us that it was in 1833, while sketching the beautiful scenery of the Italian lakes with the aid of a camera obscura, that he was struck with the idea that it might be possible to fix, and retain permanently, the exquisite fac-similes of surrounding objects produced by the aid of that instrument.

Six years of steady work at the problem followed, at the end

Talbot's Early
Work in Photo-
graphy.



HENRY FOX-TALBOT.

1800—1877.

of which the publication of Talbot's process—for he succeeded in devising a means by which his object was attained—was hastened by the news that a Frenchman had also achieved success in fixing the camera-image.

It was on the 25th of January, 1839, that Professor Faraday described the new method of "Photogenic Drawing" (for so Talbot styled his invention) to the members of the Royal Institution—then, as now, a very popular London scientific club—and invited them to inspect a collection of drawings produced solely by the aid of light. On the 31st of the same month, a paper giving a full description of the method was read by Talbot before the Royal Society; this paper was shortly afterwards published in the *Philosophical Magazine*. Thus the publication of Talbot's process was made before that of Daguerre.

But when the two methods came to be compared it was found that they were essentially different. Talbot had followed up in his photographs on paper, the line of research indicated by Wedgwood; while Daguerre's method with polished silver plates was built upon the foundation furnished by Niepce; thus each had completed the work of his own countryman.

Talbot's success was due, in the first place, to the fact that he had succeeded in rendering chloride of silver far more sensitive to light than Wedgwood or Davy had been able to do. Taking fine writing-paper, he soaked it in a weak solution of common salt, and then brushed one side of the paper twice over with a solution of nitrate of silver. When this was done, what chemists call "double decomposition" took place, and chloride of silver was formed in the pores and upon the surface of the paper; while mingled with the chloride there was also a slight excess of the nitrate of silver. It was to this use in combination of the two salts of silver—the nitrate being in excess—that the increased sensitiveness to light which paper so prepared was found to possess was due. Talbot found that paper treated in this way was darkened by even a momentary exposure to bright sunlight. By its aid he readily secured images of objects in the solar microscope. But his crowning triumph was attained when, after an exposure of about an hour, he succeeded in

The Method of
Photogenic Draw-
ing.

obtaining an impression of the picture formed by the lens within the camera obscura. Talbot states that he had reached this point in 1835, and that in that year he secured several camera pictures of his residence, Lacock Abbey.

It will be remembered that it was the want of a fixing agent which baffled Sir Humphrey Davy in 1802. But Talbot was more fortunate. After well washing his photographs, he soaked them either in a solution of common salt, or in a solution of potassium iodide or bromide. By this treatment he found that his pictures were rendered permanent; at least they could be freely examined in the daylight without further darkening.

Fox-Talbot did not rest content with his early successes. After the publication of Daguerre's paper, in 1839, he tried the iodide of silver instead of the chloride; and above all he succeeded in discovering a method of development by which the time of exposure necessary to secure a picture was very greatly reduced. In Talbot's early experiments the sensitive paper had to remain at the back of the camera until the image was printed-out upon it by the action of light; and for this a good light and a long period of time were necessary. But in September, 1840, Talbot states he discovered that if the sensitive paper be brushed over with a mixture of gallic acid and nitrate of silver, and be then exposed, while still wet, within the camera, the time necessary to secure a picture is only two or three minutes. He also found that the paper might be dried and exposed in that state, the image being subsequently brought out or "developed" by brushing over it more of the "gallo-nitrate of silver" solution.

It is tolerably certain that in the system of development described in the last paragraph, Talbot had been anticipated by a few months by the Rev. J. B. Reade, a well-known English clergyman. We have seen that Wedgwood had noticed, some forty or fifty years before the time of which we are now speaking, that copies by light were produced most rapidly when leather was used as a support for the salts of silver. Reade also found this to be the case, and as his inroads upon his wife's stock of white kid gloves

How Talbot Fixed
his Pictures.

The Calotype or
Talbotype Process.

Reade independ-
ently Discovers De-
velopment by Gallic
Acid.

were not unnaturally objected to by that lady, he was led to the discovery that the increased sensitiveness to light was due to the solution of nut-galls with which leather is impregnated during the operation of tanning. Finally, he secured in what may be termed the essence of the galls—gallic acid—a substance capable of strengthening or developing the invisible, photographic, or, as it was then termed, the *latent* image, which is formed, after even a very short exposure, upon the surface of the sensitive paper within the camera.

Talbot patented his calotype (beautiful picture) process in February, 1841. It is the third British patent for photography, Talbot Patents the Calotype Process. the two previous ones being for the daguerreotype process. The calotype process was also frequently called Talbotype, in honour of the discoverer. The patent was afterwards disputed in the law courts, on the ground of its "previous discovery" by the Rev. J. B. Reade; but it was upheld by the judge mainly for the reason that Reade did not properly publish or make known his discovery.

The paper was carefully selected, of a close, even texture and fine surface. A solution of nitrate of silver (100 grains to six ounces of water) was brushed over one side of the Outline of the Calotype Process. paper and allowed to dry. It was then dipped into a solution of potassium iodide (500 grains to one pint of water), where it was left for two or three minutes. During this time the iodine combined with the silver to form iodide of silver. Lastly, the paper was rinsed in pure water and dried, when it was seen to be covered with a pale yellow coating of iodide of silver, which in that condition was practically unacted upon by light.

When it was desired to use this calotype paper, it was taken into the dark-room and brushed over with the "gallo-nitrate of silver," made by mixing a solution of nitrate of silver (50 grains to the ounce) with one-sixth its volume of strong acetic acid, and adding an equal quantity of a saturated solution of gallic acid. The paper so prepared might be used wet, or it might be dried and kept for use at some future time. In either case the picture could be subsequently brought out by brushing more gallo-nitrate of silver over the exposed surface; though, if the paper was

exposed while still wet, this was not absolutely necessary. Finally, the picture was fixed by well washing first in water, then in a solution of potassium bromide or some other soluble bromide, and then in water again.

In a patent taken out in 1843, Talbot claimed the use of a hot solution of "hyposulphite of soda (or any other soluble hyposulphite)," to give increased whiteness to calotype and other photographic pictures, and at the same time make them more permanent; but this claim was quite indefensible, since Sir John Herschel had announced the power of this substance to dissolve the salts of silver as early as 1819, and had again called attention to its value for this purpose in 1840.

Niepce found that in the pictures obtained on his resinized plates, the lights and shades were just the reverse of those of nature; the whitest parts of the original objects being represented by the dark surface of the insoluble parts of the bitumen, while the shadows

Photographic
Negatives and
Positives.

were indicated by the bared surface of the metal plate. In the same way Talbot found that the brightest parts of any landscape were represented by black patches of reduced silver upon his sensitive paper, while those parts of the paper upon which little light fell (the dark shadows, etc., of the landscape) remained white. Thus the developed image upon a sheet of calotype paper was the exact reverse, as far as light and shade were concerned, of the objects depicted. To such a picture Sir John Herschel, in 1841, applied the name of "negative." But paper is a semi-transparent substance, and by oiling or waxing it its transparency can be greatly increased. This fact, combined with the reversed nature of the original, enabled Talbot to obtain true copies of any negative by placing a piece of sensitive paper underneath the negative, and then exposing it to sunlight. The rays of light passing through the clear or transparent parts of the negative, blackened the paper beneath. After a sufficient time had elapsed the lower sheet of paper was removed, and it was then found to present a correct picture in black and white of the original objects. To such a copy Herschel applied the name of "positive." It is obvious that in this way any number of positives could be obtained from a single negative, and in

this respect the calotype process had a great advantage over the daguerreotype.

In 1843, Fox-Talbot visited Paris, lecturing on his calotype process to large audiences, and instructing the Parisian photographers in his method. To make generally known its capabilities, he began, in 1844, the issue of "The Pencil of Nature," a book which appeared in six parts, containing twenty-four calotype plates, between 1844 and 1846; it is a handsome quarto, and was sold for three guineas. This book is now very scarce, but in all the various copies which I have examined the pictures are more or less faded, the fading extending gradually from the edges to the centre. The fact is that the necessity for a very thorough washing of each print to free it from hyposulphite of soda was not fully recognised in those early days of the art.

After the introduction of Archer's collodion process, in 1851, Talbot devised a modification of it by which he obtained instantaneous pictures, as those are called which receive an exposure of a fraction of a second only. Perhaps the experiment which he performed in the lecture room of the Royal Institution in proof of his success has never been surpassed. Fastening a page of the *Times* newspaper to the edge of a revolving wheel, a clear photograph of every letter was obtained by the aid of the electric discharge of a battery of Leyden jars. Now it is known that the brilliant spark of light produced by such a discharge does not continue for more than the ten-thousandth part of a second. This "instantaneous process" was, however, complicated and difficult, and only its inventor was successful with it.

In 1852, Talbot invented a process of engraving on steel plates by the action of light upon a surface composed of gelatine and bichromate of potash, to which he gave the name of photo-glyphy. About 1854, he introduced albumen to give a gloss to the surface of the paper on which photographs are printed.

It is hardly possible to overrate the difficulties which photographers had to contend with half a century ago. Many of these difficulties were extraneous to their art. Thus hyposulphite of soda was, in 1840, a chemical

Publication of the
"Pencil of Nature."

Later Work of
Fox-Talbot.

Defects of the
Calotype Process.

curiosity, and for years afterwards its price was six shillings per pound; *pure* chemicals, too, were hardly to be obtained, so that the worker was often forced to manufacture his own materials.

The calotypists were especially at the mercy of the paper-makers. Canson, in France, and Turner, Hollingworth, and others, in England, made good paper, but still the grain was perceptible, and it was frequently uneven, knotty, and speckled with particles of metal from the machinery of the paper mills. Then it was difficult to get the paper to lie flat in the dark-slide, and its comparative opacity made the negatives print slowly. To remedy the latter defects, the French experimenters, Le Gray and Blanquart-Evrard, introduced, about 1850, the method of waxing the paper by dipping it in melted wax and then ironing it between sheets of blotting-paper. This made the paper more even in texture and very translucent. It was then sensitized, exposed, and developed in the usual way.

From the moment that the silvered plate of Daguerre, or the sheet of paper used by Talbot, was fully sensitized, it became impossible to expose it to ordinary light. The

Light for the
Dark-Room.

only white light allowed to fall upon the sensitive surface must be that which passes through the lens of the camera, and by that light the image is imprinted on the film containing the silver salt. But it is impossible, or at all events most inconvenient, to go through the operations of sensitizing and developing the plates in utter darkness. Here the fact discovered by Scheele, in 1777, comes to our aid. He found that red light produced no chemical effect upon the chloride of silver; and, speaking of the ordinary salts of silver employed in photography—the chloride, the iodide, and the bromide—it may be said that they are unaffected by pure red light. Even yellow light has little or no effect upon these substances if they are contained in collodion; but when bromide of silver in gelatine is tested in the same way, a few minutes' exposure to strong yellow light will be found to produce a change. Capt. Abney, however, has recently prepared bromide of silver in such a molecular condition that it is strongly affected even by the red rays. Speaking generally, however, we may say that no harm is done to the sensitive surfaces ordinarily used by the photographer by a few minutes' exposure

to red, or even orange light, and this space of time is sufficient to enable him to perform the various operations which are necessary. I have elsewhere recommended the use of covers of red card-board for all the flat dishes in which sensitive plates or paper are manipulated; and by using trays fitted with lids of ruby glass, it is quite possible to develop plates in any ordinarily lighted room. Thus the photographer's "dark-room" would be more properly called the "red-room," for its windows are usually glazed with ruby glass, and its gas-jets and lamps fitted with ruby globes.

In 1844, Claudet actually took out a patent for the use of red light in photographers' dark-rooms; but he does not appear to have attempted to enforce it. During the collodion epoch (1851-80), yellow light was generally employed to develop by. For our gelatine dry-plates, either an orange or a ruby-coloured light is preferable.

For ten or twelve years after the publication of the discoveries of Daguerre and Talbot, their processes—so distinct in method, although aiming at a like result—held joint sway over the little world of photography. By professional portraitists the Daguerreotype process was preferred, owing, no doubt, to the clear, sharp pictures and beautiful detail which could be secured thereby; in part, also, their preference may have been due to the high prices which were cheerfully paid for pictures on "plates of silver." Amateurs, on the other hand, usually employed the Talbotype process; it was less expensive, less cumbrous, and permitted of the multiplication of the results obtained—for one good negative would furnish a large number of positive copies.

Photography is indebted to Sir John Herschel for many great improvements. The "famous son of a famous father," he was born in 1792, and was, therefore, in the zenith of his powers at the time of Daguerre's discovery (1839). He immediately suggested the use of glass plates as a support for the sensitive salts of silver; recognizing in the transparency, rigidity, and cheapness of glass, together with its indifference to the chemicals employed, properties of the highest value in photography.


Contrast between
Daguerreotype and
Talbotype.

Herschel Intro-
duces Glass Plates.

Herschel's plan was to place his glass plates at the bottom of a vessel containing finely divided silver chloride in water. The white silver salt was slowly deposited, in a uniform film, upon the upper surface of the glass. The water was then syphoned off, and the plate dried and exposed to the camera. The images obtained in this way were, however, very faint, and although some success attended Herschel's attempts to intensify them by electro-deposition, still good prints could not be obtained. At that time it was not known that silver chloride is unaffected by light, unless there be some substance mixed with it which is capable of attracting and combining with the chlorine which is liberated, under such conditions, by the action of light.

Niepece de St. Victor, born 1805, died 1870, nephew of *the* Niepce, improved on Herschel's plan by recognizing the fact that it is necessary to coat the glass plates employed in photography with a film of some suitable substance, in and on which the particles to be affected by light may rest. For this purpose he employed albumen, beating up white of egg with potassium iodide (20 grains per egg), potassium bromide (four grains), and common salt (two grains). The clear liquid so obtained was poured upon the glass plate, dried, and heated until the albumen hardened and became insoluble. It was then dipped into a bath of silver nitrate, where a chemical change took place, resulting in the formation of iodide and bromide of silver within the pores of the albumen. The plate thus sensitized could either be exposed while wet, in the camera, or it might be rinsed, dried, and kept in a dark place till wanted. Development was effected by brushing a solution of gallic acid over the albumenized plate. This process was published in 1848, and improvements in it were quickly effected by two other French investigators—Blanquart-Evrard and Le Gray.

This albumen process was a considerable advance. The transparency of the glass permitted the production of positive prints at a rapid rate; while the clear and delicate film of albumen furnished a capital medium for holding the molecules of the sensitive silver salts, and securing their adhesion to, and equal distribution over, the surface of the plate. It is a mistake, however, to suppose that such substances as albumen,



NIEPCE DE ST. VICTOR.

collodion, and gelatine, are nothing more than vehicles in which the sensitive molecules are contained. They each exercise an influence—differing in degree—upon the silver salt imbedded in them, by which the decomposing action of light is facilitated. In Great Britain the albumen process was practised very successfully about 1850, by Messrs. Ross and Thomson, of Edinburgh, whose pictures of architectural subjects on plates fifteen inches square were greatly admired. Many travellers also used dry-plates prepared on this system. Its chief drawback was the length of exposure necessary—from five to twenty minutes under ordinary conditions.

CHAPTER V.

SCOTT-ARCHER AND THE COLLODION PROCESS.

Schönbein, the famous Swiss chemist, discovered, in 1846, that when ordinary cotton is soaked in a mixture of nitric and sulphuric acids its properties become greatly changed. The explosive substance so obtained received the name of gun-cotton, or insoluble pyroxyline. When the acids were slightly dilute, or when the time of soaking was very short, a less dangerous compound was obtained, which was known as soluble pyroxyline.

In the next year—1847—an American investigator named Maynard (of Boston), showed that when soluble pyroxyline was dissolved in a mixture of ether and alcohol, a somewhat viscid liquid was produced, to which he gave the name of collodion. When this collodion was poured out upon a level surface, as that of a sheet of glass, the ether quickly evaporated and a delicate skin or film was left behind. When dry this film was fairly tough and horny. Collodion formed so admirable a covering for bruises, etc., preventing the access of air, that it speedily became of use in surgery.

In 1849, a Frenchman, Gustave Le Gray, suggested that collodion might prove useful in photography. In his book—which was translated into English in 1850—he writes, “I have just discovered a process upon glass by hydrofluoric ether, the fluoride of potassium and soda dissolved in alcohol 40 degs. Fahr., mixed with sulphuric ether, and afterwards saturated with collodion; I afterwards react with nitrate of silver, and thus obtain proofs in the camera in five seconds in the shade. I develop the image with a very weak solution of sulphate of iron, and fix with hyposulphite of soda.”

Another early investigator in this line was Robert J. Bing-

ham, who, as assistant to the great Faraday, made the acquaintance of collodion immediately on its introduction into England in 1847. In a book published in 1850, he gives, first Herschel's method; then a method with albumen; then one for coating glass plates with isinglass, and finally adds, "we may, in place of the gelatine (isinglass) employ a number of other substances to form an adherent film upon the glass. The following are a few of those we have experimented with and found to answer moderately well—gluten, collodion, varnishes, etc." But although Le Gray and Bingham may take the credit for having been the first to *suggest* a possible use of collodion in photography, yet the merit of the invention and publication of the collodion process proper belongs entirely to Frederick Scott-Archer; his article describing this method first appearing in a London periodical called *The Chemist*, in March, 1851.

Born at Bishop Stortford, in 1813, Archer was apprenticed to a silversmith in Leadenhall Street, London. His tastes were artistic, and on attaining manhood he became a sculptor. It is said that his early attempts at photography, by the calotype method, about 1847, were stimulated by his desire to employ the art to secure mementos of the productions of his chisel. In September, 1850, Archer's new process was so far advanced that he communicated it to his friends, among whom were Dr. H. W. Diamond, Mr. P. W. Fry, and others, from whom he received much assistance. Probably Archer did not realize the importance of his discovery, for he did not attempt to patent it; although in 1855 he patented a method of removing the collodion film from glass by coating it with gutta-percha, an improvement which had little or no practical value.

So good and complete was Archer's method that in three or four years it practically displaced both calotype and daguerreotype, and reigned supreme from 1855 to 1880. The inventor took up photography professionally, opening a studio in Great Russell Street, near the British Museum; but he made no money by photography, for his brain was too busy in imagining new things to reap the benefit of that which he had already accomplished. Among other inventions devised by Archer,

we may name a camera, within which the plates could be developed and fixed, as well as exposed; a triplet lens; and a useful method of whitening positives on glass by soaking them in mercury bichloride. This was called the "alabastrine process."

Scott-Archer died in May, 1857, and was buried in the London suburban cemetery called Kensal Green. A subscription of £747 was raised for his widow and little children; but, Mrs. Archer dying shortly afterwards, the amount was settled on the children, together with a government pension of £50 per annum, awarded on the ground that their father was "the discoverer of a scientific process of great value to the nation, from which the inventor had reaped little or no benefit."

The following account is taken from a small book—"Manual of the Collodion Photographic Process"—published by Archer in 1852; a second edition appeared in 1854.

1. Immerse eighty grains of cotton-wool in a mixture of one ounce each of nitric and sulphuric acids; take out after fifteen seconds, and wash thoroughly in running water.

2. Dissolve the pyroxyline so obtained in a mixture of equal parts of sulphuric ether and absolute alcohol. The solution so obtained is ordinary collodion.

3. Add some soluble iodide—usually iodide of potassium—to the collodion. A little potassium bromide may also be added.

4. Pour the iodized collodion on a perfectly clean glass plate, and allow two or three minutes for the film to set.

5. Take the coated plate into the dark-room and immerse it in a bath of silver nitrate (30 grains to every ounce of water) for about a minute. Here a chemical change takes place by which silver iodide is formed in the pores of the collodion.

6. Remove the plate, which is now sensitive to white light, place it in a slide-holder, and expose it in the camera. The time of exposure "may vary from one moment to a quarter of an hour."

7. Take the plate back to the dark-room and develop it by pouring on it a mixture of water, one ounce; acetic acid, one dram; pyrogalllic acid, three grains. Archer claims that "the

great power shown by pyrogallic acid in bringing out the latent image was first made known by me in a short description in the May number of *The Chemist* for 1850."

8. Fix the image by soaking the plate "in a strong solution of hyposulphite of soda." At a later period cyanide of potassium was preferred by most operators for this purpose.

When a single picture only was desired, a short exposure was given, and the deposit of metallic silver which forms the image was whitened by soaking the developed plate in mercury bichloride. When a black surface was then placed behind the photograph it stood out on the glass in correct black and white as a positive image. Probably every household has specimens of such collodion positives, of which large numbers were produced between 1854 and 1870. An American improvement consisted in the use of thin plates of black or chocolate enamelled iron—ferrotypes, irreverently called tintypes—or sheets of black japanned leather, instead of glass. Itinerant photographers still employ this "positive" method largely, since by it they can complete and hand over their productions to their clients within a few minutes.

For making lantern slides the wet collodion process is still considered one of the best, if not the best method.

Up to about 1853 a photograph was considered a curiosity; but the introduction and perfection of the collodion process made photography, for the first time, a really popular pursuit. With mistaken ideas as to the ease of the new method, large numbers of amateurs purchased the necessary materials; and, about 1858, the camera became as common an object as the barrel organ!

But with the practice of photography came the sad knowledge that there is no royal road to the taking of good pictures. Although money might be lavishly spent in the purchase of costly apparatus, yet it was soon found that some knowledge of chemistry, and some artistic taste, together with practice in manipulation, and neatness and accuracy in working, were indispensable to success. Moreover, the chemicals employed—more especially the silver nitrate—had ways of marking the apprentice to photography; stains of inky darkness upon the

Collodion Positives
AMBROTYPES.

Popularization of
Photography.

An
t

hands and clothes soon earned for the infant science the appellation of the "black art."

Thus the popularity of photography—as an amusement for amateurs—declined almost as rapidly as it had risen. Still some lasting effects of the first photographic boom remained. The Photographic Society of London,* established in 1853, has always exercised a favourable influence on photography in Great Britain: while our two old weekly periodicals, the *Photographic News*, dating from 1858, and the *British Journal of Photography*, 1859 (as a monthly from 1854), have steadily led the way in endeavouring to make photography more and more a science; and in showing that it is something better than a mere mechanical pursuit, or means of getting a livelihood.

In 1841, Towson, of Liverpool, pointed out that since in an ordinary or "uncorrected" lens the focus of the blue-violet or chemical rays (as we may call those which produce the principal effect upon the salts of silver) is not the same as the focus of the yellow or visual rays, *i.e.*, those by which the image is seen, it is necessary to adjust the distance of the lens from the ground glass, after the picture has been focussed, in order to allow for this. Here Professor J. Petzval, an eminent mathematician, of Vienna, came to the rescue, and devised a portrait lens which brought all the rays practically to the same focus. This lens was manufactured by Voigtlander, of the same city, and soon acquired a great reputation.

Among the earliest daguerreotypists of America were Messrs. John Johnson and A. Wolcott, who worked together. Mr.

Wolcott, in order to take portraits more rapidly, devised a camera with a concave mirror instead of a lens, and the plate was placed in the focus of the mirror. In 1840, Johnson came to London, took out a patent for his "reflecting camera," and entered into partnership with the holder of Daguerre's patent, Mr. Beard. They engaged a Mr. Goddard, from the Polytechnic Institution, as an assistant, and it was found that by using bromine in addition to iodine for sensitizing the silver plates, the time of exposure was reduced from minutes to seconds. At this time, 1841, there were only

* Title changed to Photographic Society of Great Britain, in 1876.

two photographic establishments in London, those of Beard and of Claudet, but the new art already enjoyed much popularity, and their takings were frequently as much as £50 per day.

The census of Great Britain for 1841, does not record photography as an occupation at all; even in 1851, only 51 professional photographers are included; while in the returns for 1881, we find no fewer than 7,614 photographers.

In 1857, professional photography derived considerable benefit from a fancy of the Duke of Parma, who had his portrait gummed on his visiting cards in the place of his name. Disderi, in Paris, court photographer to Napoleon III., pushed the matter, and soon it became the correct thing for every person in society to present his friends with his *carte-de-visite*.

The patent of Daguerre lapsed in 1853, and as Fox-Talbot was defeated in a lawsuit which he brought, in 1854, against a professional photographer called Laroche, who employed the collodion process (which Talbot claimed as only a modification of his calotype), the field of photography was free to all. Ever since 1854, its history has been one of steady and continued progress.

Of the annoyance and damage caused by the black stains of nitrate of silver we have already spoken; but the odour of the collodion, due to the evaporation of the ether and alcohol which it contained, was also very disagreeable, especially in the small and usually hot rooms in which photographic operations were commonly carried on. Then, in the preparation of the glass plates before they were coated, great care had to be exercised to get a smooth and chemically clean surface; the least scratch, or speck of dust, showed as a defect in the finished picture. The making of collodion was so troublesome a process that it was usually purchased ready made. The bath of silver nitrate was another source of endless trouble; accounts of its vagaries fill a large portion of the photographic periodicals of the time; it needed continual care, attention, and renewal. Lastly, the necessity of keeping the surface of the sensitive plate wet during the whole time of exposure, introduced a serious difficulty when it was desired to carry the plates even a small distance; or when, as in the case

Some Defects of
the Wet Collodion
Process.

of photographing interiors, the necessary exposure extended over a period of several hours.

Although the photographer who has only acquired the art within the last few years is apt to look upon the earlier processes which we have now described with the contempt which naturally springs from ignorance, yet it is certain that many of the wonders of the new photography have been equalled in the past—"for there were giants in those days!" The principal difference is that the work has now been rendered more easy and more certain. We glory in the wonderful rapidity of gelatine dry-plates; but many years ago Breeze, Blanchard, and others, secured upon wet plates all those surprising effects of breaking waves and fleeting clouds which many believe have but recently been obtained.

In general work, to take a few examples only, the genre pictures of Rejlander—whose "Ginx's Baby" enjoyed unbounded popularity—the landscapes of Mudd, England, Bedford, and Frith, and the portraits of Salomon, Claudet, and Silvy, were all done with collodion, and will ever remain "hard to beat."

The main results of the new discoveries in photography which have signalized the last half dozen years, has been to render it possible for any person of ordinary intelligence and industry to produce good or even excellent pictures with far less expenditure of time and labour than was formerly the case; and this without that soiling of the fingers, clothes, and surroundings, which in the old days caused every photographer to be a "marked man."

Some Achievements of the Workers with Collodion.

Effect of the Recent Improvements in Photography.

CHAPTER VI.

COLLODION DRY-PLATES, WITH THE BATH.

In the earliest photographic processes, the sensitive surfaces employed were exposed in a dry condition to the action of light.

Inconvenience of Wet Plates. The silver chloride paper of Wedgwood and Davy, the bitumenized plates of Niepce, and the iodized silver plates of Daguerre, were all used in a dry or desiccated state.

In the calotype process, devised by Fox-Talbot, where a support of paper coated with silver iodide was employed, the paper might be exposed either in a wet or in a dry state. In the younger Niepce's albumen process on glass, when it was desired to use the plates dry, which was generally the case, the surface, after sensitizing, was washed to free it from the free nitrate of silver, and the plate was then dried by the aid of heat, which coagulated the albumen.

But in the collodion process, as introduced by Scott-Archer, in 1851, it was absolutely necessary that the glass plates coated with collodion containing iodide and nitrate of silver, should be exposed while wet; in fact, as soon as possible after their removal from the bath of silver nitrate solution. Moreover, the exposed plates must be developed as quickly as possible—before the surface has had time to dry.

The chief reason for this is that the silver nitrate crystallizes as the plate dries, and the network of distinctly visible crystals so formed interferes with and spoils the picture. The iodide of silver also becomes insensitive to light when dried in contact with the silver nitrate, combining with it to form iodo-nitrate of silver.

For this reason the ordinary wet collodion process, though well adapted for the studio, is not so suitable for landscape work, or for the requirements of travellers. A heavy equip-

ment has to be carried in the form of tent, nitrate bath, etc., and a good supply of water—indispensable for the processes of development and fixing—must be at hand ; so that we sometimes read, in the early photographic journals, of tremendous exertions incurred by enterprising photographers in carrying barrels of water to a mountain top, where that precious fluid was otherwise unattainable. Again, if the exposure was a very long one, as in the case of dark interiors, where several hours were sometimes necessary, the surface of the plate had time to dry, and the picture was then, of course, spoiled for the reasons given above.

Lastly, in very cold weather, the solution of silver nitrate froze upon the plate when it was used in the open air, so that out-of-door photography during the winter months was all but impossible.

To remedy this defect of the wet collodion process, otherwise so great an improvement on all that had gone before, was the aim of many experimenters in the years which immediately succeeded its introduction in 1851. Of the steps by which success was finally attained, and of the still later workers who caused gelatine to displace collodion, only meagre and unconnected details have been hitherto given. Aided by an earnest study of the contemporary literature, it will be our aim to endeavour to supply this defect.

Early in 1853, a French photographer, M. A. Girod, proposed* to apply a second plate of glass to the surface of the wet collodion, so as to protect it from the action of the air ; the plates were placed together in the dark-slide, the plain glass being next the light. After exposure, the plates were separated, and the collodionized plate developed as usual.

One objection to this plan was the liability to injure the delicate skin of collodion. It was also difficult to apply the second glass plate without including air bubbles ; imperfections in the glass itself also had an injurious effect. As an improvement, M. Gaudin suggested the separation of the two glass plates by strips of filter paper around the edges. The plain glass plate would then be removed just prior to exposure. Or, better, the plates might be carried, one above another, in an

* In *La Lumière* for March 19th, 1853.

air-tight box, by which evaporation would be checked. None of these plans, however, were found to be of much practical value; for one thing, they greatly increased the weight of glass which had to be carried.

In the *Philosophical Magazine* for May, 1854, Messrs. John Spiller and William Crookes, names that have since become famous in the annals of chemistry, proposed to keep the collodion *moist* by the use of some deliquescent salt, *i.e.*, some substance which, having a strong affinity for water, would absorb moisture from the air. They tried the nitrates of lime, magnesia, and zinc. The glass plate was collodionized and sensitized in the usual way, and was then immersed in a solution of zinc nitrate and silver nitrate for five minutes. After draining for half an hour on blotting-paper, the plate was ready for use. Such plates remained moist (owing to the hygroscopic nature of the zinc salt), and fit for use for a week or more. They could also be kept for some time after exposure, but before development it was necessary to dip them again into the silver nitrate bath. Subsequently Spiller and Crookes found that nitrate of magnesia acted rather better than nitrate of zinc.

In 1854, George Shadbolt and Maxwell-Lyte independently proposed the use of a solution of honey, or of grape sugar, to coat the sensitized plate, which had been previously washed until the greater part of the free nitrate of silver was removed. Before development, the syrup was washed off, and the plate again dipped in the nitrate bath. By this coating with honey the surface of the sensitive plate was kept moist, and crystallization of the remaining silver nitrate was prevented. Plates treated in this way required about double the exposure of ordinary wet plates; but they could be kept for days between sensitizing and exposing; and again between exposing and developing. They were, however, very liable to spots, since particles of dust adhered firmly to the sticky coating.

A process which found great favour, and which was practiced for many years, was published, in 1855, by the French scientist, Dr. J. M. Taupenot.* It was, in fact, the first dry-plate

* *La Lumière*, Sept. 8th, 1855.

The Taupenot, or
Collodio - Albumen
Dry-Plate Process.

process of practical utility. As first published, Taupenot's method was to take the collodionized and sensitized plate, pour over it a solution of iodized albumen, and allow it to drain and dry; the plate was then dipped a second time into a silver-nitrate bath, again washed, and finally dried. This double process was thought rather tedious, but the plates so prepared would keep for weeks or months.

It may be remarked that the addition of albumen to the ordinary silver nitrate bath had been previously recommended by Mayall,* the plates being dipped in the mixture, and then washed and dried.

In the collodio-albumen process the film was very apt to slip off the glass during fixing, and Barnes, Hardwich, and others advocated, in 1859, the application of a coating, or substratum, of gelatine, albumen, or india-rubber, which, adhering firmly to the glass surface below and to the collodion above, would hold the latter securely on the plate.

Taupenot's process owed its popularity in England largely to Mr. W. Ackland, who wrote several papers pointing out its advantages. Of the many who practiced it, Mr. James Mudd, of Manchester, obtained, perhaps, the best results, his landscapes being objects of admiration at many of our exhibitions between 1860 and 1870. The principal, almost the only, fault of the collodio-albumen process, was its slowness. The plates required an exposure about six times longer than wet collodion. Then the plates would not keep for very long periods; at least, they were never so good after six or eight weeks.

This method of arresting evaporation from the surface of a collodionized plate was described by J. D. Llewelyn in April, 1856. Oxymer is a mixture of vinegar and honey, and plates covered with it were found to retain their good qualities for eight or ten hours. But the exposures were long—about six times more than for ordinary wet collodion plates.

Perhaps the simplest way of keeping collodion "moist" was suggested by H. N. King,† who carried his sensitized plates in a

* *Journal London Photographic Society*, May 21st, 1855.

† *Journal London Photographic Society*, Feb. 21st, 1857.

light-tight box filled with distilled water; the weight of the water required was an obvious objection to this plan.

Mr. G. R. Muirhead, of Glasgow, stated† on the 4th of August, 1854, that “light acts almost as energetically on a dry surface as on a wet, and if a plate be washed well in water (after immersion in the silver bath) to remove all the free nitrate, and allowed to dry, it will remain unaltered for a lengthened period; before developing the plate it must be dipped in the silver bath, as a photograph will not develop without the presence of free nitrate of silver.”

But in this discovery Muirhead had been anticipated by M. A. Gaudin, who had declared,‡ several months previously, that “the presence of this film (of nitrate of silver) during the exposure is altogether superfluous; it is only useful during the development” of the plate.

Accordingly Gaudin washed his sensitized plates in distilled water, until the silver nitrate upon their surfaces was removed; having thus “suppressed the argentiferous film,” the plate was dried by the aid of heat, exposed, again dipped in the nitrate bath, and then developed. In this very suggestive paper the author also points out, that the absence or thinness of the image at the point where the developer is poured on, is due to the liquid sweeping away the free nitrate of silver from that part. He also suggests the use of a solution of white sugar, honey, treacle, etc., which permit, in fact, the nitrate of silver to dry upon the plate without crystallizing; in this, Gaudin may be said to have anticipated Shadbolt and Lyte.

Early in 1855, Dr. Hill Norris, of Birmingham, described§ a dry process in which the sensitive plates were washed, first in distilled water, and then in the usual developing solution of pyrogallic acid, after which they were dried and kept till wanted.

This process was first described by Mr. Thomas Fothergill in the *Times* newspaper early in 1858. It was, in fact, merely the first half of Taupenot’s process, the albumen being washed off the sensitized plate, which was

The Fothergill
Process.

† *Journal London Photographic Society*, vol. ii., p. 19.

‡ *La Lumière*, for April 22nd and May 27th, 1854.

§ *Journal London Photographic Society*, May 21st, 1855.

then allowed to dry. It was found that notwithstanding this washing, sufficient albumen was retained in the pores of the collodion to answer all necessary purposes. From its simplicity, Fothergill's process was largely practiced between 1857 and 1865; and dry-plates made on this principle were then an article of commerce.

After the publication of Dr. Taupenot's collodio-albumen process in 1855, every few months saw the announcement of some new substance or other, wherewith the sensitive surface of a collodion plate might be covered, so as to enable it to be dried and kept ready for use. We now know that such "preservatives" have a triple function; (1) they fill the pores of the collodion, and so give ready access to the developing solution when it is subsequently applied; (2) they protect the silver salt from the action of the atmosphere; and (3) they assist the action of light by absorbing the bromine or iodine given off from the silver salt during the exposure.

Among the preservatives formerly in use we may name gelatine (Hill-Norris, July, 1856), meta-gelatine (Maxwell-Lyte, February, 1857), golden syrup (J. Sang, April, 1857), gum arabic (A. Johnson, August, 1857), besides brown and white sugar, dextrine, raspberry vinegar, beer, wort, malt, morphine, tea, coffee, tobacco, and many other substances.


Dr. Norris first laid down the theory that for dry processes a porous collodion was necessary, and that one great function of the preservative coating was to fill up the pores of the collodion while the latter were wet and open.

Dr. Hill Norris's
Collodio - Gelatine
Process.

Then, subsequently, when the developer was applied, it passed readily by means of the coating *into* the collodion film. On September 1st, 1856, Dr. Norris took out a patent for the following process, by which pictures may be produced "on perfectly dry and hard collodion films. Having produced in the film the sensitive iodide of silver, it is immersed in a solution of gum arabic, or of dextrine, starch, gelatine, albumen, gum tragacanth, vegetable mucilage, caseine, gluten, or other such like substances, that will, by occupying the pores of the collodion film, prevent its condensation on drying, and retain it in a sensitive and pervious state; the films are then



THE UNIVERSITY OF CHICAGO
LIBRARY



MAJOR C. RUSSELL.

From a Photograph (copyright) by J. Thomson, of London.

dried, and are ready for exposure to light, or may be kept for any convenient length of time and used as desired." Dry-plates prepared according to this method, or rather, it was supposed, according to a modification of it which was kept secret, were made in large numbers at Birmingham under Dr. Norris's direction. They were, perhaps, the first dry-plates introduced into commerce, and were largely used between 1856 and 1866. They appear to have had many good qualities, and to have been nearly as rapid as wet plates. A. J. Melhuish writes:* "Having used during the last year or two nearly 2000 of Dr. Norris's dry gelatine plates, I have never had one negative *spoiled*, and but two or three affected by blistering." Some believed that Dr. Norris discovered the superior sensitiveness of bromide over iodide of silver, and that it was bromide of silver which was used in the "Norris" dry-plates.

About the year 1856, the Abbé Desprats recommended the introduction of a little resin into the collodion. The glass plates were coated with this resinized collodion, which
 The Resin Process. was then sensitized, and finally well washed and dried. Such plates were found to keep well, but the resin soon caused the silver bath to get out of order. Its useful action on the plate was due to the fact that, being in an extremely fine state of division, it kept the collodion open, and facilitated the entrance of the developer into its pores.

In 1861, Major C. Russell published a small book containing an account of the researches which he had then pursued for nearly five years in dry-plate photography. A
 The Tannin Process. second edition appeared in 1863, and an appendix in 1865. It had been known for some time that a wash of gallic or pyrogallic acid over the collodion before drying it, imparted keeping powers and sensitiveness to dry-plates. Russell found that the substance from which these acids were prepared—*tannin*—was preferable even to them. The process at first published was as follows: "Coat the plate with collodion, and sensitize it as usual; then wash well; now pour over the surface a solution of tannin, fifteen grains to the ounce of water; lastly, drain and dry."

* *Journal Photographic Society of London*, January, 1860,

The ingredients from which this process derives its name were used by Hardwick in the preparation of dry plates as early as 1860; but the process with which Mr. Russell
The Gum-Gallic Process. Manners Gordon obtained such excellent results was entirely of his own working out, and was first published in the "Photographic News Year Book," for 1868. The plate was edged with albumen, coated with iodized collodion, and immersed in the nitrate bath for ten minutes. It was then well washed and flowed over with a solution containing gum arabic, sugar candy and gallic acid; the plate being then drained and dried. The exposure required was from four to twenty times that of a wet plate.

The early dry-plate workers used to joke each other on a certain "gin-and-water" process, the defect of which was said
The Albumen Beer-Process. to be that the liquid would not "keep." Sherry was actually employed with success, while beer was found to be a capital preservative. In 1874, Capt. Abney devised the "albumen-beer process," which was successfully used in that year by the expeditions sent out to study the transit of Venus. He used a very porous collodion, which was poured on the glass plates, then sensitized by immersion in a bath of silver nitrate, and flowed over with a mixture of albumen and (flat) beer. The plate was drained, and then a second mixture, composed of beer with a little pyrogallic acid, was poured over it. It was then dried in the ordinary manner, and was ready for use.

Dry-plates prepared by the methods we have now described were usually translucent, the light passing freely through the
Backing for Dry Plates. film and being (in part) reflected from the glass behind, thus producing halation. To remedy this, it was usual to "back" the plates with a mixture of burnt sienna and gum-water, or some similar opaque compound. This "backing" was washed off prior to development. At a later date, pieces of black tissue rubbed over with glycerine were placed on the back of the plate for the same purpose, and this is a plan which might still be adopted with profit where the chances of halation are great.

CHAPTER VII.

COLLODION EMULSION.

The term emulsion is applied to a liquid which holds in suspension a large number of particles of some solid body.

What is an Emulsion? Milk may be considered as the type of an emulsion—the word itself being derived from the Latin *emulgere*, to milk out—since it consists mainly of water in which are suspended innumerable minute particles of fat (cream). The white colour of milk, and of most emulsions, is due to the reflection of light from these solid particles.

Very soon after the discovery of the wet collodion process, it was seen how advantageous it would be if the “bath” of silver nitrate could be dispensed with. In August, 1853, M. A. Gaudin, a French photographer, whose work has hardly received proper recognition, stated in the pages of *La Lumière*, that “the whole future of photography seemed to require a sensitive collodion, which could be preserved in a flask and poured, when required, upon glass or paper; and by the use of which, either at once, or after the lapse of time, positive or negative pictures could be obtained.”

This idea must have occurred to many minds; in September, 1861, a London photographer named Bellini, announced* a process for coating glass with a solution of shellac containing iodide, bromide, and lactate of silver; “all that is necessary is to coat a plate with this preparation and expose it in the camera.” This process was not a workable one; but next year Captain Dixon and Mr. Samuel Fry attempted to form a company to work a method by which “a preparation is poured upon the plate, whereby an even, homogeneous film is produced, which is sensitive to light.” The then editor of the *Photographic News* justly remarked that “we conceive it to

* *Photographic News*, p. 250.

be very possible that the germ of a considerable modification or revolution in the ordinary negative process may spring from this discovery.* From Dixon's patent it appears that he simply added nitrate of silver, dissolved in alcohol, to ordinary iodized collodion. His first results—which appear to have been comparatively accidental—were his best; and he did not work out the method so as to arrive at any definite formula.

In the same year Gaudin published in *La Lumière* his method of preparing *photogene*, a name which he applied to “any sensitive compound containing iodide of silver with excess of free nitrate of silver.” He writes: “I prepare the collodion photogene by dissolving nitrate of silver in hot alcohol with a few drops of water, and adding this to collodion; the mixture must be well shaken, and while shaking add from time to time a few drops of iodized collodion.” The photogene so prepared was poured upon glass or paper, and was ready for use at once. But Gaudin found that “upon glass the image develops very feebly and superficially. The photogene is almost impenetrable to developing agents; and this is unfortunate, because, but for that, it would realize the long-sought-for dry collodion.” The fact is, although Gaudin did not know it, that silver iodide alone does not form a good emulsion unless special precautions are taken; it clots too rapidly and sinks to the bottom of the collodion.

It was on September 9th, 1864, that Messrs. B. J. Sayce and W. B. Bolton, of Liverpool, published† an account of a process which they had then but just devised. They

Sayce and Bolton's
Collodion Emulsion
Process.

added nitrate of silver to a bromized collodion, thereby forming bromide of silver in the collodion.

Plates were coated with this liquid, and then flowed over with tannin, after which they were dried. Improvements, mostly by the authors of the process, quickly followed. The amount of silver was increased, and the preservative (the tannin) was mixed with the emulsion instead of being added afterwards. From this time we find the words “organifier,” or “sensitizer,” more frequently used than “preservative,” for such substances as tannin, etc. Mr. Sayce, the elder and more experienced of the

* *Photographic News*, April, 1861, p. 193.

† *British Journal of Photography*.



B. J. SAYCE.

From a Photograph by Vandyke, Liverpool.

two workers, retired* in 1865 from the practice of photography ; but his coadjutor, Mr. Bolton, continued to introduce valuable improvements ; thus, in November, 1865, he pointed out the advantages of a small excess of nitrate in the collodion emulsion.

In April, 1870, a well-known American worker, Mr. Carey Lea, recommended the addition of a few drops of aqua regia to the emulsion, the result being that the plates no longer fogged, a defect to which they had previously been liable, especially when a high degree of sensitiveness was aimed at. Capt. Abney has since shown that this introduction of a mineral acid into the emulsion prevents the formation of, or destroys when formed, any oxide or sub-bromide of silver, substances which would inevitably produce fog on the application of the developer.

Many other workers, among whom we may name Col. Stuart-Wortley, and Messrs. George Dawson, T. Sutton, W. J. Stillman, J. W. Gough and H. Cooper, added their mites ; and an unfortunate paper war was carried on as to the respective claims of B. J. Sayce and W. B. Bolton to be considered the sole, or at all events, the principal originator of the process. As the first announcement of the collodion emulsion process was signed by both, it surely ought to be a case of "honours divided."

During the first ten years after the introduction of collodion emulsion, the excess of soluble salts was removed by washing the emulsion after it had been poured upon the glass plates. It is true that in 1871 Sutton proposed the use of a "corrected" emulsion, in which the proportions of the bromide and the nitrate were so adjusted as to leave neither in excess ; but the practical difficulty of securing this result led to the universal practice of washing the plates after the emulsion had been poured on them.

On January 16th, 1874, Mr. W. B. Bolton showed† that the emulsion might be washed *before* coating the plates. A

The Washed Col-
lodion Emulsion
Process.

* Mr. Sayce has, we are glad to say, once again taken up photography as a recreation ; and is now President of the Liverpool Amateur Photographic Association. This is good news, for photography can ill spare so able and distinguished a worker.

† In the *British Journal of Photography*.

collodion emulsion was made in the usual way, and it was then poured into a shallow dish. Here the ether and alcohol soon evaporated, leaving a semi-solid mass behind, which was cut up into pieces and well washed until all the soluble salts were removed. This pellicle was then dried and afterwards redissolved in ether and alcohol; the final result being an emulsion of the pure silver salt in collodion, uncontaminated by the presence of any other substance. Such an emulsion could be kept in bottles for years, and when required for use it was only necessary to melt the emulsion by placing the bottle containing it in hot water, and then to coat the plates and dry them. A "preservative," usually tannin, might be added to the emulsion, or the plates might be flowed over with it after coating and before drying. By this process Gaudin's ideal was attained, and from 1874 to 1880 the "washed collodion emulsion process" found many friends and admirers.

In the *British Journal of Photography* for October 1st, 1875, an English clergyman, the Rev. Canon Beechey, described what The Beechey Dry-plates. has been considered by many as the "simplest, easiest, and most uniform preparation of collodion dry plates;" a fuller account appeared in the "*British Journal Photographic Almanac*" for 1879. A collodio-bromide emulsion was made in the ordinary way, a few drops of hydrochloric acid being added to produce a little chloride of silver also.

The plates, after being coated, were soaked for a few minutes in flat bitter beer to which pyrogallic acid had been added (thirty grains to one and a half pints), which acted as a "preservative."

Emulsion and dry-plates prepared in this way became an article of commerce; and, indeed, Messrs. Rouch still sell "Beechey Dry-plates," for making lantern transparencies. For landscape work, an exposure of about one minute with a medium stop was necessary with these Beechey plates.

CHAPTER VIII.

GELATINE EMULSION WITH BROMIDE OF SILVER.

Gelatine is an amorphous, brittle, nearly transparent, faintly yellow, tasteless, and inodorous animal substance. It is obtained from the hides of oxen, skins of calves, spongy parts of horns, etc. Bones, when boiled, yield one-third their weight of solid gelatine. Isinglass—or fish-glue—is a form of gelatine obtained from the swimming-bladder of the sturgeon. Ordinary glue is an impure form of gelatine; but fairly pure gelatine, such as is used in the making of jellies, etc., was not manufactured until the beginning of the present century. In 1844, Cox, of Gorgie, near Edinburgh, patented an improved method of making gelatine; and somewhat later Nelson, of Leamington, England, introduced steam as an agent for softening and dissolving this substance. In 1872 Nelson began to make a specially pure “photographic gelatine,” which has ever since been largely used. Foreign makers of repute at the present time are Coignet, of Paris; Heinrich, and Drescher, in Germany; and the “Winterthur” gelatine, of Switzerland. The maker of gelatine uses largely the parings and cuttings of hides from the tan-yard, ears of oxen and sheep, skins of rabbits, hares, dogs, cats, etc., old gloves, parchment, etc. These are steeped in lime-water, washed, and then bleached with sulphurous acid, and washed again. The gelatine is then extracted by means of steam, and run on marble slabs to set. It is next cut up and washed, redissolved, and, lastly, dried in thin sheets on nets. In the cutting, it is the practice of some workmen to lubricate the knives; but this ought to be rigorously avoided, if the gelatine is to be used for photographic purposes, since the fatty matter thus introduced causes “pits” or spots in the plates.

* See Davidowsky's “Practical Treatise on Glue, Gelatine, etc.,” 8vo, 297 pp.; illustrated. Baird & Co., Philadelphia.

Gelatine is, without doubt, a "sensitizer." If we remove silver bromide from one-half of a gelatine emulsion and mix it with collodion, the collodion emulsion will not be nearly so sensitive to light as the remaining gelatine emulsion; the precise cause of this sensitizing action is not certainly known. For one thing, the gelatine wraps round and grips firmly every particle of silver bromide, thus allowing us to use a stronger developer without danger of fogging the plate, than we can do in the case of collodion. But it has also been shown by the German chemist, Knopp, that gelatine is capable of combining with bromine, and it thus assists the action of light in decomposing the silver bromide by attracting and uniting with the bromine given off from the silver salt under the action of light.

Gelatine is insoluble in cold water, in which, however, it swells considerably, increasing in weight. The jelly so formed liquefies immediately when its temperature is raised to about 100 deg. F.

The introduction of gelatine, as a means whereby the sensitive salts of silver could be retained upon a plane surface of glass or paper, followed quickly upon the publication of the "albumen-on-glass" process, discovered by Niepce de St. Victor, in 1848. In Gustave Le Gray's book—translated into English in 1850—he mentions the use of gelatine for such a purpose, the support being coated with iodized gelatine, dried, and then sensitized by immersion in a bath of silver nitrate in the same way as collodion. The gelatine, however, was found to swell or even dissolve in the silver bath. In Germany, Dr. Halleur obtained beautiful images on similarly prepared plates, but they quickly disappeared, a result probably due to the acetic acid (in which gelatine is soluble), then used as an ingredient of the developer.

In 1854, "E. R., of Tavistock," published* full and clear directions for the use of "Swinburne's patent isinglass" (a variety of gelatine) as a substitute for collodion, the exposure required being thirty-five seconds with a diaphragm or "stop" whose aperture was one twenty-fourth of the focal length of the lens employed.

* *Photographic Journal*, vol. i., p. 206.

In 1861, Gaudin used gelatine as one of the substances with which he prepared his "photogene"—the forerunner of emulsion photography.

Poitevin, who had long used gelatine in his printing process, showed, in 1862, how "dry-plates with the bath" could be prepared with it. A curious feature of this method was that bichromate of potash was mixed with the gelatine, after which the plates, coated with the mixture, were exposed to light; "then the bichromate reacts upon the gelatine, and prevents it from creasing* in the water during the subsequent operations."

In 1865, W. H. Smith took out a patent for impregnating the surfaces of wood, canvas, silk, glass, etc., with some resinous solution which would fill up the pores, and then coating the prepared surface with "collodion or gelatine, or any gelatinous substance—mixed with spirits of wine and nitrate of silver, the nitrate of silver being mixed with a chloride, a bromide, or an iodide. After exposure in the camera a toning solution is employed."

In January, 1868, Mr. W. H. Harrison wrote a short article on "The Philosophy of Dry-plates,"† in which he starts by asking a question that we have not yet been able

An Early Experiment with Gelatino-Bromide.

to fully answer: "Why should one organic solution give a rapid plate, and another a slow one?" In experimenting on this subject he made a very weak solution of gelatine in which a "little bromide and iodide of cadmium were dissolved, after which some nitrate of silver was added in the dark. In fact, I wanted to have a solution which would give a good dry-plate, by simply coating a sheet of glass with it." Plates coated with this emulsion were dried and exposed in the camera, and then developed by the alkaline method. "The picture came out very rapidly, and was of great intensity, but the rough and uneven surface of the film made it worthless." When a stronger solution of gelatine was used, no pictures could be obtained, a result possibly due to the weakness of the developer then used. This article of Mr. Harrison's appears not to have been noticed by writers on the discovery of

* Or, as we should say, "frilling."

† *British Journal of Photography*, January 17th, 1868.


the gelatino-bromide process, of which it really contains the germ.

From 1855 to 1870 there were few more active among the workers and writers on photography than Thomas Sutton. He

^{Thomas Sutton}
has a Theory. was rather too fond of theorizing, and was apt to believe that, because he could trace out the steps of a process in his "mind's eye," it must, therefore, be a practical success. Still, the following remarks, taken from one of his contributions to the *British Journal of Photography*,* show that his ideas upon gelatine emulsion were in advance of the time. "There is something very ingenious and promising in M. Gaudin's gelatine emulsion. Used with bromide of silver instead of iodide, it might turn out something grand. The objection to collodion is that, when it is allowed to get dry upon the plate without having been wetted, it dries to an almost impenetrable skin, which the developer has scarcely any power of entering, so that the image is thin and superficial. This would not occur with a gelatine film. There do not seem to be any difficulties in spreading it as there are in spreading albumen, for it is applied hot, and quickly sets. Oxide of zinc gives a structureless and homogeneous film when made into an emulsion with gelatine; bromide of silver ought to do the same. A gelatino-bromide emulsion, slightly alkaline, would be exquisitely sensitive without any free nitrate; and tannin, with the aid of the alkali in the film, would, no doubt, develop it, perhaps to sufficient density, without silver. A great advantage would be that the film could be composed of a capital organifier through its entire substance, instead of having a mere layer of organifier upon the surface. The process is well worth trying; it seems to be right in theory throughout."

Sutton then goes on to describe Gaudin's gelatino-iodide process, after which comes the following paragraph which reads, to us, amusingly enough: "A tourist, employing the above process, would have his bromide of silver emulsion ready made in a semi-solid state, resembling *blanc-mange*; he would melt it by putting the bottle containing it into boiling water; he would then coat his plates at night for the next day, and put them at once into the plate-box to get dry. No washing of the plates

* July 14th, 1871.



DR. R. L. MADDOX.

From a Photograph (copyright) by J. Thomson, Grosvenor St., London.

would be required, and that is one grand feature of the process. The next morning he would hang a yellow curtain before his window, and put them into the dark-slides, developing them at night. He would have no dangerous, explosive, strong-smelling, unhealthy collodion to carry about with him on his travels, and he might pack in a very small compass enough chemicals in a dry state to last him for a tour round the world. What a blessing it would be to be independent of collodion, and at the same time not to have to trust to the keeping qualities of dry-plates!

"It may turn out that I have done well in digging up this old process of M. Alexis Gaudin[†], whose name be exalted as the author of collodion emulsions and photogenes!"

Sutton died shortly after writing the above note, but we can imagine how enthusiastically he would have welcomed the fulfilment of all his hopes—and more, in our modern gelatino-bromide plates which *will* "keep," and whose exquisite sensitiveness is beyond everything that even he imagined.

In the autumn of 1871, Dr. Maddox—so well known for his work in photo-micrography—published in the *British Journal of*

*Photography** "An Experiment with Gelatino-bromide." Thirty grains of gelatine were swelled

in cold water, and then dissolved by heat, four drams of pure water and two drops of aqua regia being added.

To this solution eight grains of cadmium bromide and fifteen grains of silver nitrate were added, forming a fine milky emulsion of silver bromide. Without further treatment this was spread upon glass plates and dried. The plates were tested by exposing them beneath negatives, and gave a faint but clear image when developed with a plain solution of pyrogalllic acid; intensification with pyro and nitrate of silver followed.

Plates fumed with ammonia fogged when treated with pyrogalllic acid. The gelatine emulsion was also used to coat paper with very fair results. In conclusion, Dr. Maddox writes: "As there will be no chance of my being able to continue these experiments, they are placed in their crude state before the readers of the *Journal*, and may eventually receive correction and improvement under abler hands. So far as can be judged, the

Dr. R. L. Maddox
makes Gelatino-
Bromide of Silver
Emulsion.

* September 8th, 1871, p. 422.

process seems quite worth more carefully conducted experiments, and, if found advantageous, adds another handle to the photographer's wheel."

With our present knowledge it is easy to see why Dr. Maddox did not obtain complete success. His emulsion would contain—in addition to the silver bromide—silver nitrate, sodium nitrate and nitric acid (from the *aqua regia*). The presence of the free silver nitrate was the reason why it was possible to develop the plates with plain pyrogallic acid; while the nitric acid acted as a restrainer, and caused the plates to be very slow. By fuming with ammonia the nitric acid was neutralized, but the plates then fogged, because the free silver nitrate was reduced all over the plate by the developer in the absence of any restrainer.

In an appendix to this book, Dr. Maddox has kindly given some account of the way in which he was led to take up the subject, and of the results which he obtained.

CHAPTER IX.

INTRODUCTION OF GELATINO-BROMIDE EMULSION AS AN ARTICLE
OF COMMERCE BY BURGESS AND BY KENNETT.

We have now seen that, between 1868 and 1871, three men Harrison, Sutton and Maddox—had clearly recognized the *possibilities* of gelatino-bromide emulsion; while two of them — Harrison and Maddox — had actually prepared such an emulsion, with—for a first experiment—a marked degree of success. None of these three men, however, followed up their work, and it seems to have attracted little or no notice.

Burgess Advertises
Gelatine Emulsion in
1873.

At least one worker, however, took the hint, and in the pages of the English trade journals for July, 1873,* the following advertisement appeared :

“Mr. J. Burgess begs to announce that as the result of innumerable experiments he has made an *important photographic discovery*, which enables him to prepare dry-plates equal in sensitiveness and superior in many respects to the best wet plates, and that by simply pouring an emulsion (prepared by an entirely new and original method) on the glass and allowing it to dry without any washing or the application of any preservative; thus saving an immense amount of trouble and expense, and what is more important still, securing films of absolute uniformity, of good keeping qualities, and up to the highest standard of excellence.

“In order that any one may test the truth of the above statement, a four-ounce bottle of the emulsion, sufficient to coat four or five dozen quarter plates, will be sent, post-free, for 3s.; and when the new method has been thoroughly tested, if the subscribers are willing to pay one guinea each, a pamphlet will be printed giving an account of the experiments which have

* The exact date is July 18th, 1873.

been tried, and the formula by which the results above described have been realized. Address Mr. J. Burgess, Artist, 207, Queen's Road, Peckham (London)."

Mr. Burgess did not publish, or make known in any way the details of his process, and unfortunately it did not prove a commercial success. But the following quotations from an editorial article* will show its real nature—it was without doubt a gelatino-bromide emulsion :

"We obtained samples and have given the process a trial. Instead of collodion a colloidal substance, without doubt gelatine, is used ; and the sensitive material, which we assume to be bromide of silver, is introduced in such a way as to necessitate no washing. The method of preparing a plate is extremely simple. The emulsion, after being slightly warmed, is merely poured upon the glass and allowed to dry, and—that is all. In exposing, we adhered to the instructions given, viz.: that the exposure should be precisely the same as for a wet collodion plate. On the application of the developer (alkaline pyro), the picture rapidly made its appearance, every detail being visible."

In the next number of the same periodical, the gentleman who wrote under the title of "A Peripatetic Photographer," made the following remarks :

"It appears that a new negative emulsion process has been discovered by Mr. Burgess, in which collodion is displaced by gelatine. This is undoubtedly a very great variation in the existing state of emulsion matters, and at first sight it seems to be an improvement. One has heard so much about the vexed questions in collodion emulsions, the difficulty of getting the right kind of pyroxyline, and the impossibility of succeeding unless it be obtained ; the difficulty of determining whether a little silver or a little bromide is the correct thing to have in excess ; whether the organifier or preservative should consist of gum, tea, coffee, tannin, salicine, cochineal, or gallic acid, and so forth ; that one is glad to try a process in which pyroxyline is not, in which there is neither free bromide or free nitrate, but only the emulsified bromide of silver, and in which preservatives

* *British Journal of Photography*, July 25th, 1873.

and organifiers are rendered of no avail because the whole substance of the film itself is organic. . . . The simplicity of the Burgess process is a charming feature. The emulsion is poured over the clean glass plate, and, when dry, it is fit for use. There is no substratum, no washing, and no preservative; while over and above all, the sensitiveness is said to be equal to that of wet collodion, which, if true, means that plates prepared by the gelatino-bromide process may be used in the studio for the purposes of every-day portraiture."

The objections at this time to the introduction of gelatine emulsion were the "necessity for liquefying the gelatine before it could be used; the equal necessity for laying down each plate in a carefully level position until the film set, and the long time the film took to dry."

In a letter from Mr. Burgess himself,* he states that "the weak point of the gelatino-bromide emulsion is its liability to decompose, as I have found out to my cost lately. In a moderate temperature it will keep for weeks; but in spite of all the anti-septics I am acquainted with, it will ferment if the thermometer rises above 70 deg. Fahr. I have, therefore, determined to confine myself to the making of dry-plates, which will keep any time."

In accordance with this resolve, the first advertisement of "gelatino-bromide dry-plates" appeared on August 29th, 1873, the price being half-a-crown per dozen for quarter plates.

But the time was not ripe for so great a revolution; Burgess's process was not—could hardly be—perfect, and the result was a lack of commercial success, which meant—for the time—failure. But Mr. Burgess never abandoned his belief in gelatine, and in 1880 he wrote, for Messrs. W. T. Morgan & Co., of Greenwich, an anonymous pamphlet, "The Argentic Gelatino-Bromide Worker's Guide," which was the first book devoted wholly to that subject.

In the autumn of 1873, a writer who took for his *nom de plume* "Ostendo non Ostento," contributed a formula (the first which contains alcohol), for the preparation of gelatine emulsion to the pages of the *British Journal of Photography*,† which was the first formula published

Removal of Extraneous substances from the Gelatine Emulsion.

* *British Journal of Photography*, August 15th, 1873.

† October 3rd, 1873.

since that of Dr. Maddox in 1871. But neither of these workers stated the necessity for the removal from the emulsion of the extraneous salts formed by the combination of the chemicals employed.

The first photographer to point out publicly* the need for the removal of all soluble matter from the emulsion was Mr. J. King, of the Bombay Civil Service, who *dialyzed* his emulsion, *i.e.*, placed it in a vessel with a bottom of vegetable parchment or bladder; the whole being half immersed in a large vessel of pure water. Under such circumstances the soluble salts contained in the emulsion pass outwards through the parchment, etc., to mingle with the water. This process was well known to chemists, but it had not been before employed in photography. The editor adds: "The negatives sent by Mr. King, illustrative of his paper, are singularly faultless."

Curiously enough we find side by side with King's communication, a short letter from J. Johnston, in which two very important points are included. The first of these is a direction to use an excess of the cadmium or other soluble bromide in making the emulsion (previous workers had used an excess of silver nitrate), and the second to "let it stand till cold, cut in slices with a piece of thin glass, and wash in distilled water to remove the excess of bromide." This way of washing, or a modification of it, has ever since been employed; it is far simpler and more effective than dialysis.

Burgess's experiments with gelatine emulsion caused Mr. R. Kennett, an amateur residing in Maddox Street, London, to again turn his attention to the subject (it seems that he had experimented with gelatine some years previously). To remedy the grave defect experienced by Burgess, *viz.*, that the finished emulsion would not "keep," Kennett took out the following patent in November, 1873:

"ABRIDGEMENT OF SPECIFICATION OF PATENT:

"A.D. 1873, NOVEMBER 20, NO. 3782.

"A 'substance to be used instead of collodion and other emulsions for photographic purposes.'

"This substance is produced, for use, in a dry or solid condition, and will keep good for any length of time.

* *British Journal of Photography*, November 14th, 1873.

"The compound essentially consists of an aqueous solution of gelatine, together with a bromide, chloride, or iodide; and nitrate of silver.

"The compound is cleared of certain salts, which are formed during the mixing, and then dried. These processes must be conducted in non-actinic light.

"The bromides, chlorides or iodides that may be used are those of potassium, cadmium or ammonium. When the compound is mixed and thoroughly incorporated, it contains a free bromide and nitrate of potash; these are removed or eliminated by pouring the compound into a dish, letting it cool, and cutting into small strips which are washed with many changes of water until all the free salts are dissolved out. The subsequent drying process is accomplished by heating the compound in flat dishes, until it is reduced to a thick paste. When cold, it is stripped from the dishes and placed in suitable frames in a drying-closet in which a circulation of dry air is maintained."

It will be noticed that Kennett's patent is not, as has been stated, for the whole process of gelatino-bromide emulsion making, *that* had been previously published and could not be patented, but for a *method of preserving such an emulsion in a dry and solid state*. To the dried emulsion prepared according to the patent, Kennett applied the name of *pellicle*; when required for use, it was only necessary to dissolve this pellicle in water and coat the glass plates with it.

The following contemporary advertisements are interesting:

"NOTICE.—R. Kennett is now issuing his patent sensitized gelatino-pellicle, in packets containing sufficient to make two, four or six ounces of emulsion, with full instructions for use at the following prices: One, two, and three shillings."*

A complaint against this pellicle was that it gave very thin images, so that we find in a somewhat later advertisement the following addition:

"A special pellicle for obtaining extra density at 1s. 6d., 3s. and 4s. 6d."

At a later date Kennett prepared plates for sale as well as pellicle, and in April, 1876, his advertisement runs:

"R. K. is now prepared with his rapid pellicle plates to photograph interiors of mines, caverns, or any other subject that has hitherto been an impossibility with any other process, wet or dry. . . . R. K.'s latest improvement in his plates admits of greater latitude of exposure, gives more density and brighter shadows, without in the least interfering with their now universally acknowledged wonderful and unprecedented rapidity."

During the years 1874-77, Kennett tried hard to introduce his gelatine pellicle and dry-plates. But photographers seem then to have been a terribly conservative body, and hard to move, and he failed in his endeavour to introduce these articles

* From the trade journals for March, 1874.

into general practice. The following note from an amateur of the first rank, the Rev. H. J. Palmer, will, however, give some idea of their capabilities:†

“As regards exposure, it should be borne in mind that Kennett's *rapid* pellicle and plates are, with good light, really instantaneous. Nothing can surpass the cloud, wave, and street views taken with this preparation; and for babies' portraits it is simply perfection itself. The *ordinary* pellicle is much slower, . . . requiring rather more than half the exposure requisite for a wet plate.”

But at that time all was in vain. The very rapidity of the Kennett plates was one cause of their commercial failure. The workers of ten or twelve years back could not, generally speaking, be brought to believe that a dry-plate could possibly be more rapid than the collodion wet plates which they were so accustomed to manipulate; and Kennett complained bitterly that the purchasers of his emulsion *would* over-expose immensely, and then blame the plates for fog and for yielding thin images. Moreover, the amount of yellow light by which the dark-rooms were then illuminated was in most cases of itself sufficient to “fog” these sensitive gelatine plates.

At the excellent exhibition of photographs held in Edinburgh, under the auspices of the local photographic society in 1876-77, there were 719 pictures from negatives taken by the wet process, as against 105 dry-plate pictures.

Processes Worked
in 1877.

The latter were by the following processes:

Fothergill	15
Gum-gallic	8
Collodio-albumen ..	22
“Dry-plates”	20
Warnerke's tissue.....	3
Beer and albumen.....	15
Coffee	9
Emulsion.....	13

Whether any of the “emulsion” plates were gelatino-bromide we do not know; but in any case this summary of the pictures contributed to one of the most popular exhibitions ever held shows that up to that time, only some ten years ago, the gelatine process was practically not used at all.

† *British Journal of Photography*, March 10th, 1876.

The pages of the English trade journals from 1873 to 1877 contain many useful suggestions and improvements from one or ^{Other Pioneers of} other of a race of experimentalists which then ^{Gelatino-Bromide.} flourished, a race which appears, alas ! to be dying out. In December, 1873, E. W. Foxlee pointed out the value of alcohol as a preservative in gelatine emulsion, showing that it enabled gelatinous solutions to be kept for a long time without undergoing decomposition ; its use also caused the plates to set and dry more rapidly.

Mr. F. Wratten, in August, 1877, showed that the gelatine along with the silver bromide could be precipitated by adding alcohol to the solution containing it, leaving behind in the water all the soluble salts. By this method the necessity for dialysis or washing could be obviated.

In the "British Journal Almanac" for 1874, Mr. W. B. Bolton showed how to form the emulsion in a small portion of the gelatine only, the remainder being added at the close of the operation. In this way the retarding action of the viscid gelatine was avoided. At a later period this method was found very useful.

Of other workers about this time (1873-77) we can only name Messrs. P. Mawdsley, H. B. Berkeley, J. W. Gough, Col. Stuart-Wortley ; and the anonymous contributors, "Amateur," "Franklin," "F. S. K.," and "L. S. D."

CHAPTER X.

GELATINE DISPLACES COLLODION.

M. J. S. Stas, the famous Belgian chemist, published in 1874* certain "Researches on Chloride and Bromide of Silver," in which he pointed out that the latter substance can exist in at least six well-marked physical states, each state having properties peculiar to itself. These researches by Stas contain the key to our present system of obtaining that exquisite sensitiveness to light in bromide of silver, which has of late years effected a practical revolution in photography. But in 1874 the discovery passed unnoticed. Stas was no photographer; and if any photographer studied his paper—which is doubtful—it did not strike him that here was the germ of a process which might surpass all that had gone before. The following translation includes the (to photographers) most interesting portion of Stas's paper:

"*Modifications of Silver Bromide.*—This bromide assumes a large number of physical states of different appearance:

- (1.) The white flaky state. }
- (2.) The yellow flaky state. }
- (3.) An intense-yellow powdery state. }
- (4.) A pearly-white powdery state. }
- (5.) A yellowish-white granular state.
- (6.) A pure intense-yellow crystallized or melted state.

"The white and yellow flaky forms (1 and 2) are produced by mixing cold aqueous solutions of any suitable silver salt with hydrobromic acid or some soluble bromide.

"These two forms may be converted into the powdery or pulverulent modifications (3 and 4) by shaking up well with water. When we pour either the flaky or the powdery bromide of silver into boiling water, it is changed instantly into a very fine powder, which is the granular bromide (No. 5). This may be produced directly, by adding to a boiling solution of silver nitrate (one part to 1,000 of water) a sufficient quantity, also boiling, of a very weak solution of ammonium bromide. The granular powder resulting from the breaking up of the flakes, is of a dull yellowish-white, while that which is produced by the transformation of the pulverulent variety, or which is formed

* *Annales de Chimie*. Fifth Series, vol. iii., p. 289.

with the aid of very weak solutions, is of a *shining* yellowish-white. Under the influence of a boiling prolonged for several days (the water being constantly replaced), the dull granular bromide is modified; it becomes more and more divided to the point of remaining completely in suspension, and rendering the water white. The suspended bromide presents, in this case, a shining reflection, and is not deposited for a considerable length of time. Separated from the liquid it is of a pearly-white. The pearly bromide becomes a pure intense-yellow by contact with a concentrated solution of ammonium bromide. This change is, so to speak, instantaneous.

"The granular bromide, either dull or shining, and the pearly-white modification of it, resulting from the action of boiling water on the first two, are the most sensitive substances to light with which I am acquainted.

"It is sufficient to boil them for two or three seconds in water over the flame of a Bunsen burner, burning with excess of air, to cause them to blacken. Because of this extreme liability to change, these experiments would not have been possible if they had not been carried on with exceptional precautions.

"Thus the production of the granular bromide, and its change into the pearly-white bromide, were effected in an apparatus which admitted no light. The manipulation of these bodies took place in the dark, and they were examined in a yellow or in a diffused light.

"The pearly-white bromide passes by fusion into the pure intense-yellow state."

Thus, fourteen years ago, Stas discovered and made known that "the most sensitive substance to light" could be obtained by the action of heat upon silver bromide. Yet his discovery fell on barren (photographic) ground, and it was not till 1879 that Monckhoven showed how this work of Stas explained the results obtained by Bennett and others.

Certainly every photographer ought to study chemistry.

The report of a meeting of the South London Photographic Society on March 7th, 1878, states that "a number of gelatine negatives were exhibited by Mr. Bennett, one of

Bennett obtains
Great Sensitiveness
by "Stewing" the
Emulsion.

them being an interior of a room, taken by ordinary gaslight, the exposure being one hour;" others were "Boat scene on river, exposure by drop-shutter—say twentieth of a second," and "River scene, exposure four seconds," etc. The experts who examined these negatives considered them sufficiently surprising, and a general appeal was made to Mr. Charles Bennett—an amateur photographer and member of the well-known firm of London hatters—to publish the process by which he had obtained such (for that time) marvellous results. It is greatly to Mr. Bennett's honour that he at once acceded to this request, and gave to the photographic

world on March 29th, 1878,* the details of a method which was destined to revolutionize our mode of working. When the process was studied, the essential point was seen to be the use of *heat*. The different solutions were to be made at a temperature of 90 degrees (Fahrenheit), and, after mixing, the temperature of the emulsion was to be maintained at 90 deg. (by placing the bottle containing it in a vessel of hot water) "for two, four or seven days, according to rapidity required." During this slow and long-continued heating, the silver bromide gradually assumed the "granular" state of Stas, and became exquisitely sensitive to light. Bennett says, "if washed after two days, the emulsion is rapid and dense; in four days, more rapid and less dense—quick enough for any drop-shutter known; with some that I kept for seven days, with drop-shutter and dull February morning, pebbles close to the camera were perfectly exposed. The negative was thin under ammonia, but bore intensifying to any extent."

The commercial importance of Mr. Bennett's discovery was soon seen, and the trade journals for April of the same year contain advertisements from Peter Mawdsley, of the Liverpool Dry-plate Company, of "Bennett Plates" at three shillings per dozen ($\frac{1}{4}$ -plates), and from Messrs. Wratten & Wainwright, of the "London Gelatine Dry-plates and Pellicle;" the latter firm at the same time offering collodion emulsion for sale, the two processes thus overlapping.

Gelatine, however, now soon beat collodion out of the field, although the years 1878-80 must be considered years of transition.

In a remarkable communication to the Photographic Society of Great Britain in 1876,† Lieut.-Col. Stuart-Wortley describes

the preparation of a gelatine emulsion at a temperature of 180 deg. Fahr., adding, "you will notice that I make a considerable alteration from any instructions that have hitherto been given for the preparation of a gelatine emulsion, as I work at an exceedingly high temperature with the object of forming my emulsion at once, instead of spreading the formation over many hours, as, I believe, other workers do. I get the most perfect films by this method of working, and I am

* See *British Journal of Photography*.

† Reprinted *British Journal of Photography*, June 30th, 1876.

certain that the above temperature has no injurious effect whatever on the gelatine." The only reason we can think of why Col. Wortley did not attain complete success with this method was that he did not maintain the high temperature for a sufficient length of time; he says he allowed the bottle containing the emulsion to stand "for a quarter of an hour in the hot water," which would hardly be long enough at 180 degrees to permit the conversion of the bromide of silver into the sensitive "granular" molecular state.

After general attention had been drawn to the gelatino-bromide process in the spring of 1878 by Bennett's remarkable work, it was soon found that the prolonged emulsification required in his method—stewing for seven days at 90 deg.—was not only very tedious and troublesome, but that—more especially in summer—it produced other evils, especially the decomposition of a part or the whole of the gelatine. Bearing Stuart-Wortley's experience in mind, it was not difficult to see that a possible remedy might be found in cooking, or digesting, the gelatine for a shorter time, but at a much higher temperature. This seems to have been done by several workers, but it was first publicly announced by Mr. Geo. Mansfield at a meeting of the Photographic Society of Ireland, in August, 1879,* who "drew attention to the fact that the long and troublesome process of digestion might be obviated by forming the bromide of silver in a very weak solution of the gelatine, which was then *boiled* for about ten minutes, the remainder of the complement of gelatine in the formula being added when the first solution had cooled down to about 100 deg. F."

The other point here recommended—to emulsify the silver bromide in a small portion of the gelatine only, the remainder being added *after* the cooking—was a repetition of the advice given by W. B. Bolton in 1874; it is the plan now generally adopted.

In May, 1879, Captain Abney, to use his own words, "showed that a good emulsion might be formed by precipitating silver bromide by dropping a solution of a soluble bromide into a dilute solution of silver nitrate in water and glycerine. The supernatant

* *British Journal of Photography* for August 22nd, 1879.

liquid was decanted, and after two or three washings with water, the precipitate was mixed with the proper amount of gelatine." The object of this method was to save the trouble of washing the emulsion.

In connection with this note, it is curious to turn back to a paper written by Thomas Sutton, in February, 1874,* where he writes :

" Mix aqueous solutions of silver nitrate and potassium bromide. White silver bromide will be immediately formed and quickly precipitated. Wash the precipitate repeatedly in water in order to remove the potash nitrate, etc. . . . Mix the dry silver bromide with a little glycerine and add to it a hot solution of gelatine."

It will be seen that the two methods are nearly identical. But, alas! Sutton only asks " Why not do this?" He did not actually try the experiment, or he might perhaps have anticipated Abney by five years.

Dr. D. von Monckhoven, of Ghent, born 1834, died 1882, was an excellent chemist and good " all-round " man of science, who devoted himself chiefly to the scientific side of photography. His " General Treatise on Photography " (1863), and " Photographic Optics " (1868), were leading books in their day, and are still useful. His solar enlarging apparatus (1864) is well known, and for many years he carried on a large business in Belgium for the manufacture of carbon tissue, and afterwards of dry-plates.

A We have seen that in the ordinary methods of preparing a gelatine emulsion, a great deal of washing is necessary in order to remove the superfluous salts. When Monckhoven tried this plan he found that " the water of our good city of Ghent is so chalky—caused by the nature of the soil—that I was obliged to find some method of doing away with washing my emulsions." The plan which he hit upon* was to mix with the fluid gelatine, first, carbonate of silver, and then hydrobromic acid, in the precise quantities in which they would combine chemically with

* *British Journal of Photography*, February 13th, 1874.

* Monckhoven's paper, read before the Photographic Society of France, in August, 1879, was reprinted in the *British Journal of Photography* for August 8th of the same year.

one another. The result of their interaction was the formation of silver bromide (which remained suspended in the gelatine), carbonic acid gas which escaped, and water which was harmless.

Owing, however, to the practical difficulties of the process, which required a skilled chemist to carry it out successfully, and the expense of the ingredients, this method was never employed commercially.

In the same paper in which Monckhoven published the method described above, he stated that he had obtained the

sensitive green form of silver bromide by the addition of ammonia, and without the aid of heat.

Monckhoven uses
Ammonia to Obtain
a Sensitive Gelatine
Emulsion without
the Aid of Heat.

In an admirable lecture, delivered in October, 1879,* before the Belgian Photographic Association, after describing the formation of an emulsion in the ordinary way by the addition of silver nitrate to a gelatinous solution of ammonium bromide, Monckhoven adds: "Now pour in the pure ammonia and shake up well the solution. The ammonia exercises quite a special action here; its effect is to render the emulsion ready to be used in a few minutes; or, if great sensitiveness be required, it can be obtained in a few hours instead of days, and thus decomposition of the gelatine is avoided."

Some remarks in the same lecture on one of the most frequent causes of failure in out-door work are so valuable that we reproduce them also. "I am certain that I shall not make a great mistake in saying that scarcely one dark-slide of a camera protects the plate as it ought to do. Light enters, especially when the shutter of the slide is pulled out to expose the plate. I have frequently proved this in the following manner: I have exposed a plate in the camera without taking the cap off the lens; and in developing, the entire plate has been fogged. You must also make certain that light does not enter through the holes of the Waterhouse diaphragms; nor round the ring upon which the lens is screwed.† I am accustomed in the open air to completely envelope my camera with a large focussing cloth, allowing only the lens to protrude. I even open the

* Reprinted *British Journal of Photography*, October 17th, 1879.

† Nor round the cap of the lens. Look for these defects in bright sunshine, by removing the focussing glass, and then putting head under focussing cloth; lastly, remove lens and look through lens aperture at dark-slide.—W. J. H.

dark-slide under this cloth. . . . When I first began my experiments on gelatino-bromide, I could obtain nothing but fogged plates. I wrote to the maker, and he informed me that the cause of my failure was owing either to the red glass of my dark room, or the state of my dark-slide. I reglazed my window with proper glass, and over-hauled my dark-slides. As soon as I took these precautions I had no more trouble with fog."

Monckhoven's "ammonia method" of preparing emulsion at once came into use commercially, and is employed by many manufacturers at the present day. Plates prepared in this way do not, however, retain their good qualities so long as those coated with emulsion which has been simply boiled.

CHAPTER XI.

HISTORY OF PHOTOGRAPHIC PRINTING PROCESSES.

The first successful experiments in photography were those in which copies of opaque or semi-opaque objects were obtained by placing them upon sensitive paper and exposing the whole to light. The parts of the paper not protected from the light were blackened by it, and when the object was removed, its position and outline were shown in white upon a black ground. Such a process was, of course, only suitable for flat and thin bodies, as plants, engravings, etc.; and those of varying degrees of opacity gave the best results, because a similar gradation of shade was obtained in the copies. As a sensitive surface, Schulze used a mixture of chalk and silver nitrate in 1727, and Thomas Wedgwood silver nitrate spread upon paper or leather in 1795; Davy in 1802 found that silver chloride gave better results than silver nitrate.

The first person to introduce a photographic copying process of real value was Fox-Talbot. He commenced his experiments, it appears, in 1834, using silver nitrate upon paper; but, soon discovering that silver chloride mixed with a little silver nitrate was far more sensitive to light than either of these substances alone, he employed it with great success for copying purposes; and even, as we have described in a former chapter, succeeded in obtaining pictures within a camera by its aid. These camera-pictures, however, were *printed right out*, by the action of light, and this caused the exposures to be very long—from half an hour to an hour. It was not till Talbot discovered a method of *development* (in 1841) that his process became a practical success as far as taking pictures in the camera was concerned.

To this copying process upon paper coated with certain salts

of silver, Talbot applied the name of "photogenic drawing," and the term might well be retained for this still useful method of copying natural objects by super-position. In the first description of his process, Talbot writes:* "I dip superfine writing paper in a weak solution of common salt, and wipe it dry. I then spread a solution of nitrate of silver (60 grains to the ounce) on one surface only, and dry it at the fire. By alternately washing the paper with salt and with silver, and drying it between times, I have succeeded in increasing its sensibility. For fixing the images, after having tried ammonia and several other reagents with very imperfect success, the first thing which gave me a successful result was the iodide of potassium, much diluted with water. If a photogenic picture is washed over with this liquid, an iodide of silver is formed which is absolutely unalterable by sunshine. The specimen of lace which I exhibited to the Royal Society, and which was made five years ago, was preserved in this manner. But my usual method of fixing is different from this. It consists in immersing the picture in a strong solution of common salt, and then wiping off the superfluous moisture and drying it."

Talbot's first application of his process was to the copying of flowers and leaves selected from his herbarium. In those early days of the art, the vast saving of time and trouble effected seems to have struck the observers very forcibly. In the same memoir Talbot remarks: "It is so natural to associate the idea of *labour* with great complexity and elaborate detail of execution, that one is more struck at seeing the thousand florets of an *Agrostis* depicted with all its capillary branchlets (and so accurately that none of all this multitude shall want its little bivalve calyx, requiring to be examined through a lens) than one is by the picture of the large and simple leaf of an oak or a chestnut. But in truth the difficulty is in both cases the same. The one of these takes no more time to execute than the other; for the object which would take the most skilful artist days or weeks of labour to trace or to copy is effected by the boundless powers of natural chemistry in the space of a few seconds."

Applications of
Photogeny.

* *Philosophical Magazine*, 1839, p. 209.

“To give an idea of the degree of accuracy with which some objects can be imitated by this process, I need only mention one instance. Upon one occasion, having made an image of a piece of lace of an elaborate pattern, I showed it to some persons at a distance of a few feet, with the inquiry, whether it was a good representation: when the reply was, “that they were not to be so easily deceived, for that it was evidently no picture, but the piece of lace itself.”

It is to be regretted that “photogenic drawing” seems to have almost fallen into disuse. With our ordinary sensitized paper, or with paper prepared in the way described by Talbot, very beautiful copies of suitable natural objects—ferns, for example—can be obtained. The process forms a capital introduction to photography, and is especially suitable for ladies and children. The copies obtained can be used for many decorative purposes.

In Talbot's first communication (1839) he clearly recognizes the valuable fact that the pictures obtained by his process are *negatives*, from each of which any number of *positives* can be obtained by printing. Thus he writes: “In copying engravings, etc., by this method the lights and shadows are reversed, consequently the effect is wholly altered. But if the picture so obtained is first *preserved*,* so as to bear sunshine, it may be afterwards itself employed as an object to be copied; and by means of this second process the lights and shadows are brought back to their original disposition.” But the inventor did not then think of employing photography as a means of portrait-taking, except indeed for “the making of outline portraits, or *silhouettes*. These are now often traced by the hand from shadows projected by a candle. But the hand is liable to err from the true outline, and a very small deviation causes a notable diminution in the resemblance. I believe this manual process cannot be compared with the truth and fidelity with which the portrait is given by means of solar light.”

But the improvements patented by Talbot in 1841, with others added by Cundell in 1844,† so improved the *Calotype*

* *i.e.*, fixed.

† *Philosophical Magazine* for May, 1844.

Process (as Talbot then styled his method) that it became applicable to portraiture, and the inventor granted licenses to several professionals to use it for likeness-taking. The first of these was Mr. Henry Collen, of London, of whose "beautiful Talbotype miniatures" a contemporary reviewer remarks* that "touched up and improved, they show how much is yet to be accomplished by the application of artistic skill to the productions of the solar pencil."

Talbot believed strongly in the suitability of photography for book illustrations, and in 1844-46 he issued a series of twenty-four plates (positive prints from calotypes) under the title of the "Pencil of Nature." The subjects include the Boulevards of Paris, Bridge of Orleans, Lacock Abbey, etc. In only one picture are figures introduced. In all existing copies of this valuable book which we have examined, the photographs are more or less faded, yellow outlines only being visible, though a few of the photographs are still of a purplish hue in the central part. A description of the methods employed in the printing is given by Mr. Malone in the *Liverpool and Manchester Photographic Journal*, 1857, p. 270; and 1858, p. 23.

In 1846, Talbot published a similar book, entitled "Sun Pictures in Scotland;" and a specimen of his work was given in the *Art Journal* for June 13th, 1846. The first scientific periodical which contained a photograph as an illustration was, we believe, the *Quarterly Journal of Microscopical Science* for April, 1853. Two Scotch photographers, Messrs. Hill and Adamson, prepared large collections of Talbotypes, about 1850, which were sold at prices of £40 and £50 each.

In later years, more especially about 1866-70, many books, some of them very expensive, were published, in which photographs of works of art, pictures, scenery, etc., formed the principal features; but a radical defect in most or all of these was the gradual fading and yellowing of the pictures, so that purchasers became very chary of paying from three to ten guineas for such unstable productions. During the last few years, however—say since 1883—the introduction of such permanent processes as carbon and platinotype, together with

* *North British Review*, 1847, p. 479.

the advance of the photo-mechanical methods, bid fair again to bring photography to the front, and to give it that leading place to which it is entitled as a mode of illustrating books.

It may be interesting to add here that the first public exhibition of photographs was held under the auspices of the Society of Arts, in their room in the Adelphi, London, on December 22nd, 1852. This exhibition resulted in the formation of the Photographic Society of London, on January 30th, 1853; and this society has ever since held an annual exhibition of photographs in London.

Fox-Talbot's method of printing upon ordinary white paper has come down almost unaltered to the present day. The standard size of the paper employed is $23\frac{1}{2}$ by 17 inches, and it is nearly all made at the little towns of Rives in France, and Saxe in Germany. Thirty years ago the principal makers of photographic paper were Hollingworth and Sanford in England, and Canson in France; but for some reason or other the two towns above-named now enjoy a practical monopoly. The chief points to be attended to in making paper for use in photography are the avoidance of metallic particles—such as might come from buttons in the rags, etc., and of the hyposulphite of soda which is largely used by ordinary paper-makers in the process of whitening the paper, but which is very destructive to photographs.

The paper is "salted" by being floated for three minutes upon the following solution :

Water	500 parts.
Ammonium chloride	8 parts.
Sodium citrate	10 parts.
Gelatine	1 part.

It is then dried and sensitized by being floated for the same length of time upon a solution of silver nitrate, fifty grains to the ounce; when dry it is ready for use.

Plain salted paper is most useful where the photograph is to be afterwards coloured, as it gives a dead surface which is easy to work upon; but, unless special precautions are taken, the image has a gray and sunken-in appearance. To remedy this, a quantity of albumen (white of egg) is now almost always mixed with the first or "salting"

Printing on Albumenized Paper.

solution. This fills the pores of the paper and keeps the sensitive salt of silver (silver chloride) which is subsequently formed by floating the prepared paper upon silver solution, upon the surface; its gloss is also considered to add to the appearance of the picture. The introduction of albumenized paper has been credited to Fox-Talbot, but the first description of it which I have been able to find in English is in the third edition of "Hunt's Manual of Photography" (preface dated December, 1852), where it is given as an extract from a book by the French investigator Le Gray. There is another account of the process, by H. Pollock, in the journal of the (London) Photographic Society for July, 1853.

Papers tinted pink, mauve, etc., were introduced in 1863; and enamelled paper (to give greater brilliancy) about the same time.

Thomas Sutton patented (October, 1862) a plan of giving paper a preliminary coating of india-rubber dissolved in benzole, before albumenizing it. This completely prevented the solutions sinking into the paper and caused the prints to be more vigorous and brilliant. Such paper was manufactured for several years by Messrs. Ordish in London.

In 1866, A. Taylor used* a solution of bleached shellac in phosphate of soda to prepare the paper instead of albumen. Great permanence was claimed for this method.

In 1842, Dr. A. S. Taylor (and A. Smee and Mr. Collen, about the same time) used ammonio-nitrate of silver to sensitize plain salted paper with good results. Albumenized paper cannot be sensitized in this way, inasmuch as it is dissolved by the ammonio-nitrate.

In 1842, Sir John Herschel devoted much time to experiments upon printing on paper soaked in the colouring matter extracted from the petals of many species of flowers. The petals were crushed in a mortar, a little alcohol added, and the pulp was then strained through a cloth. The liquid so obtained was then spread upon paper with a brush and dried in a dark place. Poppies, violets, roses, etc., were tried with success; but the exposures required to produce a

Printing with the
Juices of Flowers.

* *Photographic News*, June 15th, p. 280.

visible impression were very long, extending over weeks, or even months.*

More than twenty years ago Palmer and Smith showed† how paper coated with an emulsion of gelatino-chloride of silver could be used for photographic printing. In 1881, Dr. Eder and Capt. Abney published‡ further details; while W. T. Wilkinson gave a number of practical details in the *British Journal of Photography* for the same year.§

In 1886 the firm of Liesegang, of Dusseldorf, in Germany, prepared a paper coated with gelatino-citro-chloride of silver, which, under the name of "Aristo," or aristotype paper, has found favour, especially for printing from weak negatives. The picture is "printed out," as upon ordinary albumenized paper, but it only requires about one-third of the time; it must then be toned and fixed. A similar paper is manufactured by Obernetter.||

The albumenizing of paper is so troublesome an operation that it has been left, almost universally, to the manufacturer. But it is the custom with most professional photographers and with many others to sensitize for themselves the already salted and albumenized paper, by floating it upon a bath of silver nitrate. Unfortunately, it is the case that paper sensitized in this way loses its colour rapidly. It ought, in fact, to be used as soon as it is dry. The convenience of a paper which could be purchased *ready sensitized* and which would *keep* for a reasonable period, was doubtless recognized at an early date; and such an article came into use commercially in 1869, and is now largely used; yet, strange to say, the exact method of preparation has been successfully kept a "trade secret."

Mr. J. C. Hopkins, in the *Photographic News* for 1873, stated

* See Herschel "On the Action of the Solar Spectrum on Vegetable Colours;" Philosophical Transactions, 1842, part ii., p. 181.

† *Photographic News*, 1866, p. 24, 36.

‡ Ibid, p. 400.

§ Pp. 140, 168.

|| This well-known Munich photographer has died since this sentence was written, but the paper will doubtless be continued to be issued under his name.

that ordinary sensitized paper keeps well if placed when nearly dry between sheets of blotting paper which have been soaked in carbonate of soda solution (thirty grains to the ounce of water), and then dried. Pads of carbonated blotting paper placed behind the negative in the printing-frame, also answer well.

Captain Abney washes the sensitized paper (to remove the free silver nitrate) and then dips it into a weak solution of either potassium nitrite or potassium sulphite.

Mr. W. Bedford sensitizes the paper on a neutral bath, and then floats the face upon a bath containing thirty grains each of citric acid and of silver nitrate to the ounce of water.

Another method is to float the *back* of the paper, after sensitizing, upon a weak solution of citric acid. The addition of this substance to the printing bath was recommended in 1863* by Colonel Stuart-Wortley. It is believed that much of the ready-sensitized paper made at the present day is sensitized upon a nitrate of silver bath to which citric acid and a little gum has been added. M. Baden, of Albona, found that by washing sensitized paper (to remove the free nitrate of silver) the paper would keep for a long time; but, before using, it *must be fumed with ammonia*. This method was introduced into England in 1870, by Colonel Stuart-Wortley.†

Ammonia fuming has been used with great success in America (where it was introduced in 1863), but has not met with much favour in England, although its effects are undeniably good, and "old" samples of paper may often be made available for use by simply fuming them.

It is a common practice with artists to "improve" any landscape which they may be engaged in painting by the omission of such portions as would tend to mar the effect of the finished picture, replacing them by objects sketched in another locality. Figures, too, are introduced where and as required. Such a power of selection is generally considered to be beyond the means of the photographer; but that it has been possible to produce a single print or finished picture by combining two or more negatives has been

Combination Printing.

* *Photographic Journal*, February 16th, 1863.

† *British Journal of Photography*, p. 337.



BEHROSE & SONS. PHOTO-TINT.

LONDON & DERBY.

Henry P. Robinson

known and successfully practised for more than thirty years.

At an exhibition held in connection with the meeting of the British Association in Glasgow, in 1855, Messrs. Berwick and Annan, of that city, exhibited a picture "printed from two different negatives"—a figure introduced into a landscape. The process was exactly that subsequently used by Mr. H. P. Robinson, which we have described further on.

On April 5th, 1858, O. Sarony patented a means of "producing a positive portrait by means of two or more negatives." The first part of the "patent" is practically Berwick and Annan's method, but he adds, "these improvements may also be effected by taking up the different portions of the collodion film from the glass of one or more negatives and laying them down on a glass or in the printing frame in their proper relative positions, and then printing from them without marks."

This reminds us of the plan adopted by many in 1885 (when paper negatives came into general use), of cutting out the parts required from each negative with a sharp pair of scissors, and fitting them accurately together on a sheet of glass.

The first man to attract general attention to combination printing was Oscar G. Rejlander (born 1803, died 1875), a Swedish artist, who practised photography at Wolverhampton; and who in 1857 sent a very large photograph called "The Two Ways of Life" to the famous Manchester Exhibition of that year. Thirty negatives were employed in printing this photograph,* each being laid in turn upon the sensitized paper and exposed to sunlight, while the rest of the paper was covered over with black velvet. As an example of ingenuity and power to overcome difficulties, this picture has never been surpassed.

In the next year, 1858, Mr. H. P. Robinson produced his famous combination picture (printed from five negatives), entitled "Fading Away," a consumptive girl surrounded by grieving friends; which was exhibited in January, 1859, before the London Photographic Society.† It attracted great attention, and much

* "On Photographic Composition; with a Description of 'The Two Ways of Life,'" by O. G. Rejlander. *Photographic Journal* for 1858, p. 191.

† Mr. Robinson's first description of his method is contained in a paper printed in the *Photographic Journal* for April 16th, 1860; but his method is fully described in the book on "Silver Printing" (chap. xiv.), which he wrote in conjunction with Capt. Abney.

difference of opinion was excited as to the propriety of photography being employed to delineate such a subject. But all opposition was stopped by the splendid series of photographs with which Mr. Robinson followed up his first success, including "Bringing Home the May," 1863 (size 40 by 15 inches, printed from nine negatives), "Wayside Gossip," "A Merry Tale," and a score of others, the result of the artist's noble resolve "to do something, at least one picture every year, for the love of art and of photography." Mr. Robinson's method may be called the "stopping-out" plan. As many negatives as are required are taken, and then from each is stopped out in some way or other—as by painting over with black varnish, or gumming-on opaque paper—all but the part required. The sensitive paper is then printed in turn under each negative.

This is merely a variety of combination printing. In the early days of photography, about 1855 say, a perfectly white clear sky was much admired. In the very first
 Printing-in Clouds. number of the *Photographic Journal* (March, 1853), Sir W. J. Newton suggests the addition of clouds by the use on the skies of dense negatives of cyanide of potassium; or of Indian ink upon thin ones. About 1862 the desirability of adding clouds to landscape prints was generally recognized, and at first this was done by painting or dabbing upon the back of the negative. Then separate cloud-negatives were taken; and these "natural clouds" printed-in by methods which are well explained by V. Blanchard in the *Photographic News* for September 4th, 1863.

This mode of shading-off the light so as to cast a halo round the picture is described by Mr. Latimer Clark in the *Photographic Journal* for December, 1853. He placed a sheet
 Vignetting. of some opaque substance having a hole cut in the centre, in front of the negative and about half-an-inch above it. The printing frames so fitted were placed on a light stage which was made to revolve by means of a bottle-jack. Vignetting came into extended use in 1857-58. Mr. Forrest, of Liverpool, was the inventor of the stained and ground vignetting-glasses now so commonly used.

"Toning," as photographers call it, is practically gilding the

image formed by light, either by a thin deposit of gold upon the silver of which the image is composed, or by the replacement of part or the whole of the silver by gold. In 1841* the French scientist, Fizeau, toned daguerreotypes by applying to the heated surface of the silver plate a mixture of hyposulphite of soda and chloride of gold.

The early paper prints of Talbot were of a foxy-red or bistre tint, due to the colour of the deposited silver in a finely divided state, modified by the "size" with which the paper was impregnated. By using continuously the same fixing bath (adding crystals of hypo occasionally to keep up its strength), or by placing such prints in an "old hypo bath," *i.e.*, one already impregnated with chloride of silver and which had been allowed to stand for a week or so, or until a black deposit was seen to form, the prints were changed in colour from red to brown or black. This process was largely used between 1848 and 1855; it was really "sulphur toning," the black colour being due to the formation of sulphide of silver. A sulphuretted organic salt of silver was, however, also formed, and under atmospheric influences this speedily altered, reacting in addition upon the other substances present. At this period, moreover, the necessity for a thorough removal of the hyposulphite of soda used in fixing was not generally recognized, and its presence contributed to a rapid fading of the picture. It is doubtful whether a single photograph taken before 1855 could be produced to-day which has not undergone serious, and for the most part fatal deterioration.

Very valuable information on these points is contained in a report of a committee of the London Photographic Society,† appointed in May, 1855; His Royal Highness the Prince Consort (who always took a lively interest in photography), contributing £50 towards the expenses of the inquiry.

The proved advantages of the addition of chloride of gold to the hypo solution for toning daguerreotypes naturally led to its trial for the same purpose for toning paper prints. In

* Communicated to the Academie des Sciences on May 15th and 24th, 1841.

† *Photographic Journal*, vol. ii., page 251; see also "Reports of Juries," Exhibition of 1862.

Gustave Le Gray's book. (published in France in 1849), he writes: "I obtain also fine velvet-like tints by putting the photograph (when taken out of the hyposulphite of soda), upon a bath of salt of gold, using fifteen grains of the chloride of gold to one pint and a half of distilled water." In this method we see that toning followed fixing; and such was for a long time a general custom, being recommended, for instance, by Hockin, in 1860, in a book† which had a very large circulation. A disadvantage of Le Gray's method was that the prints were very much weakened by the toning process, necessitating a great amount of over-printing to commence with. The gold solution was always acid.

In 1855, Thomas Sutton recommended‡ the use of an acid bath of *sel d'or* for toning. *Sel d'or* is a compound of chloride of gold and hyposulphite of soda, formed by mixing concentrated solutions of the two salts, and then precipitating the double salt by the addition of alcohol. The print was washed before toning, and fixed afterwards. This process became popular; but it was ultimately abandoned because—as there was no means of knowing how much gold remained in the bath at any given time—it degenerated in the hands of most photographers into mere sulphur toning, the bath being kept in use long after the gold was exhausted.

The classical investigations of Hardwich, in England,§ commenced in 1854, and of Davanne and Girard, in France (1855 and following years), laid down the lines upon which the print ought to be treated after its removal from the printing frame; and minor investigators filled in the details.

In 1855, Mr. Waterhouse, of Halifax, the inventor of the removable diaphragms which bear his name, introduced a most valuable improvement in toning processes by the use of an alkaline (or, at all events, strictly non-acid) solution of the chloride of gold. The alkali used by Waterhouse was carbonate of potash, and he "added more or less of it according to the tint desired." This process was first published in 1856 in

† "Practical Hints on Photography," by J. B. Hockin.

‡ *Photographic Journal*, vol. ii., p. 133.

§ *Photographic Journal*, vol. ii., pp. 35, 268; vol. iii., etc.

the third edition of Hardwich's "Photographic Chemistry," and was subsequently recommended by Mr. Hardwich in a paper read before the London Photographic Society.* Soon the changes were rung on all the alkalies; Hardwich (in 1856) substituted carbonate of soda for the potash "as being a salt more easily obtainable;" within the next year or two the Abbé Laborde (in France) and Hannaford† (in England) used acetate of soda; and in 1858 Maxwell-Lyte‡ recommended the phosphate of soda, his formula being

"Terchloride of gold	10 grains.
Phosphate of soda (pure)	3 drams.
Distilled water	1 pint."

At that time the toning process was commonly called "colouring" — thus Maxwell-Lyte's paper is entitled, "A Process for Colouring Positives;" in a postscript to it he adds, "the phosphate of soda may be replaced by common borax." From this time (1858-59) the principal toning processes may be said to have remained practically unchanged to the present day.

The only thing deplored by Wedgwood and Davy in 1802 was their inability to discover any satisfactory solvent for the salts of silver—the muriate (or, as we should now call it, the chloride) and the nitrate — which they employed.

In 1819 Sir John Herschel pointed out§ the ready solubility of silver salts in the alkaline hyposulphites. From this time the problem of photography was solved; but, unfortunately, Niepce, Daguerre, and Talbot seem to have known nothing of the work already done by Davy and by Herschel.

In 1839 Daguerre fixed his iodized silver plates by washing them either with ammonia or with a strong solution of common salt.

At the same time Fox-Talbot used common salt, and also solutions of bromide of potassium and iodide of potassium.

Immediately Herschel heard of Daguerre's and of Talbot's successes in photography (in January, 1839), he remembered

* *Photographic Journal*, vol. v., p. 95.

† *Ibid*, vol. vi. for 1859, p. 83.

‡ *Ibid*, vol. v., p. 112.

§ *Edinburgh Philosophical Journal*.

the substance whose solvent power for silver salts he had announced in 1819 (hyposulphite of soda), and the directions which he gives for its use in a valuable paper, read before the Royal Society on February 20, 1840, have ever since formed the foundation of our ordinary method of fixing photographs on paper. Herschel writes, after washing in pure water, the paper must be dried, "and then brushed over very quickly with a flat camel's-hair brush, dipped in a saturated solution of the hyposulphite, first on the face, then on the back. This having remained on it till the paper is completely penetrated with it, it must be washed off with repeated and copious effusions of water, aided by a soft sponge, with a dabbing motion, often turning the picture until the liquid comes off without the slightest *sweetness*. The photograph is then fixed, and may be dried and put by; but to make it quite secure it is best to repeat the process, and if the paper be thick, even a third time. The hyposulphite of soda and silver being liable to spontaneous decomposition, it is necessary to be very careful in washing away the very last traces of this salt."

It would have been well if the early photographers—under which phrase we include the workers before 1855—had paid more attention to Herschel's remarks; then we should have had more of their work remaining. Indeed, the men of to-day might remember the advice as to sponging and dabbing—Capt. Abney strongly recommends this plan—for by applying pressure in this way to the prints a photograph may be more thoroughly freed from hypo in two or three hours than by days of mere soaking; the result too, being a more brilliant print.

In the face of Herschel's work, it is difficult to understand how Fox-Talbot could have included as part of a patent for "Improvements in the Calotype Process," which he took out in 1843, a claim to "give increased whiteness to calotype and other photographic pictures, and at the same time make them more permanent, by plunging them into a hot solution of hyposulphite of soda (or any other soluble hyposulphite) after which they are removed, washed, and dried."

In the first edition of his "Manual of Photography," published in 1841, Robert Hunt remarks:

(a) "That prints upon nitrate of silver may be fixed by washing with distilled water only.

(b) "That prints upon chloride of silver are 'half-fixed' by thorough washing with pure water.

(c) "I have in my possession some pictures which have been fixed with a strong *brine*, and subsequently washed with warm water. They have become slightly blue in the white portions, but otherwise they are very permanent.

(d) "Chloride of silver being soluble in solution of ammonia and some of its salts, they have been recommended for fixing agents. The ammonia, however, attacks the (silver) oxide, which forms the darkened part in some preparations, so rapidly, that there is great risk of its destroying the picture, or at least of its impairing it considerably. It matters not whether the liquid ammonia or its carbonate be used, but it must be a very diluted solution.

(Quite recently ammonia has again been brought forward as a fixing agent by Mr. R. H. Bow, of Edinburgh.*)

(e) "The ferrocyanate of potash, or, as it is more commonly called, the prussiate of potash, converts the chloride into a cyanide of silver, which is not susceptible of change by light; consequently this cheap salt has been employed as a fixing agent; but, most unfortunately, photographs which have been subjected to this preparation are slowly, but surely obliterated in the dark.

(f) "The iodide of silver, which is readily formed by washing the photograph with the solution of the iodide of potassium, is scarcely sensitive to light. It tinges the white lights of the picture of a pale yellow—a colour which is extremely active in absorbing the chemical rays of light, and is therefore quite inapplicable where any copies of the original photograph are required.

(g) "Of all the fixing agents, the hyposulphite of soda is decidedly the best."

These remarks on fixing agents are repeated in the later editions of Hunt's popular manual. They are taken mainly from Herschel's paper of 1840, referred to further on.

* *Photographic News*, 1887, p. 234.

About 1850, Reuben Phillips used electricity to accelerate the fixing process. He employed "electrodes the size of the photograph to be fixed, and placing upon the under one a flannel wetted with the fixing agent, he placed the print, wetted with the same solution upon it, and laid another wetted flannel upon the print, covering the whole with the other electrode. Connecting the electrodes with a galvanic battery, the metallic salt is rapidly removed to one pole, and thus the fixing process rendered comparatively short and easy."

J. H. Croucher, in a book published in 1845, advises* "to fix the picture, soak it for two or three minutes, or longer if strongly developed, in a solution of half an ounce of hyposulphite of soda to a pint of water, turning it occasionally; and then soak it in water for twelve to twenty-four hours."

In Le Gray's book, edition of 1849, he gives (in addition to the hypo bath) a fixing solution of bromide of potassium, 360 grains to $1\frac{3}{4}$ pints of water; its advantage being the avoidance of the use of hypo when travelling, the latter salt being even then recognized as likely to spoil everything photographic with which it came into contact.

Other fixing agents suggested by Herschel in 1840 were hydriodate of potash and chromate of silver.

From the remarks made in the paragraphs on toning processes, it will be seen that the operations of toning and fixing were most commonly performed in one and the same bath—first of old hypo alone, and then of hypo plus chloride of gold—from 1839 down to 1858; the advantage of separating the one process from the other being first authoritatively shown in Mr. Hardwich's paper communicated to the London Photographic Society in December, 1858. From that date down to the present day hyposulphite of soda has been, we may say, universally used for fixing positive prints on paper, the best proportions being three ounces of the salt to each pint of water. The hypo should be kept alkaline by the addition of a little carbonate of ammonia.

"Hypsulphite of soda" was first prepared by Chaussier in

* See also paper by R. Hunt "On the Use of the Hydriodic Salts as Photographic Agents," *Edinburgh Philosophical Magazine*, September and October, 1840.

1799, and was first studied by Vauquelin. In 1869, Schutzenberger showed that the so-called "hyposulphurous acid" was really *thiosulphuric acid*,* from which it resulted that the salts previously called "hyposulphites" were really *thiosulphates*. The correct chemical name of $\text{Na}_2\text{S}_2\text{O}_3$ is therefore sodium thio-sulphate, but its old name of "hypo" will probably stick to it as long as the present generation of photographers exists.

In Herschel's excellent paper, published in 1840,† he writes :
 "By far the most remarkable fixing process with which I am acquainted, however, consists in washing over
 Magic Photographs. the picture with a weak solution of corrosive sublimate (mercury bichloride), and then laying it for a few moments in water. This at once and completely *obliterates* the picture, reducing it to the state of perfectly white paper, on which the nicest examination (if the process be perfectly executed) can detect no trace, and in which it may be used for any other purpose, as drawing, writing, etc., being completely insensible to light."

"Nevertheless, the picture, though invisible, is only dormant, and may be instantly revived in all its force by merely brushing it over with a solution of neutral hyposulphite, after which, however, it remains as insensible as before to the action of light. And thus it may be successively obliterated and revived as often as we please. It hardly requires mention that the property in question furnishes a means of painting in mezzo-tint (*i.e.* of commencing on black paper and working in the lights), as also a mode of secret writing, and a variety of similar applications."

In 1866 these "magic photographs" obtained widespread popularity. They were sold everywhere at a cheap rate. The improvement which brought them into notice consisted in selling with each photograph a piece of blotting paper which had been saturated with hyposulphite of soda and then dried. It was only necessary to dip this into plain water and lay it upon the "magic photograph" to cause the picture to appear.

* *Comptes Rendus*, vol. lxi., p. 196.

† On the Chemical Action of the Solar Spectrum; on Preparations of Silver and other Substances, both Metallic and Non-metallic; and on some Photographic Processes. "Philosophical Transactions," 1840, part i.

Cyanide of potassium was used by M. A. Gaudin in 1853,* for fixing collodion positives on glass, and for such work it has ever since been preferred to hyposulphite of soda. Cyanide, however, is not fitted for fixing paper prints on chloride of silver, since it attacks the image. In extremely dilute solution (four drops saturated solution to the pint of water), it has, however, been found useful for reducing over-printed proofs. Vernier, in 1860, employed it for this purpose. One great drawback to the use of this substance is its terribly poisonous nature.

Sulphite of soda was shown in 1885,† by Captain Abney, to be an excellent fixing agent, though about twelve times more expensive than hypo. It should be used in the proportions of four ounces to the pint of water.

Sulpho-cyanide of ammonia was proposed as a fixing agent by M. Meynier in 1863.‡ It gives a yellow hue to albumenized paper, but answers well for proofs on plain salted paper. A compound fixing and toning bath of this salt, plus chloride of gold, is said to work admirably with the "Aristotype" paper lately introduced.

* *La Lumière*, April 23rd, 30th.

† *Photographic News*, pp. 339, 354, 370.

‡ *Bulletin de la Société Française*.

CHAPTER XII.

HISTORY OF PHOTOGRAPHIC PRINTING PROCESSES.—Continued.

(1) *With Iodide of Silver*.—In dull weather and in winter it is sometimes found impossible to get a single print for days together by the “printing-out” process upon our ordinary printing paper, which contains chloride of silver in albumen. The advantage of employing a method of development to produce positive prints from negatives, as well as the negatives themselves, was recognized at an early date; for the necessary time of exposure to light was thereby reduced from hours it might be, to seconds; moreover, the prints so obtained are undoubtedly more permanent.

In the Report* of the Jurors of the Exhibition of 1851, they state that Blanquart Evrard (France) has proved “that from one good original negative (Talbotype), any number of positive copies may be taken to the extent, indeed, of two or three hundred copies in a rainy day.” The following graphic description of how 250 prints were produced from one negative with one pressure frame in one hour and fifty minutes, is by Thomas Sutton,† who was himself for some time a partner with Blanquart Evrard about the year 1857: “The single pressure frame employed is contrived to run in and out of a window on a platform provided with rails. The window has a dark shutter which works up and down like a guillotine. Each print was exposed separately for a few seconds. The time occupied in exposing the 250 was about an hour and a half. The operation was conducted by a girl with a metronome at her side which ticks seconds. When a certain number had been exposed they were taken to the developing room. Here three or four girls were employed in developing the pictures.

* Page 277.

† See Photographic Notes, 1856, p. 63.

They used large glass dishes and each girl developed twenty or thirty at a time. The development of each print occupied about twenty minutes. Of the 250 prints produced on that occasion, 13 were rejected, and the remainder were published and sold."

"The girls employed divide their time between photography, and agricultural and other pursuits. When a sufficient quantity has been ordered a day is fixed and it is done. This is the way in which we print by the method of development. During the last five years at M. Blanquart Evrard's establishment at Lille, a staff of country girls have produced more presentable prints by the method of development than all the rest of Europe combined by other printing processes."

This development-printing process consisted in sensitizing iodized paper upon a solution of silver nitrate (thereby producing iodide of silver with an excess of nitrate of silver upon the paper), and then, after exposure beneath the negative, brushing over it a solution of gallic acid. This method was, therefore, practically identical with the calotype process. The defects were the "cold tone" of the prints, with a "lack of purity in the whites." No toning bath was employed. The *Photographic Album*, issued in monthly parts (price six shillings), by Sutton and Blanquart Evrard, in 1856, contained four developed prints in each part, and for some years Sutton challenged anyone to produce one of these prints which, having had fair treatment, had faded.

(2) *With Bromide of Silver*.—In 1854, Sir W. J. Newton described* a method almost identical with that given above, except that silver bromide was formed on the paper instead of silver iodide. The time of exposure required was from half a minute to three minutes, according to the (sun) light.

The first notice of the now very popular and largely used gelatino-bromide paper is contained in the "British Journal Almanac" for 1874, where Peter Mawdsley (of the Liverpool Dry-Plate Co.) advertises gelatino-bromide plates (price, 4s. per dozen, quarters), and adds: "in addition to the plates, we can supply sensitive

Development-printing on Gelatino-Bromide Paper.

* *Journal of Photographic Society*, vol. i., p. 222.

paper at from 20 to 25 per cent. less cost, including postage."

"For those who object to the weight and fragile nature of glass as a support for the sensitive film, the paper possesses many advantages; in fact, there is but *one* drawback to its use—the slight texture, which, however, by skill and care in printing, may be reduced to a minimum. It may also be used for positive proofs by contact and development-printing, an exposure of a few seconds to gas or other artificial light being sufficient. It will be found invaluable for enlargements."

In the body of the same book a capital article, by P. Mawdsley, also appears (page 129) on the "Development of Gelatino-Bromide Plates and Paper," in which he recommends our ordinary pyro-ammonia developer, restrained with bromide.

On July 22nd, 1879, J. W. Swan patented in England "a method of printing by development on surfaces coated with bromide emulsion."

He added "small quantities of alum and carbolic acid to make the emulsion less soluble," or else submitted the coated surface to the action of steam for the same purpose. The printing was done "either in the camera or by contact (artificial light preferred), developed with ferrous oxalate," and fixed in the usual way with hypo.

In 1880, Messrs. W. T. Morgan & Co.,* of Greenwich, near London, commenced the manufacture on a large scale of paper coated with gelatino-bromide emulsion. In a pamphlet written for the firm by John Burgess, and published in July, 1880, it is stated that such paper had been made by them since 1874.

In 1881 T. C. Roche took out a similar patent in America.

In June, 1882, Messrs. Morgan & Kidd patented a method of coating or enamelling paper with an impervious and insoluble layer of gelatine containing alum; this layer prevented the film of emulsion subsequently applied from sinking into the paper, and thus rendered it available for the production of brilliant pictures from small negatives by contact printing.

Messrs. Hutinet and Stebbing in 1883 made a tour of Great Britain, demonstrating in the principal towns the easy method of enlarging with the lantern upon gelatino-bromide paper.

* Now Morgan & Kidd, of Richmond, Surrey.

While speaking of enlarging we may remark that an article, describing a method of enlarging by daylight, devised by Heilmann, appeared in the *Athenæum* for July 9th, 1853.

The Eastman Co., of Rochester, N.Y., exhibited their photographic paper and appliances at the Inventions Exhibition, South Kensington, in 1885, and a notice of their work appeared in the *Times* for August 11th of that year. The paper is given a preliminary coating of gelatine, is then calendered, and finally receives a double coating of gelatino-bromide emulsion. The paper used for positive printing requires an exposure, when in contact with the negative, of from three to twenty seconds. It is developed with ferrous oxalate, and requires no toning.

The *Times* newspaper for November 24th, 1884, contains a description of a new printing paper issued by Marion & Co., of Soho Square, London, and called the "Alpha," of which, although the precise formula has not been published, we know that it consists of silver chloride, together with a little silver bromide, contained in gelatine. The special advantages of this paper are cheapness and the warm and varied tones which can be obtained; it generally requires toning, however. This paper has been successfully used in connection with an automatic printing machine invented in 1885, by John Urie, of Glasgow, with which 200 prints per hour can be obtained.

A very similar machine was invented in the United States many years ago by Fontayne.

The Alpha paper is exposed beneath a negative for from ten seconds to two minutes—according to the density of the negative—and then developed with ferrous oxalate.

A full and valuable description of the methods of making gelatino-chloride emulsion and spreading the same upon paper, opals and glass for positive printing, is contained in a long series of papers contributed by Messrs. Ashman and Offord to the *Photographic News* for 1885 and 1886.

When the early photographers found their silver prints fade one by one, despair for a while took possession of their hearts; but they speedily rallied and began to look around for some permanent material in which to imprint their pictures. In 1856,

History of the Carbon Printing Process.

the Duc de Luynes placed in the hands of the Photographic Society of France the sum of 10,000 francs, to be offered for the invention of a *permanent* photographic printing process ; and in announcing this handsome donation, the then president of the society, M. Regnault, the famous chemist, directed the attention of inventors to *carbon* in the following words* : "Of all the substances with which chemistry has made us acquainted, the most permanent, and the one which best resists all chemical reagents in the temperature of our atmosphere is carbon. . . . The present condition of ancient manuscripts shows us that carbon, in the form of lampblack on the paper, remains unchanged for centuries. If, therefore, it were possible to form photographic pictures in carbon, we should then have the same guarantee for their permanency that we now have for our printed books ; and that is the best which we can hope or wish for."

Since carbon is unalterable by light, the next step was to find some substance *upon* which light could act, and *in* which finely divided carbon might be contained.

Such a substance was to hand in a mixture of bichromate of potash and gelatine, which, soluble enough if kept in the dark, becomes insoluble when exposed to light.

Mungo Ponton, in 1839, announced to the Royal Society of Scottish Artists that paper soaked in a solution of bichromate of potash and dried, is changed in colour from yellow to brown by exposure to sunlight. He obtained copies of drawings in this way, and fixed them by simply washing them in water, which dissolved out the unaltered bichromate.

In 1840, Becquerel announced that if the paper was first sized with iodide of starch, it was more sensitive. Robert Hunt's "chromatype" process, published in 1843, varies only from Ponton's in the addition of sulphate of copper to the bichromate.

Joseph Dixon, of Massachusetts, copied bank-notes in 1841 by mixing gum arabic with bichromate of potash upon a lithographic stone, exposing to light through a bank-note, then washing away the unaltered portion of the gum, and, lastly,

* *Bulletin de la Société Française de Photographie*, vol. ii., p. 215.

inking the stone and taking prints in the usual way. Dixon's method, however, was not published till 1854, when it appeared in the *Scientific American*.

The first "idea" of the chain of circumstances which has resulted in the carbon printing process of to-day is contained in a patent taken out by A. L. Poitevin on December 13th, 1855, in which he describes the effect of light upon a layer of "chromatized" gelatine, adding "a design is produced in colour by mixing a suitable colour with the above-mentioned organic mixture, and when the photograph is impressed, washing away those portions of the mixture which have not been acted upon by the light." The "suitable colour" might, of course, be printer's ink, lampblack, or any other form of finely divided carbon.

On December 12th, 1857, Testud de Beauregard patented a further advance in the method of "producing photographic proofs or pictures by means of carbon or other colouring matter."

His favourite method, which we should consider all but impracticable, was to rub the pigment upon a surface of bichromatized gelatine; but he adds, "or the paper (to be coloured) may be immersed in a bath of Indian ink or other pigment ground up very fine with water and mixed with bichromatized gelatine." The paper, having been prepared in the dark, is exposed beneath the negative to the action of light, after which it is washed in hot water. This "dissolves the gelatine which has been acted upon by the light, but does not dissolve that which has been rendered insoluble by the action of the light, and which insoluble gelatine retains the pigment, and thus produces the image."

Beauregard's statement contains a clear outline of the principle of the carbon process, but John Pouncy, of Dorchester, England, has always claimed to be the first to actually produce successful carbon prints. The specification of his patent is dated April 10th, 1858; but a fuller description of his method is contained in Sutton's *Photographic Notes* for January 1st, 1859.

Pouncy exhibited his specimens at a meeting of the London Photographic Society, December 7th, 1858, from which body,



A. POITEVIN.

however, he received little but depreciation and criticism. Pouncy's method consisted in brushing over and into paper a mixture of bichromatized gum and vegetable carbon; the paper was then dried, exposed beneath a negative, and finally the picture was brought out or made visible by washing in water.

By all these methods *half-tones* were wanting. The Abbé Laborde showed* the reason of this in 1858, saying: "In the sensitive film, however thin it may be, two distinct surfaces must be recognised; an outer, and an inner which is in contact with the paper. The action of light commences on the outer surface. In the washing, therefore, the half-tones lose their hold on the paper and are washed away." This was, in fact, the same defect which we have seen in connection with the bitumen process of the elder Niepce.

In the same year (1858) J. C. Burnett gave a partial remedy for this defect by exposing through the *back* of the coated paper; placing, in fact, the *uncoated side* next to the negative. But in 1860, Fargier, in France, showed that the best way was to coat the exposed film with collodion, then transfer it bodily to glass, and wash away the unacted-on gelatine from the thus exposed back surface of the film. A similar process had been previously used by Poitevin, to whom the greater portion of the Duc de Luynes' prize was ultimately awarded in 1867.

Improvements quickly followed; in 1864 J. W. Swan patented "carbon-tissue," which is simply paper coated with a mixture of gelatine, sugar, and colouring matter, "resembling black oil cloth in appearance," and which can be sensitized at any time by floating it on a solution of potassium bichromate. The final touches necessary for success were given by J. R. Johnson in 1869, and by the "flexible support" patented by J. R. Sawyer in 1874.

At present the carbon process is largely worked by the "Autotype Company," of Oxford Street, London, whose "autotypes" (carbon prints), made of any size up to twelve square feet, are alike beautiful and permanent.

The "tissue" is usually purchased from the company; but if

* *Bulletin de la Société Française de Photographie*, vol. ii., p. 216.

"ready-sensitized," it must not be kept long, as it rapidly deteriorates. The exposure is a somewhat "blind process," as it effects no visible change on the black surface of the tissue, but it is rendered easy by the aid of an actinometer. The tissue is then soaked in cold water, squeegeed on to a piece of "Sawyer's flexible support," and washed with warm water till the paper backing and soluble gelatine are removed. The picture is finally retransferred to its permanent support, usually white paper, coated with insoluble gelatine.

From this brief description it will be seen that the carbon process is scarcely suitable for photographers who "don't like much fuss or trouble, you know." It is, however, admirably fitted for commercial work and for the production of enlargements.

Gehlen, in 1804, noted that uranium chloride is affected by light. But it was reserved for J. C. Burnett, in 1857-58,* and

for Niepce de St. Victor, 1858-59,† to invent a practical printing process with this metal by floating paper upon a solution (1 to 30) of uranium nitrate, exposing beneath a negative until a faint image was visible, and then developing by floating upon silver nitrate solution (40 grains to the ounce) or upon chloride of gold (9 grains to the ounce of water). Light changes uranic into uranous nitrate, and the latter salt is able to reduce gold and silver to the metallic state from their solutions.

In 1864 Herr Wothly, of Aix-la-Chapelle, patented a printing process in which nitrate of uranium and nitrate of silver were contained in collodion, with which paper was coated. Beautiful prints were produced by the inventor, and a company, with Col. Stuart-Wortley at its head, purchased the English patent; commercially, however, it proved a failure.

Several chemists, from Bestuscheff, in 1725 downwards, noticed the action of light upon various compounds containing iron, but Sir John Herschel in 1840 and 1842‡ was the first to use the salts of that metal for photographic processes. Of the three methods

History of Printing with Salts of Uranium—Wothly. type.

* *Photographic Notes*, 1857, pp. 97, 160; and *Photographic Journal*, 1859, p. 317.

† English patent, Feb. 27th, 1858.

‡ See the *Philosophical Transactions* for those years.

which he devised, and which he named respectively, *chrysotype*, *aurotype*, and *cyanotype*, only the last-named has proved of practical value. Known as the "blue process" (because the picture is produced in white lines upon a blue ground), it is largely employed by engineers and others for copying plans, etc. Paper is coated with a mixture of ammonio-citrate of iron and potassium ferri-cyanide; the action of light upon this mixture being to change it into insoluble Prussian blue. The paper is dried, exposed beneath the negative, and cleared by simply washing it in water.

In a preceding chapter we remarked that Marc Antony Gaudin, of Paris, had suggested the preparation of a "photogene" or liquid containing a haloid salt of silver with which paper or plates might be coated; in 1861 he prepared such a sensitive liquid with the iodide and the chloride of silver, but achieved no practical success.

At the close of 1864, G. Wharton Simpson (then editor of the *Photographic News*), announced † his discovery of a printing process in which chloride of silver contained in collodion was employed; and in March, 1865, he read a description of the process to the London Photographic Society. Very beautiful results were obtained, especially upon opal glass, but the collodio-chloride paper, though prepared commercially in Germany, never got a fair footing in Great Britain. From this remark, however, we must except Mr. George Bruce, of Dunse, in the south of Scotland, who for twenty years or more has sent out all, or the greater part of his work, printed upon collodio-chloride paper; and with excellent results so far as beauty of appearance and permanency are concerned.

Leptographic paper was a variety of collodio-chloride paper introduced on the Continent in 1866.

In November, 1864, W. Willis patented a process for reproducing plans, drawings, tracings, etc., without taking a negative. Paper prepared with an acid bichromate was exposed beneath the plan to be copied; it was subsequently developed by aniline vapour and fixed by

Willis's Aniline Process

† "Photographic Year Book, 1865," p. 63.

washing in weak acid and in water.* The operation is cheap, and the result said to be permanent. The method, however, never came into general use.

Metallic platinum, which, like several other metals, is perfectly black when in the state of a fine powder, is one of the Platinotype, or Printing with Salts of Platinum. most stable substances known. It is not affected in the slightest degree by air, by moisture, or by acids; and hence any photograph composed of it may be reasonably said, so far as the platinum is concerned, to be absolutely permanent.

The fact that certain salts of platinum are sensitive to light was noted by Sir John Herschel in 1832,† and by Hunt in 1844. When organic substances are present, the light exercises a reducing influence, changing platinic salts into platinous, and the latter into metallic platinum. An organic salt of iron—ferrous oxalate—acts especially well in assisting this reduction.

In 1856, Caranza published‡ a method for toning silver prints with an acid solution of platinum chloride; this gives black tones, while an alkaline solution gives brown ones. Eder and Toth (1875) showed that collodion negatives and lantern slides could be intensified in the same way.

The ordinary platinotype printing process, which has become very well known and widely practised during the last few years, depends not on the direct influence of light upon platinum salts, but mainly upon its action on certain organic salts of iron, which then react upon the platinum salt.

Herschel discovered in 1840, that ferric were reduced to ferrous salts by light; that is to say, that under the influence of light iron parts with some of the non-metallic element—oxygen, chlorine, etc., as the case may be—with which it happens to be combined.

Hunt actually tried§ to turn this fact to account in photography by mixing ferric oxalate with platinic chloride, and when dry exposing to light. He noticed a slight darkening,

* See *Photographic News*, 1865, pp. 186-196; and *British Journal of Photography*, March 16th, 1866.

† Report of British Association; Oxford meeting.

‡ *Photographic News*, 1859, p. 251, and *La Lumière*, February 23rd, 1856.

§ See Hunt's "Researches on Light," 1854.

but he missed the cardinal point—that the ferrous salt must be in solution before it can act.

It was in June, 1873, that W. Willis, jr., the actual inventor of our platinotype process, took out his first patent for platinotype in England; he patented improvements on it in July, 1878, and in March, 1880. His process is now worked by the Platinotype Company at 29, Southampton Row, High Holborn, London, under the management of Mr. Berkeley. In its latest form, the platinotype paper is prepared by coating paper with a mixture of chloro-platinite of potassium and ferric oxalate. This is exposed beneath the negative until a faint image is visible, when the paper is floated upon or drawn over a hot solution of potassium oxalate. In this liquid the (reduced) ferrous oxalate is soluble, and immediately it is dissolved it attacks the platinum salt in contact with it, abstracting the chlorine, etc., and reducing the platinum to the metallic state. The advantages of the process are permanency, a beautiful black “engraving-like” picture, simplicity of manipulation and great sensitiveness. Its progress has been retarded—in Great Britain at all events—by the fact that to practise it a license must be obtained from the patentees.

An admirable account of the entire process and its history is contained in a little book written by the Austrian investigators, Pizzighelli and Hubl, and published by Harrison and Sons, Pall Mall, London.†

† Price, two shillings.

CHAPTER XIII.

HISTORY OF ROLLER-SLIDES ; AND OF NEGATIVE-MAKING ON PAPER
AND ON FILMS.

There is nothing new under the sun—especially in photography. Two years ago the introduction of paper negatives and of a roller-slide to match, created quite a *furore* in both England and the “States;” but from 1839 to 1855, or thereabouts, every English amateur used paper as the support for his “calotype” pictures ; and the roller-slide is at least thirty-three years old.

The first account of a roller-slide which we have been able to discover, is contained in a patent taken out in England by Melhuish's Roller Slide. J. B. Spencer and A. J. Melhuish, on May 22nd, 1854. The Specification describes how a “series of photographic pictures may be obtained in succession upon a long sheet of sensitive paper, the parts of the paper or sensitive surface not in use, being rolled up within the frame of the camera. The frame in which the prepared surfaces are employed is fitted up with two rollers ; in using the apparatus after one picture has been taken, that part of the prepared sensitive surface is wound up on to one of the rollers, and a fresh quantity of the prepared surface suitable for receiving another picture is unwound off the other roller, and so on till all the prepared paper or surface on the roller has been used. Two rods or tubes of yellow glass are employed to retain the part of the sensitive surface which for the time being is brought into position in the correct plane or position. It is preferred to focus directly on to the prepared surface when using waxed paper (instead of focussing on to a plate of ground-glass), a plate of yellow glass having previously been placed in front of the lens to prevent the light from injuriously affecting the surface, and a plate of yellow glass is also placed behind the paper for the same purpose.”

The fact of the focussing being effected upon the paper coated with silver iodide and protected only by yellow glass, shows how comparatively insensitive to light were the materials then employed. A defect in Melhuish's slide was the apparent lack of any mode of registering when sufficient paper had been wound off one roller on to another to allow a fresh exposure. It is clear that it does not suffice to simply count the number of turns of the roller on to which the paper is wound, since that roller continually increases in thickness. Still, as the long band of paper was composed of a *number of sheets gummed together*, it was possible to *see* when one sheet had been completely rolled up by looking in at the back of the camera.

In the *Journal of the Photographic Society* for April 21st, 1856, there is a letter from Mr. Melhuish giving an account of his slide, and stating that "my best specimens at the Exhibition were taken with the roller-slide. It has been used by James Glaisher, Esq., F.R.S.; John South, Esq., of St. Thomas' Hospital, and Frank Haes, Esq., who have expressed themselves satisfied with its performance." In the drawings which accompany this note we see that the rollers were placed one on each *side* of the camera, instead of one on top and one below as in all other roller-slides.

But in 1854 the roller-slide was "before its time," and its use was probably confined to very few workers besides the three or four gentlemen named above.

It is singular that at the very time that Melhuish was striving to introduce his roller-slide to the notice of English ^{Captain Barr's} photographers, an amateur worker in India—"Dark-Slide." Captain Barr—had devised and was using a very similar instrument, being led thereto probably by the necessity for the lightest and most compact form of apparatus which could be constructed in order to overcome the difficulties of transport which presented themselves in many parts of that country. A description of this very original "dark-slide"—as Captain Barr called it—appeared in the first number of the *Journal of the Photographic Society of Bombay*, and was reprinted in *Notes and Queries* for April 21st, 1855. It consisted of a narrow box made to fit the back of the camera, and containing an upper

and a lower roller, between and in front of which a plate of glass was placed. The sheets of paper were fastened to a band of black calico, which was then wound on the lower roller, and one end of the calico was strained over the glass and attached to the upper roller. This upper roller was actuated by a key which was worked from the outside, and so the calico, etc., could be drawn from the lower to the upper roller as desired. The axis of the lower roller also passed through the side of the box, and was provided on the outside with a short index-roller of precisely the same diameter as the roller within. On this index-roller a piece of tape equal in length to the calico band, was wound, so that it was easy to judge of the amount of sensitive paper used, by the length of tape unrolled. Another valuable precaution is given by Captain Barr, "as a further precaution against light, and to guard against the evil effects of air upon the prepared paper, I leave the black calico band a *foot longer* than is necessary to carry all the (sensitive) paper. So that when all are wound round the roller, the last five or six plies are plain calico, thus excluding the light." It is remarkable that a correspondent of the *Photographic News*, in 1886, suggested exactly the same thing for the Eastman rolls, but his claim to originality is clearly *barr'd* by this paper written thirty-one years ago! Captain Barr adds another most valuable precaution which is to-day well worthy the attention of travellers in hot and moist climates: "I take the roller thus prepared out of the dark-slide and place it in a round metal case, which has a top which screws on air-tight; in the centre of this top is a short tube, opened and shut air-tight at pleasure by a small stop-cock; to this tube I attach a small suction-pump, and after all is thus prepared, I introduce the roller with the exposed paper into the metal tube, screw on the top, and exhaust the air. Lastly, shut the cock and remove the exhaust-pump."

A fortnight after the appearance of Captain Barr's paper in *Notes and Queries*, a Mr. T. E. Merritt, of Maidstone, claimed in the same periodical that he had "last year invented a camera with roller almost precisely similar to that of Capt. Barr, but somewhat more simple, inasmuch as I use a roller which by *one turn* winds off the entire picture, and brings another into its

place." Surely Mr. Merritt's roller must have been of a disproportionate diameter!

From 1855 we pass to 1871,* when M. Leon Warnerke—a Hungarian engineer, who has done so much good work in

Warnerke's Roller-Slide.

England that he may be fairly claimed as an English photographer—invented what was perhaps the first really practical roller-slide. M. Warnerke appears to have published the first account of his roller-slide in the middle of 1875.† He writes: "The principal components of the new dark-slide are two rollers on which the sensitive film is wound, and there is room for one hundred plates. A darkened glass plate is fixed in the front, in the place corresponding with the focussing surface; this glass plate guides the sensitive film in the progress from one roller to the other, and secures its proper position. Each roller has a metallic head by which it can be put in motion. By means of these heads all the ribbon of sensitive film can be consecutively drawn from one roller, and, after exposure, rewound on another roller. But to secure perfect flatness there is attached to each head a pressing screw, that arrangement permitting the stretching of the film when in position. Before the sensitive film is attached to the roller, it is divided into sections corresponding with the size of the plates by black lines drawn in pencil, or otherwise, and each section is numbered.

"In the sliding shutter there is a little window secured with orange glass and spring metallic shutter. Through the orange glass I am able to observe the black lines forming the divisions between the plates, and their corresponding numbers. This permits me to judge of the proper position of each consecutive plate."

In 1875, M. Warnerke's paper or tissue was coated with collodion emulsion. Our more sensitive gelatine emulsion does not permit observation through an "orange window," so that in the improved form of M. Warnerke's roller-slide which he introduced in 1885, he used first an electrical alarm, then a

* In the "Photographers' Annual," issued by A. H. Wall, for 1870, there is a sketch of an ingenious roller-slide, designed by T. Wiseman.

† *British Journal of Photography*, 1875, p. 306.

spring indicator, and, lastly, a measuring roller with indicator outside.*

The idea of the roller-slide is, as we have seen, essentially English. But it was reserved for the American firm of Eastman, Walker & Co. (of Rochester, N.Y.), to step in and achieve a commercial success where Melhuish and Warnerke had failed. This was done by the introduction of an admirably designed roller-slide of excellent workmanship—machine-made, with all its parts interchangeable—the details of which were first published in the summer of 1885. The success of the Eastman apparatus has been mainly due to the facts (1) that the roller-slide and the sensitive paper which it was to carry were put into the market together and by the same firm; (2) that the roller-slide was designed by skilled engineers; thoroughly tested before being offered for sale, and excellent workmanship invariably put into it.

Other roller-slides, all showing ingenuity, have been patented during 1885-87 by Messrs. Morgan and Kidd (of Richmond), S. McKellen, and J. E. Thornton (of Manchester), and by several others. But these are "creatures of to-day;" things whose descriptions still linger in our ears. Our main object here has been to draw attention to the past, and to show that the roller-slide—like most other inventions—did not spring into being perfect and full-fledged, but that it was first devised more than thirty years ago by Melhuish and by Barr; then improved by Warnerke; and finally, we may say, perfected by Eastman and others.

We have seen that Fox-Talbot employed paper solely as the support for the sensitive salt of silver (the iodide) which he used in his calotype process—so largely worked by amateurs from 1841 to 1855, or thereabouts. By this method the silver iodide was literally formed within the paper, and was much a part of it as if it had been mixed with the pulp when the paper was made. The effect of this was that, except in the largest sizes, the "grain" of the paper was disagreeably evident in the finished print; and, although the waxing of the paper before sensitizing, an improve-

Re-introduction
of Paper for Nega-
tive-making.

* *British Journal of Photography*, 1885, p. 601.

ment due to Le Gray, tended to obviate this by filling the pores of the paper, and so keeping the picture more or less on the surface, yet it was only a partial remedy.

However, the beauty, and above all the rapidity of Archer's collodion process on glass was such, that in a very few years after its introduction in 1851, it knocked paper out of the field altogether; and for negative-taking, glass coated with collodion was almost exclusively used from 1851 to 1880; and glass coated with gelatine from 1880 to 1885. In the last-named year paper once more came prominently to the front.

In 1875, Valentine Blanchard used paper for making enlarged negatives in the following way. He made an enlarged transparency in the camera, and from this took a deep print (which, of course, would be a negative), which he waxed to increase its transparency, and used as an ordinary negative. In artistic hands this method offers great facilities for introducing effects, as retouching etc., can be done both on the transparency and on the enlarged negative.

After the complete success of gelatino-bromide emulsion spread upon glass, in 1879-80, it was but natural to endeavour to apply the same material to paper. W. T. Morgan, of Greenwich, placed paper coated in this way in the market early in 1880, intending it mainly to be used for printing by development, after the manner suggested by Abney in the same year.*

But Palmer, Ranking, and other amateurs saw the possibilities of the new material, and, cutting the paper to fit their dark-slides, used it for work in the field. The manufacturers took the hint, and in 1884 made a more sensitive paper, intended specially for negative work. Then in the summer of 1885, the Eastman Company's negative paper was introduced simultaneously in England and the United States, and from the care and skill displayed in its manufacture, at once took a leading position. It is now very largely used, both in roll-holders carrying enough material for twenty-four exposures, and, cut to size, in carriers which fit the photographer's dark-slides. The secret of the beautiful results produced upon the "negative paper" now made

* *British Journal of Photography*, pp. 103, 160.

consists in isolating the emulsion of silver bromide from the paper by giving the latter a preliminary coating of gelatine, the emulsion being thus kept on the surface. After development the paper negatives may either be printed from as they are, or they may be rendered more transparent by soaking in oil-vaseline.

As a method of abolishing the "grain" of paper negatives, Warnerke patented in 1885, a process for covering a paper with emulsion on *both sides*, so that any imperfections on one side were corrected by the image on the other, "rendering the composite negative perfectly smooth, no matter how coarse or imperfect was the texture of the paper employed."

Lastly, in 1885, that inventive genius, Walter B. Woodbury, made paper transparent by soaking it in a solution of gum-dammar in benzole, after which it was coated with emulsion in the usual way. This paper, or "tissue" (with "Froedman's tissue," which is a still further improvement), is now manufactured in London by Mr. Vergara, who has invented an ingenious double dark-slide to hold the tissue.

Very early in the history of photography the possible benefits to be derived from removing the film bearing the picture from its glass support were recognized. In August, 1855, Scott-Archer patented a method of coating collodion negatives with a solution of gutta-percha in benzole. When dry, separation of the film from the glass was obtained by soaking in water. The glass might also receive a preliminary coating of gutta-percha, in which case the collodion film was enclosed between two waterproof films.

In the same year (1855) the Frenchman, Galliard, coated collodion negatives with gelatine, and then stripped them from the glass. In 1877, J. R. Johnson patented the application of a double coating of collodion and gelatine for the same purpose.

In 1869, Leon Warnerke commenced the preparation of sensitive collodio-bromide tissue, which was introduced into commerce in 1875. A film of collodion as transparent and textureless as glass was produced upon enamelled paper, and this was coated, first with india-rubber and then with collodion emulsion.

After gelatine had displaced collodion, Warnerke (in 1885)



W. B. WOODBURY.

manufactured a similar article, using gelatine in place of collodion, but in neither form can Warnerke's tissue be said to have come into general use.

A notable discovery made by Warnerke, and patented by him in 1881, is that an exposed gelatine film developed with pyrogallic acid becomes insoluble in hot water in the parts affected by light. If it is soaked in warm water and squeegeed upon a glass plate, the paper can be stripped off, and the soluble gelatine washed away, leaving a reversed negative attached to the glass. Great things were expected of this process at the time of the discovery, but practically no use has been made of it.

In 1881, H. Rogers showed how to strip negative films by varnishing them with gum-dammar dissolved in chloroform, and then soaking them in water.

The book on "Retouching," published by Burrows and Colton, in 1876, has for frontispiece an excellent "pellicular negative," apparently consisting of a film of collodion coated with gelatine.

The late W. B. Woodbury used, during the collodion times, a method by which glass was *partly* superseded, the same glass plates being used day after day. The glass was rubbed with talc, and then coated with collodion emulsion. After exposure these plates were developed, fixed, and washed, and a sheet of gelatine paper was squeegeed to the finished negative. When dry, the whole could be peeled off the glass, which was then ready for use again. At any convenient time the paper bearing the film was wetted and squeegeed down to a glass plate coated with insoluble gelatine. Finally the whole was soaked in warm water, which dissolved the upper layer of soluble gelatine, and the paper was stripped off, leaving the negative permanently attached to the glass.

In 1881-82, Stebbing, of Paris, and Pumphrey, of Birmingham, introduced sheets of gelatine made insoluble by a little chrome alum, and coated with gelatine emulsion. Pumphrey's "Filmo-graph," as the camera adapted for use with these films was called, was a really ingenious instrument, carrying a hundred films with ease.

The Eastman "stripping films," which we first saw in the

summer of 1885, are now coming largely into use. They consist of a film of *insoluble* gelatine emulsion attached to a sheet of paper by a thick layer of *soluble* gelatine. After the film has been exposed and developed in the same manner as a gelatine plate, it is squeegeed, face downwards, on a glass plate coated with india-rubber solution, allowed to dry, and is then placed in hot water, when the soluble gelatine is dissolved and the paper can be readily stripped off, leaving the insoluble gelatine film firmly on the glass. Finally, a "skin" of prepared gelatine is moistened and squeegeed upon the negative, which, when dry, is easily stripped, as a whole, from its glass support.

In 1883, Thiébaud, of Paris, patented a method of coating gelatinized paper first with collodion (hardened by a little castor oil), and then with a gelatine emulsion. Such films could be stripped *dry* from the paper support after exposure, development and fixing. Thiébaud, in 1885, substituted card-board instead of paper as a support for the emulsion.

In 1886, Pumphrey, of Birmingham, manufactured gelatine films, which were placed upon a support of thin ebonite covered with some adhesive substance for exposure in ordinary dark-slides. In 1887, he used card-board as the support, and the film (known as "flexible glass") is stripped *before* development. The films are developed and fixed as easily as glass plates; they are then dried on card-board, varnished, and remain flat and highly transparent.

The principal advantage of paper or films over glass for negative-making is, of course, their comparative *lightness*. This is most felt with the large sizes—whole plate and upwards—and is an especial boon to travellers and tourists. Then there is a marked absence of the halation or blurring which is so common upon glass, surrounding brightly-lit objects, or windows, etc., with a mist or halo of light. Paper negatives are also unbreakable, flexible, and can be stowed away in a very small space. They can also—owing to their thinness—be printed *from either side*, thus obviating the necessity in certain processes of producing a reversed negative. From several paper negatives it is easy

Advantages and
Disadvantages of
Paper and Films.

to form, by careful cutting, a single *combination negative* which shall unite the good qualities of each of its components.

The disadvantages of paper are not many ; it is not quite so easy to manipulate as glass ; not being so transparent it does not yield prints so quickly ; and no thoroughly satisfactory mode of varnishing paper negatives has yet been announced. The "grain" visible in many paper negatives has already been alluded to ; lastly, it is not so easy to get good lantern-slides from paper as from glass.

Balancing these points, good and evil, it is probable that glass will retain its pre-eminence for studio work and for small pictures ; while by those who travel and who desire to take good-sized pictures, paper or films will certainly be preferred.

CHAPTER XIV.

HISTORY OF PHOTOGRAPHY IN COLOURS.

There is probably only one thing which it is safe to predict about the problem of obtaining permanent photographs which shall represent objects in their natural colours ; and that is that the discovery, if it is ever made, will not be the result of an accident. The question must be studied and the conditions mastered before the attempt can be made with even the least chance of success. The following account is given with the hope of drawing attention to the progress which has already been made ; whence it will be seen that, with regard to naturally coloured pictures, we are now precisely in the position occupied by Davy and Wedgwood with respect to ordinary photographs at the commencement of the present century. Davy could obtain copies of objects upon paper coated with silver chloride (1802), but he could not fix them. Similarly it has been possible for many years, certainly since 1848, to obtain naturally coloured photographs ; but no certain means have yet been discovered by which they can be rendered permanent. The colours fade away when the pictures are exposed to light ; or when they are treated with the ordinary “fixing agents” of the photographer. When will the Niepce, the Talbot, or the Herschel arise who will do for colours what these “fathers of photography” did for pictures in black and white ?

Early in the present century an observation was made which favours the views of those who believe in the possibility of reproducing, photographically, the natural colours of bodies. In 1810, Dr. Seebeck, of Jena, was engaged in repeating certain experiments, first made by Ritter, in 1801, upon the existence of the ultra-violet rays. For this purpose Seebeck passed a beam of white light through a prism and received the spectrum, or band of coloured light so produced,

Seebeck's Experiment, 1810.

upon a sensitive surface of chloride of silver. Upon this substance he was afterwards surprised to see distinct traces of colour. Describing the experiment in the *Farbenlehre* of Gœthe, Seebeck writes: "When a spectrum produced by a properly constructed prism is thrown upon moist chloride of silver paper, if the printing be continued for from fifteen to twenty minutes, whilst a constant position for the spectrum is maintained by any means, I observe the following: In the violet light the chloride becomes a reddish-brown (sometimes more violet, sometimes more blue), and this colouration extends well beyond the limit of the violet. In the blue part of the spectrum the chloride takes a clear blue tint, which fades away, becoming lighter in the green. In the yellow I usually found the chloride unaltered; sometimes, however, it had a light yellow tint. In the red, and beyond the red, it took a rose or lilac tint. This image of the spectrum shows beyond the red, and beyond the violet, a region more or less light and uncoloured."

In 1839, Sir John Herschel also noticed the colours produced on sensitive surfaces by the action of coloured light. He found that "the spectrum impressed upon a paper spread with the chloride of silver is often beautifully tinted, giving, when the sunshine has been favourable, a range of colours very nearly corresponding with the natural hues of the prismatic spectrum. The mean red ray leaves a red impression, which passes into-green over the space occupied by the yellow rays. Beyond this a leaden blue is discovered." Daguerre noticed that a red house gave a reddish image on his iodized silver plates in the camera, and at an equally early date Fox-Talbot observed that the red portions of a coloured print were copied of a red colour on paper prepared with chloride of silver.

Between 1840 and 1843 Robert Hunt tried many experiments on the production of coloured images by light. By dipping paper first into nitrate of silver, and then into sodium fluoride, he obtained a thin coating of silver fluoride. When this paper was exposed to the spectrum "the action commenced at the centre of the yellow ray, and rapidly proceeded upwards, arriving at its maximum in

Observations of
Herschel, Daguerre
and Talbot.

Hunt Obtains Pho-
tographs Coloured
by Light.

the blue ray. To the end of the indigo the action was pretty uniform; it then appeared to be very suddenly checked, and a brown tint was produced under the violet rays, all action ceasing a few lines beyond the luminous spectrum. The colours of this spectrum are not a little remarkable. I have now before me a spectrum impressed two months since, and the colours are still beautifully clear and distinct. The paper is slightly browned by diffused light, upon which appears the following order of colours: A yellow line distinctly marks the space occupied by the yellow ray, and a green band the space of the green; through the blue and indigo region the colour is an intense blue, and over the violet a ruddy brown." Although this description is not very clear, it seems to point to two modes of treatment of the sensitized paper. The colours were only obtained in the second case, when the paper had been insolated, or exposed to light for a short time before the spectrum was allowed to fall upon it.

Other results obtained by Hunt are recorded as follows:—"A paper prepared by washing with barium chloride and nitrate of silver, allowed to darken whilst wet to a chocolate colour, was placed under a frame containing a red, a yellow, a green, and a blue glass. After a week's exposure to diffused light it became red under the red glass, a dirty yellow under the yellow glass, a dark green under the green, and a light olive under the blue."

In another experiment tried in 1843, with paper prepared with bromide of silver and gallic acid, "the camera embraced a picture of a clear blue sky, stucco-fronted houses and a green field. The paper was unavoidably exposed for a longer period than was intended—about fifteen minutes. A very beautiful picture was impressed, which, when held between the eye and the light, exhibited a curious order of colours. The sky was of a crimson hue, the houses of a slaty blue, and the green fields of a brick-red tint." Hunt adds: "Surely these results appear to encourage the hope that we may eventually arrive at a process by which external nature may be made to impress its images on prepared surfaces in all the beauty of their native colouration."

Perhaps the most successful reproductions of colour by means

* "Researches on Light." 1844, p. 277.

of photography which have ever been made, were obtained by the French physicist, Edmond Becquerel, in 1848.

Becquerel's Experiments in Colour Photography.*

Taking a silver plate, such as is used in daguerreotype, he obtained a thin and very uniform coating of chloride of silver upon its surface. This he sometimes effected by soaking it in chlorine water until the silver assumed a rose tint, or by dipping it into solutions of cupric or ferric chloride. By preference, however, Becquerel placed the silver plate in a solution of hydrochloric acid, and attached to it a wire from the positive pole of a voltaic battery; the wire from the negative pole being fastened to a plate of platinum, which also dipped into the acid solution. By this means the hydrochloric acid was decomposed, and the chlorine being drawn by electrical attraction to the silver plate, combined with it chemically, forming a surface of silver chloride of great purity. As the combination of silver and chlorine took place, the layer of silver chloride gradually increased in thickness, and as it did so its colour changed to gray, yellow, violet, and blue; and, continuing the action, these colours appeared a second time. When the second violet tint had been obtained, the silver plate was withdrawn from the solution, washed and dried, and gently heated until the surface assumed a rosy hue. When the spectrum of sunlight or of the electric arc was received upon a plate so prepared, an exposure of a few minutes was sufficient to impress the diverse colours. Coloured images of brightly dressed dolls were also obtained.

After Becquerel had obtained such favourable results, it may be asked, how is it that further progress has not been made, and why are not coloured photographs more frequently produced? The answer is that no

Failure in Fixing Coloured Images.

certain means has hitherto been found of *fixing* the coloured images secured; they can only be examined in a faint light, and must be kept locked up in drawers and excluded from the day. They last longer when protected from the air, for oxygen has a detrimental effect upon the colours. Becquerel, however, appears to have succeeded in rendering more or less permanent *some*, at any rate, of his "heliochromes." One which he presented to

* See *Comptes Rendus*, 1848 and 1854; also "Annales de Chimie," 1849.

Brewster was lent by the latter to J. Traill Taylor, who exposed it for several days to *bright sunshine* without injury to the colours.*

Niepce de St. Victor repeated Becquerel's experiments, but he found it better to form the chloride of silver by immersing the silver plate in a solution of chloride of lime.†
Experiments of the Younger Niepce He also reduced the time of exposure by coating the chlorinized surface with a solution of chloride of lead in dextrine. Niepce believed that a relation existed between the colours impressed and the source from which the chloride was obtained; and in 1857 he published the results of some experiments on the connection between the colours imparted to flame by certain metallic chlorides, and the colours impressed on silver plates prepared from the same chlorides. Subsequent investigations have not, however, confirmed this theory. Niepce sent specimens of his work to the London Exhibition of 1862, consisting of about a dozen reproductions of prints of figures with parti-coloured draperies. Each tint in the pictures exhibited was a faithful reproduction of the original, including yellows, blues, reds, greens, etc., all very vivid. Some of the tints faded at once when these pictures were examined by daylight, but others remained for some hours.

In 1868,‡ A. Poitevin examined and extended the results obtained by Herschel and Hunt. Taking paper sensitized in the usual way with silver chloride, he washed it and exposed the sensitive surface to light for a short period. The insolated paper was then dipped into a solution containing bichromate of potash and copper sulphate, and finally dried. When such paper was exposed to light beneath a transparent coloured picture—as a painting on glass—the colours of the pictures were reproduced on the paper. Poitevin states that the colours so obtained could be fixed by means of sulphuric acid.

Another French experimenter, St. Florent, in 1874, described§ a method of obtaining similar results in a rather different manner.

* *British Journal of Photography*, December 29th, 1865.

† Series of papers in *Comptes Rendus*, 1851 to 1863.

‡ *Comptes Rendus*, 1868, vol. lxi., p. 11.

§ In the *Bulletin de la Société Française de Photographie*.

Paper is soaked first in silver nitrate, and then in a mixture of uranium nitrate and zinc chloride, rendered acid with hydrochloric acid. The paper is dried and exposed to light until the surface is slightly darkened; it is then floated on a solution of mercuric nitrate, again dried, and is then ready for exposure to the coloured light whose impression it is desired to secure.

With reference to coloured images obtained upon paper, Captain Abney remarks:*

Coloured Copies
obtained with Paper
—Capt. Abney's Re-
searches.

salts of silver are not being dealt with as a rule. An organic salt of silver is usually mixed with chloride of silver paper, this salt being due to the sizing of the paper, which, towards the red end of the spectrum, is usually more sensitive than the chloride. If a piece of the ordinary chloride of silver paper is exposed to the spectrum till an impression is made, it will usually be found that the blue colour of the darkened chloride is mixed with that due to the colouration of the darkened organic compound of silver in the violet region, whereas in the blue and green this organic compound is alone affected and is of a different colour from that of the darkened mixed chloride and organic compound. This naturally gives an impression that the different rays yield different tints, whereas this result is simply owing to the different range of sensitiveness of the bodies."

But the coloured images obtained upon daguerreotype plates by the method of Becquerel must be truly due to the distinct effects of different rays of light, for in that case there is no organic compound present to interfere with the results.

Acting on a suggestion made in December, 1865, by the then Paris correspondent of the *British Journal of Photography*, R. J. Fowler (formerly of Leeds), several trials were made by English experimentalists, and in particular by J. Traill Taylor and G. Wharton Simpson, in the course of the following year, to utilize collodio-chloride of silver films in obtaining coloured images. The colours obtained were not so vivid as those secured by Becquerel upon daguerreotype plates, but they were visible by transmitted as well as reflected light.

A year seldom or never passes without the announcement in

* "Encyclopædia Britannica," vol. xviii., p. 835 (ninth edition).

some newspaper or other that "Photography in colours is at last an accomplished fact!" In some cases the "discovery" merely relates to a modification of the well-known mechanical process by which—several negatives being employed—the picture is printed piecemeal, each portion receiving a daub of a separate colour. Frequently the method adopted is to render the photograph transparent and colour it on the back; some such plan has been patented on an average twice a year for the last twenty years!


Other reputed "discoveries" are due to the fact that by faulty manipulation, colours of some kind or other are not unfrequently obtained upon collodion—as in Hunt's example—or even on gelatine plates; or they may be the result of a splitting of the film, giving the "colours of thin plates." Some novice noting these, to him, marvellous appearances, writes in haste to the papers that he has secured the long-wished-for result—a result, however, which he finds himself unable to reproduce.

Still other cases are deliberate frauds. Thus, in 1851, an American preacher named Hill, obtained almost general credence for his statement that he could produce photographs "glowing with all the colours of nature!" Naturally, so wonderful a process was to be called Hillotype. The Rev. Mr. Hill obtained a considerable sum of money by inducing photographers generally to subscribe—payment in advance, of course—for a book which should contain all the details of this startling discovery. After many delays the promised book appeared; but what was the disappointment of the subscribers to find it a mere two-penny pamphlet containing the outlines of the daguerreotype process, with complications and additions just sufficient to render the obtaining of any picture at all a very improbable matter!

The most recent researches upon photography in colours are those of Captain Abney.* He states that the colours obtained by Becquerel and others upon daguerreotype plates are due to the oxidation of the silver compounds employed. When the sensitive plates are exposed in the presence of some oxidizing agent, as by

Origin of the
Colours obtained
upon Salts of Silver

* "Proceedings of the Royal Society," 1879, vol. xxix., p. 190; vol. xxxiii., p. 164.



BEHRDSE & SONS, PHOTO-TINT.

LONDON & DERBY.

CAPTAIN W. DE W. ABNEY, R.E., F.R.S.

From a Photograph by W. W. Winter, of Derby.

dipping them into peroxide of hydrogen before or during exposure, the colours are produced more speedily.

The same investigator points out that there are several known molecular combinations of bromide of silver, which can readily be distinguished from each other by the fact that they absorb different rays of light.

Thus we are acquainted with :—

(1) A modification of silver bromide which transmits and reflects orange light. This form of the silver bromide molecule exists in paper which has been sensitized with silver bromide, on plates coated with a collodio-bromide film, and on collodion-bath plates. This molecule will clearly be chiefly affected by the blue rays, since it absorbs the blue end of the spectrum, and work is done only by those rays which are absorbed.

(2) Another form of the silver bromide molecule appears of a bluish-green tint, by transmitted light. This modification absorbs the light of the red end of the spectrum, and even the invisible or "dark heat" rays which lie beyond the red. By taking advantage of this property, Captain Abney was enabled to obtain photographs of the region called the "ultra red," which proved its extension over a length exceeding that of the whole of the spectrum ordinarily visible.

(3) Silver bromide contained in emulsions which have been boiled, or treated with ammonia, appears of a gray tint by transmitted light.

By an exposure of two minutes to the band of coloured light, produced by passing a beam of white light through a spectroscope, Abney obtained coloured pictures of the solar spectrum upon silver (daguerreotype) plates, and upon collodion films. He considered the colours obtained to be due to the mixture, upon the same plate, of the first two modifications of the silver bromide molecule described above; the first absorbing the light of the blue, and the second that of the red end of the spectrum.

The admirable researches of Carey Lea upon the "photo-salts" of silver, published in the *American Journal of Science*, during 1887, constitute an important advance, and their author believes that the new substances which he has discovered and

isolated, will ultimately furnish the key to the question of photography in colours.

But still the original problem confronts and baffles us. No means are known of giving permanence to the size or form of these colour-producing molecules; indeed, the molecules are themselves decomposed, or radically altered, by the ordinary "fixing agents" employed by the photographer.

Under the influence of white light also the coloured molecules of silver bromide change; they are decomposed and the colours disappear. And after all, the colours which we have as yet been able to obtain, but not to fix, by means of photography, are but faint and dim, poor reflections of the brilliant tints of nature.

In this work of obtaining naturally-coloured photographs there is clearly a fine field for experiment and research. How many photographers have attempted even to confirm the results obtained by Becquerel, Niepce, Carey Lea, and Abney? And yet what an interesting and important task this would be.

The references given above will enable anyone who has access to a good library, such as our leading photographic societies ought each to possess, to ascertain more fully the details of working.

CHAPTER XV.

HISTORY OF THE INTRODUCTION OF DEVELOPERS—SUMMING UP.

1. In niepceotype the picture was "brought out" by simply washing the exposed bitumenized plate with a solvent, which washed away those portions of the asphalt that had not been acted on by light (1827).

A Brief History of
Development.

2. A daguerreotype was developed by causing the vapour of mercury to act upon a surface of silver iodide; the metallic vapour condensed on those places where the light had acted, in proportion to the intensity of the light (1839).

3. The developer for calotypes was a mixture of gallic acid and silver nitrate. The former of these bodies is a powerful *reducer*; i.e., it is able to separate the metallic silver in the silver nitrate from the other substances with which it is combined. This newly-liberated silver is *attracted by* those portions of the sensitive surface upon which the light has acted, and is deposited upon them in the exact ratio of the intensity of the light (1841).

4. Archer (in 1851) developed his collodion plates by pouring on them a mixture of pyrogallic acid and acetic acid in water. The action was precisely the same as in the calotype process; and, as the wet collodion film was already covered with nitrate of silver, there was no necessity to add more of that substance to the developer. Ferrous sulphate (first used by Robert Hunt in 1844) was frequently employed instead of gallic or pyrogallic acid as a silver reducer in the wet collodion process.

5. For our modern dry-plate work all the developers described above have been displaced by what is known as "alkaline development," in which the developer consists of pyrogallic acid, ammonia, and ammonium bromide, dissolved in water. The ammonia exercises a stimulating action upon the pyro, while the ammonium bromide prevents any action on the parts of the

silver bromide which have not been affected by light. The silver to form the image is obtained from the silver bromide embedded in the gelatine, or in the collodion with which the plate is coated. Light acts upon certain of the surface molecules of this silver bromide, displacing some or all of the bromide, and leaving (let us say for simplicity's sake), scattered molecules of silver to bear testimony to its action. Yet, upon removing an exposed plate from the camera, no picture is visible upon its white surface. The reason is that the isolated particles of silver are too small and too few to be visible; just as a handful of shot could not be detected by the eye if mixed with a sack of flour. But under the stimulus of the alkaline developer the reduced silver molecules attack the molecules of silver bromide *beneath* them, abstracting their silver, and this action goes on until "the high-lights" become visible at the back of the plate, by which time it is, as a rule, sufficiently developed to give a dense image after "fixing," as we call the process of clearing away the unacted-on silver bromide.

The alkaline developer appears to have had its inception in America. In 1862, the news reached England that Messrs. Anthony and Borda had found great benefit in fuming dry-plates with ammonia before development. At the same time Mr. Leahy, of Dublin, found that a little liquid ammonia added to a plain pyrogalllic acid developer brought out the image very rapidly. But Major Russell, the author of the tannin process, had for some time been at work in the same direction, and in the second edition of his book on the "Tannin Process," published in 1863, we find the first complete account of a workable system of alkaline development. Russell not only described the accelerating action of ammonia, but he showed the necessity for the presence in the developer of a soluble bromide, in order to prevent fog. Since 1862, the carbonates of ammonia, soda and potash have been used in turn as the alkaline element of the developer in place of ammonia, but the latter still retains most votaries in England, although the fixed alkalies (soda and potash) find great favour in America.

6. In 1877, Carey Lea, in America, and Willis, in England, simultaneously announced that ferrous oxalate formed an

admirable developer for plates containing bromide of silver. Ferrous oxalate is best made by pouring one part, by measure, of ferrous sulphate into three parts, by measure, of potassium oxalate, both the solutions being saturated. This developer has found great favour on the Continent. It gives clean plates, but there is not the same power of remedying an incorrect exposure as with pyro and ammonia.

Scores of other developers have been proposed, which the limits of our space forbid us referring to in detail.

From what has been written it will be seen that the progress which has been achieved in photography during the brief half-century of its existence has been mainly in the direction of *rapidity*. It is not so much that we take *better* photographs in 1888 than in 1839, as that we take them in a fraction of the time then required. The following table shows this very clearly :

Advance of Photography.

<i>Process.</i>	<i>Date of Discovery.</i>	<i>Time required.</i>
Heliography	1827.	6 hours.
Daguerreotype.....	1839.	30 minutes.
Calotype	1841.	3 minutes.
Collodion	1851.	10 seconds.
Collodion Emulsion Dry-Plates ..	1864.	15 seconds.
Gelatine Emulsion.....	1878.	1 second.

The above are average exposures, compared with a certain standard ; but gelatine plates can be prepared to take fully-exposed pictures of brightly-lit landscapes in the two-hundredth part of a second. Perhaps the most rapid exposures made are those by which M. Janssen, the French astronomer, daily takes photographs of the sun at the observatory of Meudon, near Paris, in the two-thousandth part of a second. This rapidity of our modern gelatine plates has led to the invention of a great variety of "shutters," by which the opening admitting light through the camera lens is opened and closed in the fraction of a second. A skilful operator can take off and replace the ordinary "cap" of a lens in the third of a second ; but for what are called instantaneous exposures it is necessary to do this in the one-eighth—or less—of a second ; and for this purpose we replace the cap by a shutter.

And now we are compelled to end our review of the growth

of this young giant, this science of our own time—Photography.

Conclusion.

We have said much, but we feel how much there is left unsaid. We desired to speak of the improvements in lenses, of the application of photography to the microscope, of astronomical photography, and of several minor topics the history of whose discovery is the best road to their thorough comprehension ; but at present we must be satisfied with having traced the " main line " from end to end.

And what lessons there are to be read in this story of the advance of photography. How beautifully it exemplifies the theory of evolution, process rising out of process, and improvement following on improvement, in as orderly, though far more rapid a manner, as the horse has been evolved from the hipparion ! Let it be our task to sustain the rate of progress, and then the photographers of the twentieth century will esteem our labours as highly as we do the work of Niepce and Talbot, of Archer and Daguerre.

APPENDIX.

DR. MADDOX ON THE DISCOVERY OF THE GELATINO-BROMIDE
PROCESS.

Feeling that some further details of the discovery of the now universally employed gelatino-bromide of silver process would be of great interest in the history of photography, I wrote to the veteran worker, Dr. Richard Leach Maddox,* to whose labours we are indebted for our gelatine dry-plates, to gain additional information as to the steps by which he was led to the inception of the work which will always be associated with his name. I am sure that the readers of this book will peruse with special pleasure the account which he has given of the work done by him sixteen years ago, which has been so fruitful. Some may feel inclined to wonder that having done so much—having advanced so far on the road to success, and with the goal in view—that Dr. Maddox did not do more, and himself perfect his valuable discovery. To such be it said that for more than half a century Dr. Maddox has borne with patience a painful disease which would have incapacitated most men from all work that was not absolutely necessary. Then the imperative calls of his profession, and the splendid work he has also done in photomicrography must be taken into account, and when we remember all this, we see that the wonder is not that he did not do more, but that he did so much, and did it so well.

And now we will let Dr. Maddox speak for himself:

“PORTSWOOD, SOUTHAMPTON, August 19, 1887.

“DEAR SIR,—In your favour of the 17th inst. you express a wish ‘to know more how and why my attention was directed to gelatine and silver bromide?’ If you find the answer rather a complex one you must excuse it upon its threefold character.


“Firstly, the cost of the collodion, with the troublesome

* Born at Bath, 1816.

manufacture of the cotton. Secondly, health more or less affected by its constant use when working, as I was in my camera, a dressing-room, often at a very high temperature in the summer months; and thirdly, dissatisfaction with the dry methods for the photo-micrographic work upon which I was much engaged.

"The first reason may be dismissed as of little moment when there was an adequate return upon the work done; but not so, when there was an absolute loss even in an amateur's point of view. The second reason was a more important one. Being often shut up for hours in the said camera, the temperature at full summer heat, I found the system completely saturated with the vapour of the collodion, so much so that it could be tasted in the breath on awakening in the night, and sleep was generally much disturbed and unrefreshing, while it was much needed to restore the nervous energy wasted by constant suffering, often very severe in character; moreover there was an outcry in the household that the collodion vapour unpleasantly pervaded every room in the house. The third reason was that I could find no satisfactory dry or sticky process that did not embrace the first two reasons, and add another of its own in the shape of additional time and trouble in the preparation of the plate.

"These reasons set me experimenting, sometimes on paper, sometimes on glass, with vegetable gummy matters as lichen, linseed, quince seed; and starchy substances as rice, tapioca, sago, etc.; and with waxy material as Japanese vegetable wax. Often I fancied I was just within the doorway when the door closed, and other plans had to be tried. All the literature I could find bordering on the subject was searched, but it rather bewildered than enlightened. At last I turned to the animal series, and wasted many eggs and some little silver; then I went to the finest isinglass at about twenty shillings the pound weight, and the very first experiment led me to hope I was on the right track; something had to be altered, as I was using iodo-bromide in varying collodion proportions, and the isinglass did not appear to yield a sufficiently even surface in spite of all kinds of filtering; yet confidence was felt that a vein had been struck. Search was now made in the house for a packet of Nelson's gelatine; this afforded a better surface,



J TRAILL TAYLOR.

especially as the plates were dried generally on a hot one-inch-thick iron slab, and tested at once. Then came the mixture of isinglass and gelatine, but the advantages pointed to gelatine. The little plates were tried under a negative, then on out-of-door objects, but it was impossible to get some laurels depicted in anything more than black and white. I remembered that someone had stated that the bromides were better suited than the iodides for foliage—now came the experiment of diminishing the iodide and increasing the bromide until it settled into bromide alone. Yet I was not satisfied; but experimenting went on so rapidly that often I did not wait to filter the gelatine before mixing the bromide of silver in it. Before this period, that talented experimenter, Mr. Carey Lea, had spoken of the use of aqua regia, and my attention was turned to it, fancying that its use would decompose some of the gelatine and furnish the extra silver a chance of forming an organic salt of silver which might possibly improve the image. After working with this and getting more satisfactory results, various substances were mixed with the gelatine, as gum, sugar, glycerine, etc., which gave different tints to the developed negatives, and it was seen that it only required further experimenting to put gelatine into use, for some of the negatives were fairly plucky, and half-tones beautifully rendered; but, compared with collodion, the gelatine was slower, although it stood its ground with some of the dry processes.

“Paper had not been neglected, for among the paper trials with the gelatine was one which I thought gave much promise, the tint on development equalling much of the kind at the present day. This was obtained by the addition of a small quantity of arsenite of silver.

“There was no thought of bringing the subject into notice until it had been lifted from the cradle. Soaking the plates before use, for, of course, I knew the useless salts were left in the gelatine, was noted down for trial; but at this stage, and while in the very hey-day of experimenting, there came an urgent appeal from my kind friend, Mr. J. Traill Taylor, to assist him, without delay, by an article for the *British Journal of Photography*, of which he was then editor, as he had been taken seriously ill.

“Without a moment’s hesitation, and thinking it would give my friend pleasure, the hurriedly written and fragmentary article that appeared in the September *Journal*, 1871, was forwarded to him, and proofs by sundry negatives were also sent, some of which, almost entirely defaced, my friend, Mr. W. B. Bolton, and I found three or four years since among the glass in the office at No. 2, York Street. Another pen had also come to the rescue, and my paper was deferred to the following weekly issue, when Mr. Taylor, with far-sighted judgment, noted the process had a future before it.

“Health had now fairly broken down, rest was needed, so that very little further experimenting was done; and as there were other irons in the fire demanding attention, the process was offered to a firm in Southampton, from whom I used to get my albumenized paper; but it was found there was no time to continue the necessary experiments to raise the rapidity and enhance its value. This was done at different stages by others, almost two years after I had freely given to the public what had cost me much time and labour.

“The world has been benefitted and I have been honoured with a gold medal and diploma by the Jurors’ Committee of the Inventions Exhibition. Do not for one moment suppose I ignore the work of other hands in *perfecting* the gelatino-bromide process, and thus giving it its world-wide value in all departments of photography, especially that far-reaching one of its adaptation to astronomical research. I am only too thankful to feel that I have been merely the stepping-stone upon which others have safely put their feet, though now and then there cropped up the old story of the prophet in his own country—let it pass, this is the jubilee year. I am grateful to those abroad, and at home who, like yourself, have recognized the original claim of

“Dear sir, yours most truly,

“R. L. MADDOX.

“W. JEROME HARRISON, ESQ., Birmingham.”

BIOGRAPHIES.

With respect to several of the "Fathers of Photography" whose portraits are given in the illustrated edition of this book, sufficient personal details are given in the body of the work. Of the others, some details will be found below.

ABEL NIEPCE DE SAINT VICTOR (see p. 36) has been styled the nephew of Nicephore Niepce, whom (in accordance with a custom in that part of France to which the Niepce family belonged) he invariably spoke of as "my uncle;" but M. Fouque has shown that the real relationship was that of "cousin-german." Niepce de St. Victor was born at Saint-Cyr, 26th July, 1805. He entered the army from the Cavalry School of Saumur in 1827, and in 1842 was made lieutenant in the 1st regiment of dragoons. The life of a military officer in a provincial French town during a time of peace is very dull, and St. Victor took up the study of chemistry; succeeding so well that in 1843 he was able to save the French Government a sum of about £5000 by cheaply effecting (by chemical means) a desired change in the colours of the uniforms of certain regiments. As a reward St. Victor was transferred to the Municipal Guard of Paris, where, however, his modest laboratory (a barrack-room) was burnt down in the revolution of 1848. In the following year he was given the Legion of Honour; and in 1854 was made Commandant of the Louvre. He died suddenly in his laboratory at the Louvre on 6th April, 1870, leaving a widow and two children, for whom a subscription was raised by the photographers of France and England.

The younger Niepce (as he is often styled) was the first to use glass plates in a really successful way in photography (though Herschel experimented with them in 1839). On 25th Oct., 1847, he communicated to the French Academy a

process in which starch spread upon glass was used to contain sensitive silver salts; and in 1848 he published the albumen process on glass. His researches on heliochromy, pursued especially from 1848 to 1865, resulted in the production of many successful naturally-coloured photographs — which, however, he was unable to fix; he also improved considerably the process of *heliography* discovered by the elder Niepce, using bitumen spread upon plates of steel. The portrait has been reproduced by Messrs. Waterlow, from a print furnished by M. Nadar.

- B. J. SAYCE (see p. 54), of Liverpool, one of those “amateurs” who have led the way in original research in photography—was born April 13th, 1837. He commenced the study of photography in 1853, and in 1864-65 was Honorary Secretary of the Liverpool Photographic Association, of which body he is now (1888) the President.

Mr. Sayce’s discovery of the “Collodio-bromide of silver emulsion process” in 1864 marks an epoch in the history of the art, which was fitly recognised by the award to him of a Gold Medal by the Jury of the International (South Kensington) Inventions’ Exhibition of 1885. The portrait is the work of the Meisenbach Co., from a print by Vandyke.

- CAPTAIN WILLIAM DE WIVELESLE ABNEY, F.R.S. (p. 122), of the Corps of Royal Engineers, and Assistant Director of the Government Department of Science and Art, was born at Derby in 1843.

After completing a course of training at the Woolwich Military Academy, Abney received the appointment of Lieutenant in the Royal Engineers—the scientific corps of the army—in 1861, and was made Captain in 1873. His first work in teaching photography was as Instructor at the School of Mining Engineers at Chatham, and the classes of military officers which were for many years under his instruction there have carried off numerous medals at our photographic exhibitions. In 1874 Capt. Abney went to Egypt as one of the scientific observers appointed to study the Transit of Venus; and in 1883 he was awarded the Rumford Medal by

the Royal Society for his researches in photography and in spectrum analysis.

Captain Abney has rendered an important service to photography by writing a series of handbooks on the science, all of which are distinguished by great originality and thoroughness. They include :—

“Instruction in Photography,” 7th edition, 1886.

“Negative-Making,” 1887.

“Emulsion Processes in Photography,” 1878.

“The Practical Working of the Gelatine Emulsion Process,” 1880.

“Photography with Emulsions,” 3rd edition, 1885.

“Art and Practice of Silver Printing,” 1881 (written jointly with H. P. Robinson).

The seven books named above are published by Piper and Carter, 5, Furnival Street, London.

“Treatise on Photography,” 3rd edition, 1888. Longmans.

Capt. Abney is also the author of the article on photography in the *Encyc. Brit.*; of two series of Cantor Lectures (Society of Arts); of a finely illustrated book on “Thebes” (Sampson Low), and of divers papers on photography, etc., in various scientific periodicals. He is President of that excellent institution the London Camera Club. He believes in having a little iodide in a dry plate, and the “Abney Plate” made from his formula, by the Derby Dry Plate Co., has great rapidity and yet allows much latitude in exposure—qualities which are rarely combined. Messrs. Bemrose have executed the portrait by their “photo-tint” process, from a print by W. W. Winter, of Derby.

WALTER BENTLEY WOODBURY (p. 112) was born at Manchester, 26th June, 1834. He began photography with home-made apparatus almost as soon as he got into his “teens.” In 1849 young Woodbury went out to Australia. He did not make his fortune at the gold-fields, but in 1853 he became a professional photographer there. In 1859 he migrated to Java; and there worked the collodion process with great success, finally returning to England with a modest com-

petence in 1863. During the next twenty years (1864-84) Woodbury took out no fewer than twenty patents for photo-mechanical printing processes, and for improvements in many articles of scientific apparatus. He will be best remembered by his invention called "Woodburytype" (patented July 24th, 1866), in which a photograph in gelatine is caused by enormous pressure to indent a sheet of lead. The lead mould so obtained can then be used to print from. The magnificent photogravures produced by the French firm of Goupil (now Boussod, Valadon & Co.) are believed to be executed by a modification of Woodburytype. Woodbury died suddenly at Margate, 5th Sept., 1885; he was buried in Abney Park Cemetery, London.

HENRY PEACH ROBINSON (p. 85)—artist and photographer—was born at Ludlow, in Shropshire, in 1830. He commenced the study of art at a very early age, and while quite a lad contributed articles and sketches to the *Journal of the Archaeological Society* and to the *Illustrated London News*. Etching, sculpture, and literature occupied much of his time, but his best efforts were given to painting; and before he came of age he had a picture in the Exhibition of the Royal Academy. To the artistic training which he received in these early years Robinson owes much of the success of his work in photography.

It was in 1852 that Robinson began the practice of photography. Archer's collodion process had then just been introduced, and the difficulties in the way of the beginner were great; but they were successfully overcome by the "new hand," and in 1857 Robinson's studio at Leamington began to be known as a place where a man was striving to do something more than merely make "portraits."

For the artist had formed the high resolve to "produce every year at least one picture with the sole object of showing the pictorial capacity of the photographic art." The first fruit of this resolve was shown in 1858 by that celebrated photograph—"Fading Away"—a girl in the last stage of consumption, surrounded by grieving friends; and a

controversy raged hotly as to the legitimacy of treating such a subject by photography.

Shortly afterwards Robinson took up combination printing, by which a number of negatives are used in obtaining a single print, and in 1862 he exhibited that magnificent photograph "Bringing Home the May," which measures 40 inches by 15, and was printed from nine negatives—the complete work, however, showing no trace of the "joins," and no unevenness of tone.

From this time onwards a series of unequalled *genre* pictures have proceeded, annually, from the artist's hands; and we need only mention "When the Day's Work is Done;" "He Never told his Love;" "Dawn and Sunset;" and "Carolling," to recall some of his latest successes.

In 1875 exhausted energies compelled temporary retirement from the active practice of his profession; but in 1878 Mr. Robinson built the splendid "Great Hall Studio" at Tunbridge Wells, where he has since continued to labour with undiminished success.

No photographer has won so many tangible tokens of success as H. P. Robinson; the medals awarded to him in open competition now reaching the number of nearly one hundred. But Mr. Robinson has been almost as busy with the pen as with the lens. His books include:—

"Pictorial Effect in Photography."

"Picture-Making in Photography."

"The Studio and What to do in it;" and (in conjunction with Capt. Abney) "The Art and Practice of Silver Printing," all published by Piper & Carter, 5, Fumival St., London. The portrait has been reproduced by Messrs. Bemrose, from a photograph taken in Mr. Robinson's own studio.

LOUIS ALPHONSE POITEVIN (p. 100)—a discoverer of photographic printing in permanent pigments—was born in France, at Conflans (Department of Sarthe), in 1819. He was educated first at St. Calais, and afterwards in the Ecole Centrale of Paris, which he left in 1843 with the diploma of Civil Engineer.

From this time to 1855 he was engaged as chemist and engineer to various French companies engaged in the manufacture of salt.

Poitevin took up the study of photography while still a student in the Ecole Centrale, almost immediately after the publication of the daguerreotype process in 1839. He clearly recognised the fact that the great defect of this method is that it gives but a single picture, and he attempted to remedy this by trying to make moulds by electrically depositing copper upon the silver plate carrying the daguerrean image; continuing his experiments in this direction Poitevin discovered a method of photo-chemical engraving upon plates coated with silver or gold, for which he was awarded a silver medal by the *Société d'Encouragement des Arts*. This discovery turned out, however, of no practical importance.

Poitevin recognised the importance of gelatine in photography as early as 1850, in which year he communicated—through M. Balard—a paper on the subject to the Academy of Science. Soon after this he began to study the action of light upon bichromatized gelatine (that action being, as every one now knows, to render the gelatine insoluble), and in 1855 he patented a “helio-plastic process” by which films of bichromated gelatine are exposed to light under a negative, and then soaked in water. The parts not acted upon by light then swell up and form an image in relief, from which moulds can be taken.

In 1855 Poitevin discovered that bichromated gelatine which has been exposed to light will allow greasy ink to adhere to it, although it repels water. On this plan he based a photo-lithographic process which he commenced to work commercially in 1856; and at the perfecting of which, and its modifications, he laboured until 1869. But like most inventors of his stamp—Woodbury, Archer, etc.—Poitevin reaped a very scanty reward for his work, and the knowledge of this soured his later years.

In 1867 Poitevin was awarded the greater part of the prize of 10,000 francs offered in 1856 by the Duc de Luynes for the discovery of permanent photographic printing processes.

Poitevin died at Conflans on March 4th, 1882; as the practical founder of photo-lithography and of collotype printing, he is entitled to rank with the "fathers of photography." The illustration is the work of Messrs. Waterlow, and is from a print furnished by M. Nadar.

J. TRAILL TAYLOR (see p. 131) is of Scandinavian origin, and was born in the Orkney Islands. Educated and intended for a profession with which, from his broadness of views, he could not sympathise, he in early life adopted his father's vocation—that of a watchmaker. This he eventually forsook in favour of the press, for which, having a strong love, he had gradually been acquiring the requisite technical education, while at the same time studying optics and chemistry especially as applied to photography, then in its infancy. He at this time contributed to several newspapers and journals until, in 1864, he removed from Edinburgh to London to occupy the editorial chair of the *British Journal of Photography*, with which he had been partially connected since 1861. This position he still occupies, and has done so continuously with the exception of a six years' residence in New York, during five of which he edited the *Photographic Times* of that city.

Re-called to England soon after the death (in 1884) of his friend Henry Greenwood, the proprietor of the *British Journal of Photography*, Mr. Taylor has resumed his old position on that journal.

When residing in Edinburgh he was on terms of friendship with Fox-Talbot, with whom he experimented much, and it is now well-known that the account of the life and career of this *Savant* which ran through the latter portion of the volume of "The British" for 1864 were from the pen of its editor. It was also during his residence in Edinburgh that, in 1861, the subject of our brief sketch, partial as he was to optical pursuits, devised and submitted to the Photographic Society of Scotland a lens, the first of the nature ever constructed, by which could be produced at the will of the operator either crisp, intense definition or as much diffusion of focus (so-called) as was desired.

Mr. Taylor has been a prolific writer and experimentalist during his journalistic career. A large portion of the ninth or current edition of *Hardwick's Manual of Photographic Chemistry* was written by him in the capacity of its editor; and the well-known *British Journal Almanac* was, in its present form, created by him.

He is an honorary member of no fewer than seven Photographic Societies at home and abroad. He is President of the North London Photographic Society and also of the Photographers' Benevolent Association; a member of Council of the Photographic Society of Great Britain, and Chairman of the Council of the Photographic Convention of the United Kingdom—an association started into existence by the joint efforts of himself and Mr. J. J. Briginshaw, the Honorary Secretary.

The portrait is from a negative by Mr. John Stuart, of Glasgow, which has been reproduced by Messrs. Waterlow.

COLONEL (better known as "Major") C. RUSSELL (p. 51), was born in 1820. He belonged to the old Essex family of Branfill, but changed his name to Russell in accordance with the wishes of a deceased relative.

Major Russell commenced the practice of photography in 1856. In 1862 he published (in the *British Journal of Photography*) a "matured and practical method of alkaline development," based on the discoveries of the American workers, Borda and Anthony. In 1863 he described the Tannin process in a book of which a second edition appeared in 1865; and about the same time he discovered the restraining influence of bromide in the developer. Russell died 16th May, 1887. The portrait has been reproduced by Messrs. Waterlow, from a print by J. Thomson.

INDEX.

	PAGE		PAGE
Abney, Capt., 34, 52, 55, 73, 83, 84, 94, 111, 121, 122, 123, 134	48	Brougham, Lord.. ..	14
Ackland, W.	49	Bruce, Geo.	103
Alabastrine process	52	Burgess, J.	63, 65
Albumen-Beer process.. ..	81, 82	Burnett, J. C.	101
Albumenized paper	36, 45		
Albumen process	125	Calotype	31, 33, 45, 106, 125
Alkaline development	88	Calotype process.. ..	80, 90
Alkaline toning	98	Cardboard coated with emulsion	113, 114
Alpha paper	84	Camera obscura	10, 28, 90
Ammonia fuming	75	Canson	34, 81
Ammonia used in emulsions.. ..	82	Caranza	104
Ammonio-nitrate of silver	103	Carbonates, alkaline	126
Aniline process	126	Carbon printing	99
Anthony	23	Carbon-tissue	101
Arago	39, 41, 45, 112	Carte-de-Visites	43
Archer, F. S.	83	Census of photographers	43
Aristotype	93	Chalons-sur-Saone	15
Ashman, W. M.	17, 19	Charles, Prof.	13
Asphalt	101	Chaussier	25, 92
Autotype Co.		<i>Chemist, The</i>	39
		Chevalier	22
"Backing" for dry plates	52	Chlorine	26
Baden, M... ..	84	Clark, Latimer	86
Barnes	43	Claudet, M.	26, 35, 43
Barrault	13	Collen, H... ..	80, 82
Barr's roller-slide	107	Collodion	33, 40, 43
Beard	26, 42	Collodio-albumen process	48
Beauregard, Testud de	100	Collodio-chloride of silver	103
Bequerel, Prof.	99, 119, 121, 122	Collodion dry plates	45
Bedford, W.	84	Collodion emulsion	53
Beechey dry plates	56	Collodio-gelatine process	50
Beechey, Rev. Canon	56	Collodion process	40, 43, 45, 125
Bellini	53	Combination printing	84
Bennett, C.	71	Colours, photography in natural	116
Berkeley, H. B.	105	Coloured photographs (natural)	121
Berwick & Annan	85	Cornailles	21, 24
Bestuscheff	102	Cox (gelatine maker)	57
Bichromate of potash	59, 99	Crookes, W.	47
Bingham, R. J.	38	Croucher, J. H.	92
Bitumen	17	Cundell	79
Blanchard, V.	44, 86	Cyanide of potassium	94
Blanchard's enlarged negatives	111	Cyanotype	102
Blanquart-Evrard	34, 35, 95		
"Blue" process	102, 103	Daguerre	16, 19, 21, 27, 43, 89, 117
Boiling emulsions	73	Daguerre, Madame	22
Bolton, W. B.	54, 55, 69, 73, 132	Daguerreotype	22, 23, 35, 42, 125
Books illustrated by photographs	80	Daguerreotypes etched	27
Borda	126	Daguerreotypes, prices of	27
Boulton, M.	13	Davanne, A.	88
Boulton, M. P. W.	13	Davidson	26
Boulton & Watt	13	Davy, Sir Humphrey	14, 77, 116
Bow, R. H.	91	Dawson, Geo.	55
Breeze (of Birmingham)	44	Desprats, Abbe	51
Brewster, Sir D... ..	120	Developers. history of	125, 127
<i>British Journal of Photography</i>	42	Development	19, 25
Bromine	26	Development-printing on gelatino-bromide, 96	

	PAGE		PAGE
Dialysis	66	Harrup, Robert	10
Diamond, Dr. H. W.	39	Harrison, W. H.	59
Diorama	21	Hawthorne	27
Disderi	43	Heilmann	98
Dixon, Capt	53	Heliocromes	119
Dixon, Jos.	99	Heliography	17, 19, 20
Draper	26	Herschel, Sir John	25, 32, 35, 82, 89, 90, 92, 93, 102, 104, 117
Dry plates (collodion)	45, 48	Hill & Adamson	80
		Hillotype	122
Eastman's roller-slide	110	Hockin, J. B.	88
Eastman Co.'s paper	111	Hollingworth (paper maker)	34, 81
Edinburgh Exhibition	68	Honey process	47
Eder, Dr.	83, 104	Hopkins, J. C.	83
Eginton, Mr.	13	Horn silver	8
Emulsion	53	Hunt, Robert	82, 90, 104, 117, 118, 125
Enlarging	98	Hutinet	97
Evrard (see Blanquart-Evrard)		Hyposulphite of soda	25, 90, 92
Exhibition (First) of photographs	81		
		Instantaneous photography	33, 44, 127
Fabricius	8	Iodine	18, 24
"Fading Away"	85	Isinglass	57
Fading of photographs	87	Ivory	14
Faraday	29		
Fargier	101	Janssen	127
Fenelon	11	Jew's pitch	17
Ferrotypes	41	Johnson, A.	50
Ferrous oxalate	126	Johnson, J.	42, 66
Ferrous sulphate	125	Johnson, J. R.	101, 112
"Film" negatives	112		
Filmograph (Pumphrèy's)	113	Kennett, R.	66, 68
Fixing agents	25, 30, 91	Kew	16
Fixing by electricity	92	King, H. N.	48
Fizeau, M.	26, 87	King, J.	66
Flexible "glass"	114	Knopp	58
Flexible support	101		
Florent, St.	120	Laborde, Abbe	101
Flowers, printing with the juices of	82	Lacock Abbey	28, 30
Fontayne	98	<i>La Lumiere</i>	53
Forrest, J. A.	86	Laroche	43
Fothergill process	49	Latent image	25
Fowler, R. J.	121	Lavender, oil of	17
Fox-Talbot, H.	28, 43, 45	Lea, Carey	55, 123, 126, 131
Foxlee, E. W.	69	Leahy	126
Froedman's tissue	112	Leather	14, 30
Fry, P. W.	39	Le Gray, G.	34, 36, 38
Fry, S.	53	Leptographic printing paper	103
		Liesegang	83
Galliard	112	Lithography	16
Gallo-nitrate of silver	30	Llewelyn, J. D.	48
Gallic acid	80, 86	Luna cornea	8
Gaudin, M. A.	46, 49, 53, 54, 56, 59, 60, 61, 94, 103	Luynes, Duc de	99
Gehlen	102	Lyte (see Maxwell-Lyte)	
Gelatine	57, 62		
Gelatino-bromide paper for negatives	111	Maddox, Dr. R. L.	61, 129
Gelatino-bromide process	59, 62, 63	Magic photographs	93
Gelatino-bromide process, discovery of, 129, 132		Malone	80
Gelatino-chloride paper	98	Mansfield, Geo.	73
Gelatino-chloride of silver	83	Mawdsley, P.	69, 72, 96, 97
"Giphantie"	11	Maxwell-Lyte	47, 89
Girard	88	Mayall	48
Girod, M. A.	46	Maynard (of Boston)	88
Glaisher, J.	107	Melhuish, A. J.	51, 106
Glass plates introduced	35	Mercury	24
Goddard	26, 42	Merritt, T. C.	108
Göethe	117	Meynier, M.	94
Gordon, R. M.	52	Moist collodion process	47
Gray, Gustave Le	58, 82, 88, 92, 111	Molecular modifications	70
Grove (Sir W. R.)	27	Molecular modifications of silver bromide	123
Gum-gallic process	52	Morgan & Kidd	97
Gum guaiacum	17	Morgan, W. T.	111
Gun cotton	38	Morgan, W. T. & Co.	97
		Morse	26
Halleur, Dr.	58		
Hardwich, Rev. T. F.	48, 52, 88, 89, 92		

	PAGE		PAGE
Monekhoven, Dr.	71, 74	Rumford, Count.	10
Mudd, Jas.	48	Russell, Major C.	51, 126, 140
Muirhead, G. R.	49		
Negatives	32	Salted (plain) paper	81
Nelson (gelatine maker)	57	Sanford (paper maker)	81
New York Harbour	27	Sang, J.	50
Newton, Sir W. J.	86, 96	Sarony, O.	85
Niepece, Claude	16	Saxe (paper making town)	81
Niepece de St. Victor	86, 120, 133	Sayce, B. J.	54, 134
Niepece, Isidore	22	Sawyer, J. R.	101
Niepece, J. N.	15, 20, 22	Scheele, C. W.	9
Niepeceotype	125	Schönbein	88
Nineveh	7	Schulze, J. H.	9, 93
Norris, Dr. Hill	49, 50	Schutzenberger	93
		Seebeck, Dr.	116
Offord, R.	98	Sel d' Or	88
Ordish, Messrs.	82	Senebier	9
Organifiers	54	Senefelder	16
Oxymel process	48	Sensitizers	54, 58
		Shadbolt, Geo.	47
Palmer, Rev. H. J.	68, 111	Shaw	26
Paper, for negative making	110, 115	Silver bromide	26, 51, 59, 62, 70, 123, 126
Paper, gelatino-bromide	96, 97	Silver chloride	9, 15, 29
Paper used in photography	34	Silver nitrate	14, 29
Parma, Duke of	43	Silver sub-chloride	9
Patents	43	Simpson, G. W.	103, 121
Pellicle for dry plates	66	Smee, A.	82
"Pencil of Nature"	33, 80	Smith, W. H.	59
Petroleum	18	Society of Arts	81
Petzval, Prof. J.	42	Soho	13
Phillips, R.	92	Solar microscope	15, 29
Photogene	54	Spectrum in colours	117
Photogenic drawing	29, 77, 78	Spencer, J. B.	106
Photogeny	78	Spiller, Jno.	47
Photo-glyphy	33	Stas, J. S.	70
Photography in natural colours	16	Stebbing, E.	97
<i>Photographic News</i>	42	Stebbing's films on cardboard	113
Photographic printing processes	77	Stillman, W. J.	55
Photographic Society (London)	42	Stripping films	113
Photo-salts	123	Sub-bromide of silver	55
Platinotype	104, 105	Substratums for dry plates	48
Pliny	7	Sulphite of soda	94
Pizzighelli	105	Sulpho-cyanide of ammonia	94
Politevin	59, 100, 101, 120, 137	Sulphur toning	87
Pollock, H.	82	Sutton, Thos.	55, 60, 74, 82, 88, 95
Ponton, Mungo	99	Swan, J. W.	97, 101
Porta, Baptista	10		
Portraits first made	26	Talbot, Fox,	28, 43, 45, 77, 82, 87, 89, 100, 117
Portraiture	79	Talbotype	31, 35, 95
Positives	32, 41	Tannin	56
Pouncy, John	100	Tannin process	51
"Preservatives"	50, 54, 56	Taupenot, Dr. J. M.	47
Printing-in clouds	86	Taylor, A.	82
Printing by development	95	Taylor, Dr. A. S.	82
Pumphrey's films on cardboard	113	Taylor, J. T.	10, 121, 131, 132, 139
Pyrogallie acid	40, 51	Thiébaud's films	114
Pyroxyline	35	Thiosulphates	93
		Times (comparative) of exposure	127
Reade, Rev. J. B.	30	Tissue for negatives	112
Ready-sensitized paper	33	Toning	26, 86, 87
Red light	34	Toth, Capt.	104
Regnault, M.	99	Towson (of Liverpool)	42
Rejlander, O. G.	85	Turner (paper maker)	34
Resin process	51	"Two Ways of Life"	85
Retouching	113		
Ritter	116	Uranium, printing with salts of	102
Rives (paper making town)	81	Urie, John	
Robinson, H. P.	85, 86, 136		
Robinson, Sir John	23	Vauquelin	93
Roche, Tiphaigne de la	11, 97	Vaseline	112
Roller-slides	106, 110	Vergara, F.	113
Rogers, H.	113	Vignetting	86
Ross & Thomson	37	Vitruvius	8
Rouch, Messrs.	56	Voightlander	42

	PAGE		PAGE
Warnerke's roller-slide	109	Wiseman's roller-slide	109
Warnerke's tissue	109, 112, 113	Wolcott, A.	42
Washed collodion emulsion process ..	55	Wollaston.. . . .	17
Waterhouse	75	Woodbury, W. B.	135
Waterhouse (of Halifax)	88	Woodbury's tissue	112
Wax-paper process	110	Woodbury's stripping films ..	113
Wedgwood, T.	14, 77	Wood (photographs on)	59
Werge, J.	27	Wothlytype	102
Wilkinson, W. T.	83	Wortley, Col. Stuart	55, 72, 84, 102
Willis, W... ..	103, 105, 126	Wratten, F.	69

J. H. DALLMEYER, Optician,

Removed from 19, Bloomsbury St., to 25, Newman St., London W.

CASH PRICES of the Principal PORTRAIT & VIEW LENSES.

EXTRA RAPID (C).

2 C—For Children, $2\frac{1}{2}$ dia... $4\frac{1}{2}$ focus ..	£15 15/-
3 C— " $3\frac{1}{2}$ " .. 6 " ..	26 5/-

QUICK-ACTING (B).

	in.	distance.	
1 B—For Carte-de-Visite	2 dia..	12 ft..	£6 5/-
1 B—(Long) "	$2\frac{1}{2}$ "	14 ft..	6 15/-
2 B— " "	$2\frac{1}{2}$ "	18 ft..	12 16/-
2 B—Patent "	$2\frac{1}{2}$ "	18 ft..	18 5/-
3 B— " for Cabts. ..	$3\frac{1}{2}$ "	18 ft..	20 0/-
4 B— " and "larger }	$4\frac{1}{2}$ "	25 ft..	40 0/-

New Rapid RECTILINEAR PORTRAIT LENSES. (See descriptive Catalogue.)

ORDINARY INTENSITY (A).

1 A Patent—For Cabinets, in short rooms, dia. $2\frac{1}{2}$ in., distance 14 ft.	£13 0/-
2 A Patent—For Cabinets up to $8\frac{1}{2}$ by $6\frac{1}{2}$, dia. $3\frac{1}{2}$ in., distance 20 ft.	18 0/-
3 A Patent—For Cabinets up to 9 by 7, dia. 4 in., distance 24 ft.	27 5/-
4 A Patent—For Imperial Portraits and 10 by 8, dia. $4\frac{1}{2}$ in., focus 14 in.	38 10/-
5 A Patent—For Plates 15 by 12 and under, dia. 5 in., focus 18 in.	50 0/-
6 A Patent—For Plates 20 by 16 and under, dia. 6 in., focus 22 in.	60 0/-

PORTRAIT AND GROUP (D).

3 D Patent—Portraits $8\frac{1}{2}$ by $6\frac{1}{2}$, Views 10 by 8, dia. $2\frac{1}{2}$ in., focus $10\frac{1}{2}$ in.	£9 10/-
4 D Patent—Portraits 10 by 8, Views 12 by 10, dia. $2\frac{1}{2}$ in., focus 13 in.	13 10/-
5 D Patent—Portraits 12 by 10, Views 15 by 12, dia. $3\frac{1}{2}$ in., focus 16 in.	17 10/-
6 D Patent—Portraits 15 by 12, Views 18 by 16, dia. 4 in., focus $19\frac{1}{2}$ in.	26 10/-
7 D Patent—Portraits 18 by 16, Views 22 by 20, dia. 5 in., focus 24 in.	48 0/-
8 D Patent—Portraits 22 by 20, Views 25 by 21, dia. 6 in., focus 30 in.	58 0/-

STEREOSCOPIC LENSES.

Patent Stereographic Lens, $3\frac{1}{2}$ in. focus	£4 5/-
Ditto, with rack and pinion	4 15/-
No. 1 Quick-Acting Single Combination Landscape Lens, $4\frac{1}{2}$ in. focus	2 0/-
No. 2 Ditto, ditto, 6 in. focus	2 5/-
Rect. Stereo Lenses, 2 & $2\frac{1}{2}$ in. focus ..	4 0/-

OPTICAL LANTERN LENSES (Patent.)

Intended for use with the Optical Lantern ONLY.	
No. 1 Lens, 14 and 14 in. dia. with rack motion ..	£4 4/-
No. 2 Lens, 13 and 2 in. dia.	5 5/-
CONDENSERS, $8\frac{1}{2}$ in. dia. mounted; each.....	5 5/-
Do. 4 in. " " "	6 6/-

Dallmeyer's New "Central" Shutter.
(Patent.) See descriptive Catalogue.

RAPID RECTILINEAR (Patent).

The best Lens for general use out of doors, and for Copying.

Size of View or Landscape.	Size of Group or Portrait.	Equiv. Focus.	Price, Rigid Setting.
*4½ by 3½ in.	3½ by 3½ in.	4 in.	£3 15 0
*5 " 4 " "	4½ " 3½ " "	6 " "	4 10 0
8 " 5 " "	5 " 4 " "	8½ " "	5 10 0
8½ " 6½ " "	8 " 5 " "	11 " "	7 0 0
10 " 8 " "	8½ " 6½ " "	18 " "	9 0 0
12 " 10 " "	10 " 8 " "	16 " "	11 0 0
13 " 11 " "	French size.		17 " "
15 " 12 " "	12 " 10 " "	19½ " "	15 0 0
18 " 16 " "	15 " 12 " "	24 " "	20 0 0
22 " 20 " "	18 " 16 " "	30 " "	27 0 0
25 " 21 " "	22 " 20 " "	33 " "	32 0 0

* To be had in pairs for Stereoscopic Views.

Wide-Angle RECTILINEAR (Patent). For Architectural Views in confined Situations.

No.	Size of Plate.	Back Focus.	Equiv. Focus.	Price.
*1AA	$7\frac{1}{2}$ by $4\frac{1}{2}$	$3\frac{1}{2}$ in.	4 in.	£4 10 0
1A	$8\frac{1}{2}$ " $6\frac{1}{2}$	$4\frac{1}{2}$ " "	$5\frac{1}{2}$ " "	5 10 0
1	12 " 10	6 " "	7 " "	7 10 0
2	15 " 12	$7\frac{1}{2}$ " "	$8\frac{1}{2}$ " "	10 10 0
3	18 " 16	11 " "	13 " "	14 0 0
4	22 " 20	14 " "	$15\frac{1}{2}$ " "	20 0 0
5	25 " 21	17 " "	19 " "	30 0 0

* To be had in pairs for Stereoscopic Views.

Wide-Angle LANDSCAPE LENS. (Patent). For Landscapes pure and simple.

No.	Size of Plate.	Equivalent Focus.	Price.
1A	5 by 4	$5\frac{1}{2}$ in.	£3 5 0
1	$7\frac{1}{2}$ " $4\frac{1}{2}$	7 " "	3 15 0
2	$8\frac{1}{2}$ " $6\frac{1}{2}$	$8\frac{1}{2}$ " "	4 10 0
3	10 " 8	10 " "	5 10 0
4	12 " 10	12 " "	7 0 0
5	15 " 12	15 " "	8 10 0
5A	15 " 12	18 " "	9 10 0
6	18 " 16	18 " "	10 10 0
7	22 " 20	22 " "	14 0 0
8	25 " 21	25 " "	19 0 0

NEW RAPID LANDSCAPE LENS.

(Long Focus.) For Distant Objects and Views.

No.	Largest Dimensions of Plate.	Diameter of Lenses.	Equiv. Focus.	Price.
1	$6\frac{1}{2}$ by $4\frac{1}{2}$ in.	$1\frac{1}{8}$ in.	9 in.	£4 10 0
2	$8\frac{1}{2}$ " $6\frac{1}{2}$ "	1 " "	12 " "	5 15 0
3	10 " 8 " "	$2\frac{1}{8}$ " "	15 " "	7 10 0
4	12 " 10 " "	$2\frac{3}{8}$ " "	18 " "	9 10 0
5	15 " 12 " "	3 " "	22 " "	11 10 0
6	18 " 16 " "	$3\frac{1}{4}$ " "	25 " "	14 0 0
7	22 " 20 " "	$4\frac{1}{4}$ " "	30 " "	17 10 0

New Rectilinear Landscape Lens.

(Protection granted February 2, 1888.)

See descriptive Catalogue.

Dallmeyer "On the Choice and Use of Photographic Lenses."
Seventh Thousand. (Enlarged and with Supplement), 1s.

FULL DESCRIPTIVE CATALOGUE ON APPLICATION.

J. H. DALLMEYER, Optician,

25, NEWMAN STREET, LONDON, W.

PHOTOGRAPHIC ART ➤✠ PRINTING ✠➤

FOR EVERY DESCRIPTION OF

Book Illustration.

Typographic Blocks

FOR EVERY KIND OF

COMMERCIAL



Book ✠ Illustration.

Blocks for Surface Printing

DIRECT FROM

Negatives from Nature without Drawing.

Price Lists, Estimates, and Full Particulars on application.

WATERLOW & SONS

LIMITED,

Photographic Art Printers
and Engravers,

FINSBURY WORKS, LONDON, E.C.

G. S. MARTIN,

OPTICIAN,

and Retail Dealer in Messrs. Perken, Son & Rayment's

'OPTIMUS'

LENSES, ÷ CAMERAS, ÷ OPTICAL ÷ AND
ENLARGING ÷ LANTERNS.

Every Accessory and Chemical for Negative Making,
Transparency Making, Printing, Mounting, &c., &c.

SEND STAMP FOR LISTS TO

BIRKBECK ÷ INSTITUTION,

BREAM'S BUILDINGS, LONDON, E.C.

(Approached from Chancery Lane and Fetter Lane.)

42-Shots Revolver Camera

For Plates $3\frac{1}{4} \times 3\frac{3}{8}$ or Paper. Best Lenses only.

CONSISTS IN SOLID RECTANGULAR BOX, $8\frac{1}{2} \times 7\frac{1}{2} \times 4$.

BRICE'S PATENT.

FOR ALL INFORMATION ADDRESS—

WILLIAM A. BRICE,

Care of Goy, Limited,

54, Lime Street, LONDON.

THIS perfect apparatus, with everything always in situ, consists in a solid rectangular Box with handle, lock and key—Circular Spirit Level—View Finder, or large ground glass window for focussing and watching effects whilst exposing, both let in on top of box—Shutter, Instantaneous or Slow—No loose parts or anything separate, except Stand, if desired. Will contain and will work 42 plates, films, or papers, etc., in succession by the simplest means possible. Nothing to get out of order—No slides to draw—No doors to open—No changing bags—No box to be constantly opening.

5. Five plates can be exposed and changed almost mechanically in three minutes or less, or as slowly as desired.

Pamphlet of Instructions with each apparatus, rendering its working quite easy to understand.

FOR FULLER PARTICULARS, SEE—

1888 *Almanac, British Journal of Photography*, p. 690.

1888 *Almanac, Photographic News*, p. cxxxvii.

W. Jerome Harrison's History of Photography.

Large size eminently adapted for Studio and Professionals, as saving time and light, sitter's patience and temper. N.B.—Children. Also Assistant's time better employed.

THIS SIZE ONLY TO ORDER.

GEORGE HARE,

Photographic Apparatus Manufacturer,
26, CALTHORPE ST., GRAY'S INN RD.,
LONDON.

FOURTEEN PRIZE MEDALS have been awarded to G. HARE'S Cameras and Changing-Box for Excellence of Design and Workmanship. Silver Medal awarded at the International Inventions Exhibition, 1885.

G. HARE'S NEW CAMERA.

Invented & Introduced June, 1882. The Best & most compact Camera ever Invented



Since its introduction, this Camera has received several important modifications in construction. It stands unrivalled for elegance, lightness, and general utility. It is specially adapted for use with the Eastman-Walker Roll Holder. A $6\frac{1}{2}$ by $4\frac{3}{4}$ Camera measures when closed 8 by 8 by $2\frac{1}{2}$ in., weighs only $3\frac{3}{4}$ lbs., and extends to 17 in. The steady and increasing demand for this Camera is the best proof of its popularity.

"Little need be said of Mr. George Hare's well-known Patent Camera, except that it forms the model upon which nearly all the others in the market are based."—*Vide British Journal of Photography*, August 28, 1885.

Size of Plate.	Square, with Reversible Holder.	Brass Binding.
5 by 4	£6 0 0	£0 16 0
$6\frac{1}{2}$ by $4\frac{3}{4}$	7 2 6	0 16 0
7 by 5	7 10 0	0 16 0
$8\frac{1}{2}$ by $6\frac{1}{2}$	8 15 0	0 16 0


Size of Plate.	Square, with Reversible Holder.	Brass Binding.
10 by 8	£9 16 0	£0 18 0
12 by 10	11 0 0	1 0 0
15 by 12	13 5 0	1 0 0

These prices include one Double Slide

Since this Camera has been introduced it has been awarded **THREE SILVER MEDALS**: at Brussels International Photographic Exhibition, 1883; at the Royal Cornwall Polytechnic Society, Falmouth; and at the INTERNATIONAL INVENTIONS EXHIBITION, 1885. Also Bronze Medal, Bristol International Exhibition, 1883—HIGHEST AWARD.

G. HARE'S IMPROVED PORTABLE BELLOWS CAMERA.

Invented and Introduced 1878.



This Camera offers many advantages where a little extra weight and bulk is not objected to. It is very solid and firm in construction, and especially suited for India and other trying climates.

PRICES, with one Double Slide and Hinged Focussing Screen:—

For Plates.	Horizontal and Vertical.	Square, with Reversible Holder.	Brass Binding.
$6\frac{1}{2}$ by $4\frac{3}{4}$	£6 7 6	£7 12 6	£1 0 0
8 by $6\frac{1}{2}$	7 18 0	9 5 0	1 0 0
10 by 8	9 4 0	10 16 0	1 5 0
12 by 10	10 13 0	12 5 0	1 10 0
15 by 12	13 5 0	15 10 0	2 0 0
18 by 16	20 15 0	24 0 0	2 10 0

For Prices of Extra Dark Slides and Inner Frames, see Catalogue.

ESTABLISHED 1830.

ESTABLISHED 1830.

S. HULME,
Manufacturer of Photographic Apparatus
AND DEALER IN PHOTOGRAPHIC MATERIALS,
Exchange Buildings, New Street,
BIRMINGHAM.



TO HER MAJESTY IN SCOTLAND.

G. W. WILSON & CO.,
2, St. Swithin Street,
ABERDEEN, N.B.

Photographic Publishers & Manufacturers
of Lantern Slides and of Stereoscopic
Slides on Glass and Paper.

CATALOGUES POST-FREE ON APPLICATION.

ASK

for the New Illustrated Catalogue of Mr. LOUIS VAN
NECK'S great Manufactory of Photographic
Cameras, Enlarging Apparatus and Requisites,
KLAPDORP, 10 and 10^{bis} ANTWERP (BELGIUM),
containing all the New Processes and latest
Novelties and Discoveries in Photography
since 1880 to 1888. PRICE 1s. 6d.
LETTERS OF ENQUIRY WILL RECEIVE PROMPT ATTENTION.

A FEW OF VEVERS' SPECIALITIES.

"PRACTICAL AMATEUR PHOTOGRAPHY." 3rd thousand, enlarged to 57 pp. Photographic Frontispiece, Gummed Labels, &c. Post-free, 7d.
 IMPROVED BURNISHER. All sizes up to 15 in. Cabinet size 12/6
 PORTABLE DISTILLERY. 1 gallon size, cheap, safe and efficient 8/6
 "HOME PORTRAITURE" HEADREST, in brass, universal movements .. 6/6
 INSTANTANEOUS SHUTTER, well made, simple and reliable, 1½ in. 2/6
 NEW PRINT WASHER, double rose spray, syphon, &c. 6/6
 NEG. WASHING TANKS, with syphon, for ½ and ¼ plates, 4/6; ½ to ¼, 6/6
 LIGHT TIGHT PLATE BOXES ¼, 1/6; ½, 2/3; ¾, 3/0

Cameras, Lenses, Tripods, Camera Cases, Scales, Ruby Lamps, Cheap Backgrounds, Burner Lighting Taps, Magic Lanterns and Accessories, Retouching Desks, & sundries of every description

GOODS SUPPLIED AT 10% OFF MANUFACTURER'S LIST PRICES.

Trade Terms on application. Send for ILLUSTRATED CATALOGUE, post-free from

C. C. VEVERS, Horsforth, Leeds.

For PHOTOGRAPHIC GOODS
 and PHOTOGRAPHIC ADVICE

GO TO

J. WERGE,

PHOTOGRAPHIC STORES,


11a, Berners Street, Oxford St., London, W.

Principles and Practice of Photography, Wet and Dry, Edited and Revised by
 J. WERGE. Price, 1/-; post-free, 1/1½.

Coppin's Patent One Back

Will work any number of Plates without changing box, and can be used in the open daylight. Is less weight, is less bulk, and less cost than the ordinary common backs. Makes a day's work a pleasure with greater results. Can be fitted to all and any Camera now in existence. Send Reversing Frame to fit.

PATENTED AT HOME AND ABROAD.



Directions for Use.—When the first two plates have been exposed, insert the mouth of the Back in the empty bag and withdraw them, i.e., let the bag hang down and with the finger of the left hand press back the spring which holds the Carrier, in the back, and tilt forward. The weight of the plates will cause the Carrier to slide out and drop into the bag, fold the end of the bag over (being made longer for the purpose) and pass the attached elastic band round the double part to keep out light. To reload, place the mouth of the Back into a bag charged with fresh plates, remove elastic band and slide the Carrier into its place. Keeping the bag to remove as above

The Weight of the Back with Six Bags and Six loaded Carriers (12 half plates) is ONLY 5 lbs., as against 9 lbs., the weight of six double backs loaded in the old style.

PRICES—including 6 Bags, 6 Double Carriers, Case and Strap complete :—

¼ plate 48/- ½ plate 60/- Whole plate 77/-

Extra Carriers & Bags can be had if desired. **TERMS**—Cash, nett; 5% Disc't. for Cash with Order.

BEERNAERT AND DERWENT PLATES ALWAYS IN STOCK.

A Dark Room provided free for changing Plates.

Address: 39, WOOD STREET, CITY.

ESTABLISHED 1849.

J. F. SHEW & CO.,

Manufacturers & Patentees

OF SPECIALITIES IN

Photographic Apparatus.

Shew's Patent Eclipse Fixed Focus Hand Apparatus.

For Plates $4\frac{1}{2} \times 3\frac{1}{2}$; weight, 12 ounces. Camera and 3 Double Backs can be carried in the pocket. New Detective Case for do., with Finder, &c.

The Cyclists' Companion.

We have now completed the above, consisting of our Eclipse Apparatus in leather covered case, which can be attached to the handle bar of any tricycle by means of a special fitting with universal adjustment, enabling the operator to instantly level the camera with the tricycle, and without further preparation obtain any view or scene that he may desire. The Camera can also be removed and carried in the pocket when required.

Shew's Automatic Rocker for Developing.

Perfectly smooth and silent in action. Price with Table, 14×9 , 17/6; 28×9 , 19/6. This useful little apparatus should form part of every developing room. By its use, perfect freedom from stains is ensured where long development is necessary, or where a number of plates are required at a time.

Shew's Combination Camera
(Brown's Patent).


New Special 1888 Camera.

Shew's Model Tourist Camera

Shew's Universal Camera Clip

Shew's Automatic Magnesium
Lamp, Enlarging Lantern,
Easels, &c., &c.

Shew's Folding Plate Washer
and Drainer, invaluable for
travelling, folding flat, to hold 6
plates, $6\frac{1}{2} \times 4\frac{3}{4}$, weight $2\frac{1}{2}$ ozs.



SEE NEW CATALOGUE FOR 1888, Free on application to

J. F. SHEW & CO.,

88, NEWMAN ST. (4 doors off Oxford St.) LONDON, W.

Negatives Enlarged,

Multiplied, Reproduced, Reduced, or Reversed (for Photographers' own use).
For Printing in Silver, Carbon, Platinotype, or Gelatino-Chloride.

COPYING AND ENLARGING OF NEGATIVES

from Cartes, Glass Positives, Daguerreotypes, &c.

TRANSPARENCIES BY

JOHN HARMER, WICK, LITTLEHAMPTON.

Telegraphic Address, "HARMER, LITTLEHAMPTON." Established 1880. LIST FREE.

IRIS DIAPHRAGMS

WRAY'S PHOTOGRAPHIC LENSES are now fitted
with these when required at a small extra cost.

ILLUSTRATED PRICE LIST FREE.

ILLUSTRATED CATALOGUE of OPTICAL INSTRUMENTS for STAMP.

A MEDAL

*was awarded for WRAY'S LENSES at the DUNDEE
AND EAST OF SCOTLAND PHOTOGRAPHIC EXHIBITION,
February, 1888.*

W. Wray, Optician,

NORTH HILL, HIGHGATE, LONDON, N.

READ—IT MAY INTEREST YOU !

THE ART OF PHOTOGRAPHY is now practised by thousands of people in all parts of the world ; in fact, since the introduction of the Dry-plate Process the art has become so universal that it is adopted by every class. *Medical men* employ it for recording special cases, Architects, Surveyors, Contractors, Draughtsmen, and hundreds of others for reproduction of their work. So simple is the process now, that it may be picked up readily and in a few hours, by merely reading Newton's "**HINTS ON PHOTOGRAPHY IN PRACTICE**," free by post to all parts of the world, 4 stamps. As we are the actual Manufacturers of Photographic Apparatus, therefore we are enabled to offer liberal discounts to Chemists and Druggists who may be induced to add to their business by stocking these saleable goods. Do not fail to send for NEWTON'S ILLUSTRATED CATALOGUE of all articles connected with the art. Liberal Wholesale Terms to large buyers.

H. NEWTON & CO., 5, SOUTH JOHN STREET, LIVERPOOL.

CRYSTAL PALACE PHOTOGRAPHIC EXHIBITION, 1888.
Special Certificate of Merit awarded for

TYLAR'S PATENTED NOVELTIES.

31, YATES STREET, ASTON, BIRMINGHAM.

ARCHER CLARKE, ESQ.

"They are as near perfection as an all metal slide can be."

G. FREEMAN, ESQ., B.A.

"Very satisfactory, easily carried, wonderfully cheap and compact."

C. LACEY, ESQ.


"Much safer than wood."

A. KENNAN, DUBLIN.

"After a year's constant wear, your slides still give me perfect satisfaction."

BAYNHAM JONES, ESQ.


"Several points of great merit in your slides."



Six Double
Slides
Pack in 3
inches
space.

Perfectly Light-tight
unbreakable, easy fitted.
ANY DEALER WILL
SUPPLY.

FOLDING DEVELOPING TRAYS AND PLATE-LIFTING FRAMES.



By means of these useful articles plates can be rocked, moved from one bath to another, all without handling the plates or soiling fingers by contact with chemicals.


In sets of 4 Trays and 4 Japanned Lifters.
 $\frac{1}{4}$ plate, $\frac{1}{6}$; $\frac{1}{2}$ plate, $\frac{2}{6}$; $\frac{3}{4}$ plate, $\frac{3}{6}$.

Trays supplied up to 36×24 inches.

SILVER-PLATED LIFTING FRAMES.

For use with ordinary developing trays. Fold flat when out of use. Set of six.
 $\frac{1}{4}$ plate, $\frac{2}{6}$; $\frac{1}{2}$ plate, $\frac{5}{-}$; $\frac{3}{4}$ plate, $\frac{7}{6}$. &c., &c.

H. P. ROBINSON, ESQ. "Your plate lifting frames are the best thing I have seen in connection with photography for a long time."




RACK CLOSED.

**TYLAR'S
FOLDING
PLATE DRAINER
AND
WASHING RACK.**

The only perfect rack allowing a free current of air to circulate from all sides to the plates.

$\frac{1}{4}$ plate, $\frac{1}{6}$; $\frac{1}{2}$ plate, $\frac{2}{6}$; $\frac{3}{4}$ plate, $\frac{3}{6}$.

Send stamp for List of Novelties.
Can be had direct by enclosing remittance, or from any Dealer.



RACK OPEN.

Desideratum Lenses.

LENSES

FROM 6/6 TO £29 10/-

These Lenses are all of the finest quality, and offered at Prices that bring them within the reach of all.

Vide report of "Amateur Photographer," Jan. 6th, 1888.

	$6\frac{1}{2} \times 3\frac{1}{4}$		$6\frac{1}{2} \times 4\frac{3}{4}$		$8\frac{1}{2} \times 6\frac{1}{2}$		10×8
Rapid Rectilinear	£1 4 0	..	£1 13 0	..	£2 10 0	..	£3 0 0
Focal Length....	$4\frac{3}{4}$ in.		$7\frac{1}{2}$ in.		$10\frac{1}{2}$ in.		$13\frac{3}{4}$ in.
							12×10
Wide Angle Rectilinear	1 4 0	..	1 13 0	..	2 10 0	..	3 0 0
Focal Length....	$3\frac{1}{8}$ in.		$4\frac{3}{8}$ in.		$6\frac{1}{4}$ in.		$7\frac{1}{8}$ in.
							10×8
Portrait, rack adjustment	1 0 0	..	1 15 0	..	3 15 0	..	9 15 0
Focal Length....	$4\frac{3}{8}$ in.		$6\frac{3}{8}$ in.		$10\frac{3}{8}$ in.		$15\frac{3}{8}$ in.
							10×8
Wide Angle Landscape..	6/6	..	9/0	..	11/0	..	15/0
Focal Length....	6 in.		8 in.		11 in.		$13\frac{3}{4}$ in.

FULL DETAILED LIST OF ALL LENSES (8 PATTERNS) ON APPLICATION.

All Orders must be accompanied by Remittance, which will be returned if Lens is returned within 6 days if not approved, and in good condition. Packing free. Carriage charged. Owing to the delicate nature of Lenses, we can take no risk in transit.

In Ordering through Dealers, please state
'HOCKIN'S DESIDERATUM'
 MANUFACTURED SPECIALLY FOR

HOCKIN, WILSON & CO.,

13 to 16, New Inn Yard,
 TOTTENHAM COURT ROAD, LONDON, E.C.

Art Works for Photographers.

Life and Landscape on the Norfolk Broads. By Dr. P. H.

EMERSON and J. F. GOODALL. Illustrated with 40 platinotypes.

Edition de luxe, limited to 100 copies, £10 10 0. Ordinary edition, limited to 750 copies, £6 6 0

* This work contains an important essay on Landscape Art by the painter, J. F. Goodall.

"We feel grateful to Dr. Emerson and Mr. Goodall for a most fascinating volume,"—*Times*.

"Some of these might be reproductions in monochrome of pictures,"—*Scotsman*.

"Good wine needs no bush, and the Norfolk scenery needs no praise; but we may blamelessly sing in praise of good wine as the singing be but good, and write or photograph Norfolk meritoriously. This Messrs. Emerson and Goodall have done, and done well, for which they deserve much thanks,"—*Saturday Review*.

LONDON:—SAMPSON LOW & CO., LIMITED, ST. DUNSTON'S HOUSE, FLEET ST., E.C.

Pictures from Life in Field and Fen. By Dr. P. H. Emerson.

Being 20 plates in photogravure, reproduced from Dr. Emerson's plates by Messrs. Dawson & Co., Goupil & Co., and the Autotype Co., together with an Introductory Essay, in handsome portfolio. Edition de luxe on India paper, limited to 50 numbered copies, £5 5 0.

Ordinary edition, on fine plate paper, limited to 550 copies . . . £3 3 0.

"His composition reminds us more of paintings than of any mechanical reproductions of Nature,"—*Spectator*.

"No painter could have produced anything more charmingly true to Nature,"—*Scotsman*.

"Dr. Emerson evidently intends to form a school in photography, and has resolved to show photography at its best,"—*Photographic News*.

LONDON:—GEORGE BELL & SON, YORK STREET, COVENT GARDEN.

JUST PUBLISHED.

Idylls of the Norfolk Broads. By Dr. P. H. Emerson.

12 autogravure plates, in portfolio, with introductory text.

Edition de luxe limited to 150 numbered copies, £11 16.

Ordinary edition limited to 600 copies, £1 10.

LONDON:—THE AUTOTYPE CO., 74, NEW OXFORD STREET, W.C.

NOW READY.

Pictures of East Anglian Life. By Dr. P. H. Emerson.

Edition de luxe, limited to 75 numbered copies £7 7 0.

Ordinary edition, limited to 500 copies £5 5 0.

This work contains 32 photogravures and 15 blocks, and the text, which is contained in 26 chapters, treats of the East Anglian Fisherfolk and Peasantry.

LONDON:—SAMPSON LOW & CO., LIMITED, ST. DUNSTON'S HOUSE, FLEET ST., E.C.

IN PREPARATION.

Naturalistic Photography. By Dr. P. H. Emerson.

ABNEY & DERBY DRY PLATES.

THE ABNEY BROMO-IODIDE Extra Rapid Plate is now largely used by scientific men for Astronomical and other work at home and abroad, by Government Offices, Military School of Engineering at Chatham, &c. The price, when compared with the best plates of other Makers, is low; while for half-tones, vigour, and sensitiveness it has no superior.

THE DERBY EXTRA RAPID is strongly recommended to those who wish for a good negative at a lower price than the Abney.

THE DERBY RAPID compares most favourably with any cheap plate in the market.

Mr. W. JEROME HARRISON, Science Laboratory, Icknield Street, Birmingham, writes on September 3rd, 1887, to the Manager, Derby Dry Plate Company:—

"Dear Sir,—During August I exposed about half a gross of your Abney and Derby extra rapid brands, and I can say that they were excellent. A marked feature of both Abney and Derby plates is the ease with which they yield both density and brilliancy."

Nett Prices of the Abney and Derby Extra Rapid, and Rapid Plates.

SIZE.	DERBY RAPID.		DERBY EXTRA RAPID.		EXTRA RAPID.		All sizes, from $8\frac{1}{2} \times 6\frac{1}{2}$ upwards, may be had in half-dozen boxes. Grooved boxes supplied when ordered at a small extra charge per cost of box.
	10	per doz.	10	per doz.	10	per doz.	
$4\frac{1}{2} \times 8\frac{1}{2}$	10	23	10	3/0	10	3/6	
$6\frac{1}{2} \times 4\frac{1}{2}$	5	3/5	5	4/0	5	4/9	
$7\frac{1}{2} \times 5$	5	4/3	5	5/6	5	6/6	
$8\frac{1}{2} \times 6\frac{1}{2}$	7/3		8/9		10/0		
10 " 8	10/6		13/0		16/0		

TERMS—Cash with Order.

THE ABOVE PLATES PREPARED ONLY BY

The Derby Photographic Dry Plate Company (Limited),

WORKS AND REGISTERED OFFICE—

Lennox Lodge, 32, Queen Street, Hammersmith, London W.

IMPORTANT !!! **The "INVICTA" DEVELOPER**

(Registered) is the Cheapest, Cleanest, and most Reliable extant. No waste, and so simple that a child can use it. Sample, 9d free.

2 oz., 9d.; postage, 3d. 4 oz., 1/3; postage, 3d. 8 oz., 2/-; postage, 4½d.

Air Tight Stoppers, 2d. and 3d. Also

Pyrogalline

(Registered). An improved substitute for Pyrogallic Acid; highly recommended. 6d. and 1/-.

May be had of any respectable Dealer, or the Inventor and Sole Manufacturer—

JOHN W. JONES, 23, Lime Street, LONDON.

N.B.—See that all bottles bear my full Name and Address.

BEMROSE & SONS,

GENERAL PRINTERS AND PUBLISHERS.

.....

CHROMO - LITHOGRAPHERS, PHOTO - MECHANICAL
AND COLLOTYPE PRINTERS.

.....

Wood, Copper, and Steel Engravers.

ELECTROTYPERS & STEREOTYPERS.

.....

MANUFACTURING STATIONERS.

ACCOUNT BOOK & ENVELOPE MAKERS,

DEALERS IN DRAWING AND GENERAL OFFICE MATERIALS.

.....

DERBY { *Irongate.*
 { *Midland Place.* **LONDON** { *23, Old Bailey,*
 { *Chetwynd St.* { *E.C.*

Telegrams—BEMROSE, DERBY. BEMROSE, LONDON.

SUCCESSFUL PHOTOGRAPHERS ARE CAREFUL TO BUY PURE CHEMICALS.

HINTON AND CO., PHARMACEUTICAL AND PHOTO-
GRAPHIC CHEMISTS,
38, BEDFORD STREET, COVENT GARDEN, W.C.

Pure Chemicals—Accurately Prepared Solutions—Cameras—Lenses—Stands—Shutters—
Trays—Measures—Scales and Weights—Printing Frames—Washing Racks—Lanterns—
and all Photographic Papers and Requisites.

NOTE THE ADDRESS, AND SEND FOR A PRICE LIST.

HIGHEST AWARD. GOLD MEDAL. INVENTIONS, 1885.

ACTINOMETER, STANLEY'S PATENT,

for gauging the actinic power of light and timing exposures. One of the best and most simple in the market. Boxwood, 5/-; or Gilt, to hang to the watch chain, 7/6. Price List post-free 1 stamp

STANLEY, Photographic Apparatus Manufacturer,

13, RAILWAY APPROACH, LONDON BRIDGE, S.E.

"The Caxton of the Photographer."—*Photographic News Almanac.*

THE PHOTOGRAPHER'S INDISPENSABLE HANDBOOK

A COMPLETE CYCLOPÆDIA ON THE SUBJECT OF

Photographic Apparatus, Material, and Processes.

THE MOST USEFUL BOOK EVER PUBLISHED IN CONNECTION WITH PHOTOGRAPHY.

Every variety of Apparatus, Dry Plate, Film
and Process carefully described and illustrated.

DEMY 8vo. OVER 400 PAGES.

OVER 500 ILLUSTRATIONS.

"This book, we may say, truly deserves the title of 'Indispensable.'"—*Amateur Photographer.*

PRICE HALF-A-CROWN. Post-free 2/10½.

IN THE PRESS. WILL BE READY SHORTLY.

THE SCIENCE & PRACTICE OF PHOTOGRAPHY.

Manual dealing with all Branches
of Photography—

CHEMICAL, OPTICAL, MECHANICAL,

BY

CHAPMAN JONES.

(ROYAL SCHOOL OF MINES, SOUTH KENSINGTON.)

FULLY ILLUSTRATED. PRICE HALF-A-CROWN.

PRINTERS AND PUBLISHERS—

Iliffe & Son, 98, Fleet Street, London.

N.B.—OTHER PHOTOGRAPHIC WORKS WILL SHORTLY BE ANNOUNCED.


DISSOLVING VIEWS & APPARATUS.

CHATHAM PEXTON

(MEMBER OF THE LECTURERS' ASSOCIATION),

22, Gray's Inn Road, London W.C.

(NEAR HOLBORN.)



Dissolving View
ARTIST and
MANUFACTURER
 to the Trade,
 Clergymen, Exhibitors,
 and
 Scientific Institutions.

ESTABLISHED 1870.

TELEGRAPHIC ADDRESS:
 "DISSOLVING, LONDON."

OIL LANTERNS, with 3 and 4-wick Lamps,
from 36s.

Bi-Unial Lanterns from £6 6s.

SECOND-HAND APPARATUS & SLIDES IN GREAT VARIETY.

CATALOGUE of over 100,000 Slides post-free.

150 Designs in CHROMOTROPEs

MECHANICAL EFFECTS, LEVER SLIDES, & STATUARY.


Slides prepared from Amateurs' own Negatives, and painted,
 if desired, in three different styles.

ALL THE LATEST LIFE MODEL & OTHER SETS OF SLIDES.

SECOND-HAND AND NEW Photographic APPARATUS,


(ALL MAKES,)

*Cameras, Tripod Stands, Accessories, Rapid
Rectilinear, Symmetrical, Portrait,
and other Lenses of the Best Manufacture.*



TUITION GIVEN to
purchasers of all
Instruments.

CATALOGUES FREE.



Shipping Orders receive
immediate attention, and are shipped
within a few days of receipt.

Studios and Works:—

HOLLOWAY, N.

Central Depot:—

22, GRAY'S INN ROAD, LONDON, W.C.

All Letters to be directed to the CENTRAL DEPOT.

ALL ORDERS TO BE ACCOMPANIED BY CASH OR BANKER'S DRAFT.

Cheques to be crossed London and County Bank, or National Provincial Bank
of England. Post Office Orders to be made payable at Hatton Garden, E.C.

Thomas's

For **CHEAPNESS,**
RICHNESS OF FILM,

'Pall Mall'

BRILLIANCY,
UNIFORMITY,

Plates

NONE CAN APPROACH THEM.

Extra Rapid : } Quarter, 1/-; Half, 2/3; Whole, 4/3 { per dozen

Thickly Coated Landscape : } Quarter, 1/6; Half, 3/6; Whole, 6/6 { per dozen

PHOTOGRAPHIC OUTFITS, from 2 to 20 GUINEAS;
and all Requisites for Photography at the Depot,
10, Pall Mall, where there is a Studio for **FREE**
INSTRUCTION to all purchasers of Apparatus.

R. W. Thomas & Co., Limited,

10, PALL MALL, S.W.

FACTORY, THORNTON HEATH.

MORGAN & KIDD,

INVENTORS *of the*

Argentic Gelatino-Bromide Process,

THE STANDARD METHOD OF PRODUCING

Permanent Enlargements and Contact Prints.

ARGENTIC GELATINO-BROMIDE PAPER.

SMOOTH OR ROUGH SURFACE, for Enlarging by Daylight or Artificial Light, and also for Printing direct from the Negative by Artificial Light.

Size.	12 Sheets.	6 sheets.	Size.	12 Sheets.	6 sheets.
4½ by 3½	1s. 3d. (2 doz.)	—	15½ by 12½	7s. 0d.	4s. 0d.
6½ " 4½	1s. 3d.	—	18 " 15	9s. 6d.	5s. 3d.
8 " 5	1s. 9d.	—	23 " 17	12s. 6d.	6s. 9d.
8½ " 6½	2s. 3d.	—	25 " 21	18s. 6d.	10s. 0d.
10 " 8	3s. 0d.	—	30 " 23	24s. 6d.	12s. 6d.
12½ " 10½	4s. 6d.	3s. 0d.	30 " 25	26s. 6d.	14s. 0d.

For the most Artistic Printing the process is indispensable. The operations are very simple, and Prints are obtained in a few minutes.

WRITE FOR A SPECIMEN PRINT, FREE ON APPLICATION.

PAPER NEGATIVES.

Morgan & Kidd's Negative Paper and Patent Roller Slide.

Size.	Patent Roller Slide.	Negative Paper in rolls of 24 exp.	Negative Paper in cut sheets per doz.	Size.	Patent Roller Slide.	Negative Paper in rolls of 24 exp.	Negative Paper in cut sheets per doz.
4½ × 3½	£2 2 0	2s.	1s.	8 × 5	£3 3 0	6s.	3s.
4 " 4	£2 5 0	3s.	1s. 6d.	8½ " 6½	£3 13 6	8s.	4s.
6½ " 4½	£2 10 0	4s.	2s.	9 " 7	£3 17 6	10s.	5s.
6½ " 4½	£2 10 0	4s. 6d.	2s. 3d.	10 " 8	£4 4 0	12s.	6s.
7½ " 4½	£2 17 6	5s.	2s. 6d.	12 " 10	£5 5 0	18s.	9s.
7½ " 5	£2 17 6	5s. 6d.	2s. 9d.	15 " 12	£6 6 0	26s.	13s.

ARGENTIC GELATINO-BROMIDE ENLARGEMENTS.

Mounted on India Tint Boards.

PRICES, INCLUDING ENLARGEMENT, MOUNTING, AND SPOTTING:—

	Size of outside of Mount. (Approximate.)	Size of Print. (Approximate.)	Price.
Half Imperial	22 by 15	12 by 10	3s. 6d.
Royal	24 " 19	15 " 12	4s. 6d.
Imperial	30 " 22	18 " 15	6s. 0d.
Atlas	34 " 27	23 " 17	8s. 0d.
Double Elephant	40 " 27	24 " 20	11s. 6d.
Double Imperial	44 " 30	30 " 25	18s. 6d.

GOOD SMALL NEGATIVES may always be made to yield important pictures instead of Photographic Scraps. Portraits, and Landscape and Marine Views make most effective enlargements in this style up to almost any size without loss of quality.

Send for full Price List of "Richmond" Dry Plates, Ultra Rapid and Special Instantaneous Arg. Gel. Bromide Papers and Opal Enlarging, Finishing, and Contact Printing, Negative Paper, and Apparatus for Exposure, &c., &c.

MORGAN & KIDD, RICHMOND, S.W.


PASSINGHAM'S RETOUCHING DESK.

(PROTECTED.)


We would direct the careful attention of the Photographic Profession to this novel desk, the outcome of considerable thought, and care on the part of Mr. Edmund Passingham, the well-known Platinotype worker.



Completely Closed.



Half open, for Positive Work.



Open at full, for Negative Retouching.

The principal novel feature consists of the arrangement for lighting the negative during retouching. Instead of the usual carriers, which allow the light to stream through the whole of the negative, the slope is provided with an aperture only 3ins. x 2ins., but a swing-arm rest is arranged so that any part of the negative can be equally easily brought over the opening. The light is reflected from an adjustable mirror and subdued by passing through a finely ground glass screen. Side-light is excluded from the upper side of the negative by wings of Leatherette Cloth.

The desk is of well-finished pine, blacked, and the struts that hold it in position when opened, are of iron.

The upper flap which forms a shade over the head for retouching can be let down, when the desk will be found convenient for spotting, colouring, or working-up positives.

Price, 15/6.

PERCY LUND & CO., BRADFORD

PHOTOGRAPHIC APPARATUS

CHEMICAL COMPANY, LIMITED.

15, BARBICAN, & AUSTRALIAN AVENUE,
LONDON, E.C.

The Barbican Set Complete,

$\frac{1}{4}$ plate	£7 15 0.
$\frac{1}{2}$ plate	£10 10 0.
1-1 plate	£13 0 0.

Comprising Camera and Three Double Dark Slides with Rapid Rectilinear Lens, Velvet Focussing Cloth, and best Tripod Stand—complete in superior Leather Case with Lock and Key.

MANUFACTURERS & DEALERS

Cameras of the best workmanship and finish.

Lenses of the newest pattern and best quality. Excellence guaranteed.

Newman's Shutters, and others.

Every kind of Apparatus kept in stock.

Enlarging Lanterns.

Magic Lanterns.

Slides in great variety.

Albumenized and Ready Sensitized Papers of best quality.

The New Matt Surface Paper.

Aristotype Paper.

Solutions.

Victoria Dry Plate Developer (Registered) in one solution. Sample bottle post-free on receipt of postage, 3d.

CATALOGUES SENT BY RETURN POST-FREE ON APPLICATION.

MARION'S Photo. Supply Warehouse,

22 and 23, SOHO SQUARE, LONDON, W.

Marion's Britannia Dry Plates.

Made at their Factory, Southgate, Middlesex. Richly coated with Emulsion, rapid, and give fine vigorous negatives.

Marion's Photo. Sets for Amateurs

THE LARGEST STOCK IN THE UNITED KINGDOM. From 21/- to £50.
FREE LESSONS to purchasers in our Studio at Soho Square.

Berthon's Collapsible Studio Tent

STRONG, LIGHT, and PORTABLE. Can be fitted up in 10 minutes, and allows of Portraits being taken equal to those in permanent studios.

Berthon's Collapsible Dark Tent

VERY PORTABLE, STRONG, and LIGHT. FITTED UP IN A FEW MINUTES. FITTED WITH TABLE.

Cowan's Photo. Developing Cabinet.

Folds into a space about 3ft. x 2ft. x 1ft.

When opened out has developing sink, water tap, dark lantern, shelves and drawers for bottles, &c., and flaps which can be used as a table. Suitable for all the operations of the Dark Room.

Fixed up in Hotels and on board Passenger Ships would be a great boon to Amateurs.

Marion's Matt Surface Coaguline

PAPER. PRINTED, TONED, AND FIXED LIKE ORDINARY SENSITIZED ALBUMEN PAPER. Most artistic results are obtained on this paper.

Marion's Flash Light Apparatus.

Excellent Portraits can be made in an ordinary room, and in the evenings by means of this apparatus. Price complete, 50/-.

Marion's Practical Guide to Photography, post-free 2/9.

Burton's Practical Guide to Photo-Printing and Photo-Mechanical
Printing Processes, post-free 4/5.

The Art of Retouching, by Robert Johnson, post-free 2/3.

CATALOGUES FREE ON APPLICATION.

MARION & CO.,

22 & 23, SOHO SQUARE, LONDON, W.

but becomes more protrusion of eye

- Camera positive later on

Org of development - page 26-

then making - then brown vapors ^{clon} plate 33
page 30, 31, 32 - page 33 - album - plate 37 - collodion p 38
Camera - page 28, 29, 71, 72

Wet plate - page 30

Production of negative - Talbot page 32-33

Improvement in plate - Talbot - P. N. B. page 33

Paper negative - wet paper - 34

Waggoner in France - ^{Waggoner} Talbot in England

John Hegeler - Herschel 34 - difficulties of production plate 38
album - page 34


Collodion 38 - 39 60 Positives 41

Improvement of Collodion about 42-43 - defects 44

Process 41 - Photography on Occasion of 1841 -

Patent plates disappear 1851 - for some time - plate
long plates - then wet plates - then dry plates - process 45-
47-48 49, 50, 51

- Prints of form left on paper. Photography of plates



TR
15
H37

Harrison, William Jerome
A history of photography

~~D&A Sci.~~



PLEASE DO NOT REMOVE
CARDS OR SLIPS FROM THIS POCKET

UNIVERSITY OF TORONTO LIBRARY



